



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 30, 2020

SUBJECT: Route Various Routes
Section 12-00008-00-SW (Creston)
Ogle County
Contract No. 85675
Item 150
January 15, 2021 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices.**
- 2. Revised sheet 2 of the Plans.**
- 3. Revised the Index to the Special Provisions.**
- 4. Revised page 4 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

**VILLAGE OF CRESTON
SECTION 12-0008-00-SW
SAFE ROUTES TO SCHOOL PROJECT
TRANSIT ST. & MAIN ST. SIDEWALK IMPROVEMENTS**

INDEX OF SPECIAL PROVISIONS

ITEM	PAGE
LOCATION OF PROJECT	1
DESCRIPTION OF WORK	1
TRAFFIC CONTROL AND PROTECTION PLAN	1
SIDEWALK REMOVAL	2
PAVEMENT REMOVAL	2
TREE REMOVAL (OVER 15 UNITS DIA.)	3
LANDSCAPE RESTORATION	3
INCIDENTAL HOT MIX ASPHALT SURFACING	3
COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12	3
CONCRETE TRUCK WASHOUT	4
REMOVAL & DISPOSAL OF REGULATED SUBSTANCES	4
EARTH EXCAVATION	4
CONTRACTORS RIGHT OF ENTRY AGREEMENT	5-16
LR 107-4 INSURANCE	17
LR 702 CONSTRUCTION & MAINTENANCE SIGNS	18
LR 1030 GROWTH CURVE	19-20

VILLAGE OF CRESTON

Ogle

12-00008-00-SW

reconstructed.

This item will be paid for at the contract unit price per Foot for COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12, which shall include depressed curb, flat curb, expansion joints, curb tip-out with 2' apron behind curb, and sawed contraction joints at 10-foot intervals.

CONCRETE TRUCK WASHOUT

The Contractor shall furnish and install this item in accordance with the detail as shown in the plans. This item shall be paid for at the contract unit price Lump Sum (L SUM) for CONCRETE TRUCK WASHOUT.

REMOVAL & DISPOSAL OF REGULATED SUBSTANCES

Description: This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites: The excavated soil and groundwater within the areas listed below shall be managed as either "uncontaminated soil", hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less.

107 S. Main Street (Railroad Sample 85675-1):

Station 156+40 – Station 157+00, 50' LT to CL. The Engineer has determined this material meets and shall be managed in accordance with the criteria of Article 669.05(a)(5). COCs sampling parameter: Lead, Benzo(a)pyrene, and Mercury.

110 S. Main Street (Hueber LLC Sample 85675-3, 85675-4)

Station 154+70 – Station 156+40 50' RT to 50' LT. The Engineer has determined this material meets and shall be managed in accordance with the criteria of Article 669.05(a)(5). COCs sampling parameter: Benzo(a)pyrene.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resources Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA sites:

None

EARTH EXCAVATION

This work shall conform to Section 202 of the Standard Specifications. Excavation shall be per the cross-sections provided in the plans. Surplus materials (outside of the contaminated area defined in the CCDD report) that can not be used within the ROW shall be disposed of offsite at the contractors expense. This work shall be incidental to the contract.