

F. A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
B46	05-00047-00-CH	WILL	036	005
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT #63033

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE						
					I000	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031-F	Y080
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	45							45
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15							15
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	5							5
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3							3
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2							2
*	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	7							7
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	3							3
*	88600100	DETECTOR LOOP, TYPE I	FOOT	292							292
*	88700200	LIGHT DETECTOR	EACH	2							2
*	88700300	LIGHT DETECTOR AMPLIFIER	EACH	1							1
*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1							1
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1							1
*	89502380	REMOVE EXISTING HANDHOLE	EACH	3							3
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	7							7
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	3854	3854						
	Z0076600	TRAINEES	HOUR	500							500
*	XX003661	ELECTRIC CABLE IN CONDUIT, COAXIAL	FOOT	307							307
	XX005656	INLET FILTER CLEANING	EACH	8	8						
*	XX003070	UNINTERRUPTABLE POWER SUPPLY	EACH	1							1
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4						
	X0322584	REVTMENT MAT REMOVAL	SQ YD	212	212						
*	X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	619							619
*	X0323371	VIDEO VEHICLE DETECTION, 1 CAMERA	EACH	1							1
*	X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1							1
	X0540000	BRICK PAVERS	SQ FT	360	360						
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	454	454						
*	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1							1
*	X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FOOT	505							505
*	XX007252	ELECTRIC CABLE IN CONDUIT, NO. 16 3/C	FOOT	307							307
	Z0005215	HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SQ YD	106	106						

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

IL RTE 53 AT UNIVERSITY PARKWAY INTERSECTION IMPROVEMENT SUMMARY OF QUANTITIES

SCALE: VERT. NA
 HORIZ. NA
 DATE: 8-29-08

DRAWN BY: RG
 CHECKED BY: WD