

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHEET	NO.	10
FAP 770	116 BR - 1	Moultrie		46	19	<i>11</i> s⊦	IEETS	
FED, ROAD DIST, NO. 7		TULINDIS	S FED. AID PROJECT-					

Contract #74183

Retainer Angle Notes:

Permanent side retainers shall be provided outside the facia beams at the expansion ends of all spans. Temporary side retainers shall be provided outside the facia beams at the expansion ends of all spans at the stage construction line.

All retainers and anchor bolts are included in the cost of Precast Prestressed Concrete Deck Beams of the applicable depth.

After the Concrete Wearing Surface has been poured and cured the temporary retainer angles and anchor bolts shall be removed. Anchor bolts shall be cut off flush, ground smooth, and sealed with epoxy.

Anchor bolts shall be ASTM F1554 all-thread (or an Engineer-approved alternate material), Grade 36 of the diameter(s) specified. ASTM A307 Grade C anchor bolts may be used in lieu of ASTM F1554 Grade 36 (Fy=36 ksi). The corresponding specified grade of AASHTO M314 anchor bolts may be used in lieu of ASTM F1554.

Drilled and set anchor bolts shall be installed according to Article 521.06 of the Standard Specifications.

Retainers shall be shimmed tight until the concrete wearing is poured and cured. The shims shall then be removed from the permanent retainers and the retainers left in place.

> EXPANSION JOINT DETAILS F.A.P. 770 (IL RTE. 128) OVER TRIBUTARY TO MARROWBONE CREEK SECTION 116-BR-1 MOULTRIE COUNTY STA. 959+14.00 STRUCTURE NO. 070-0037

> > STS AECOM

111 NE Jefferson Ave. Peoria, Illinois 61602 Ph(309)676-8464 FAX(309)676-5445 IL Design Firm Reg. No. 184-001518 www.sts.aecom.com