GENERAL NOTES

- 1. Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60.
- 2. Reinforcement bars designated (E) shall be epoxy coated.
- 3. All construction joints shall be bonded..

TOTAL BILL OF MATERIAL

Item	Unit	Total
Reinforcement Bars, Epoxy Coated	Pound	8, 605
Concrete Structure	Cu. Yd.	143
Porous Granular Embankment	Cu. Yd.	53
Pipe Handrail	Foot	291.0

INDEX OF SHEETS

1. General Plan & Elevation
2. General Notes
3. Wall Facing Section Panel 1 - 7
4. Wall Facing Section Panel 8 - 13
5. Wall Detail Panel 1-3
6. Wall Detail Panel 4 - 7
7. Wall Detail Panel 8 - 10
8. Wall Detail Panel 11 -13
9. A.D.A. Ramps Detail

FILE NAME =		USER NAME = crespole	DESIGNED -	REVISED -
c:\pw_work\pwid	ot\crespole\d0330150\D48	792-sht-details.dgn	DRAWN -	REVISED -
		PLOT SCALE = 40.0000 '/ in.	CHECKED -	REVISED -
Default		PLOT DATE = 8/15/2013	DATE -	REVISED -

SCALE:

GENERAL NOTES AND DETAILS CONCRETE STRUCTURE NO. 2				F.A.S. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.						
				1380	7W-1,RS-3		Peoria	617	313						
CONGILIE STRUCTORE NO. 2										CONTRACT	NO. 8	38792			
	SHEET	2	OF	9	SHEETS	STA.	TO STA.	Ī			ILLINOIS	FED. Al	D PROJECT		