



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 8, 2025

SUBJECT: Various Routes
Section D5 ITS 2025-1
McLean County
Contract No. 70G85
Item No. 71, January 17, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions.
2. Revised page 84 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES; CONCRETE, AND MORTAR (BDE)	47
COMPENSABLE DELAY COSTS (BDE)	57
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	60
FUEL COST ADJUSTMENT (BDE)	63
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)	65
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	66
SEEDING (BDE)	67
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE)	72
SPEED DISPLAY TRAILER (BDE)	75
STEEL COST ADJUSTMENT (BDE)	76
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	79
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	79
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	80
SUBMISSION OF PAYROLL RECORDS (BDE)	80
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	81
WEEKLY DBE TRUCKING REPORTS (BDE)	82
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	82
WORKING DAYS (BDE)	84
ETHERNET SWITCH	84

- (I) Movable Traffic Barrier. The movable traffic barrier shall be on the Department's qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings. The barrier shall be capable of being moved on and off the roadway on a daily basis."

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within **75** working days.

ETHERNET SWITCH

This work shall include supplying, installing and powering ethernet switches at locations designated in the plans for the purpose of interfacing with fiber optic network(s). Programming or configuring the switch shall be done by others. The ethernet switches provided for this contract shall be of the managed type or the unmanaged type as they are noted in the plans per location.

The ethernet switches shall be managed and shall be Control RocketLinx ES8509-XT or the pre-approved equivalent.

Managed ethernet switches shall be equipped with Comtrol SFP (small form-factor pluggable) Single-Mode 10KM 1000BASE-GLX (Extended Temperature) transceivers or the pre-approved equivalent.

All fiber optic jumpers necessary to connect SFP's to the fiber optic distribution enclosure shall be included in this pay item.

This work shall be paid for per the contract unit cost EACH for ETHERNET SWITCH and shall include the work as described herein. No additional compensation will be allowed.

Revised January 8, 2025