



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 2, 2025

SUBJECT: FAS 364 (CH 13)
Section 20-00091-03-BR
Woodford County
Contract No. 89854
Item 136
January 17, 2025 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised page 2 of the Special Provision Index**
- 2. Added page 15A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

<u>Description</u>	<u>Page No.</u>
PCC Slipform Paving Aggregate Optimization	12
PCC Automatic Batching Equipment	13
Utilities – Locations/Information on Plans	13
Construction Layout Responsibility	13
Construction Layout Utilizing GPS Equipment	14
PCC Automatic Batching Equipment	14
PCC QMP Electronic Report Submittals	15
PCC Superstructure Aggregate Optimization	15
Articulated Block Revetment Mat	15A
Storm Water Pollution Prevention Plan	16
Contractor Certification Statement	23
Insurance	24
Local Quality Assurance/Quality Management QC/QA	25
Construction and Maintenance Signs	27
Status of Utilities/Utilities to be Adjusted	28
Nationwide 404 Permit – Fact Sheet No. 9 (IL)	30
IDOT Training Program Graduate On-The-Job Training	89

ARTICULATED BLOCK REVETMENT MAT

This work shall be completed in accordance with the applicable portions of Section 285 of the Standard Specifications, ASTM C42/C42M, ASTM C140/C140M, ASTM C1262/C1262M and FHWA RD-89-199. The Articulated Block Revetment Mat shall be a closed cell class and be capable of resisting a velocity of 2.57 fps at a flow rate of 2,673 cfs. with a flat surface profile.

Shop drawings shall be submitted according to Article 1042.03(b) to the Design Engineer for approval. Shop drawings will include block size, block weight (mass), mat details including block layout patterns, anticipated locations of cast-in-place concrete joints, toe in details and anchoring details. Submitted drawings shall also show details of block and geotextile installation methods. In addition to the shop drawings, the Contractor shall submit calculations or other proof that the design has been completed.

All placement of blocks shall be in accordance with the manufacturer's recommendations and the Contractor's approved shop drawings.

Any changes needed to the design or any additional cost incurred shall be the responsibility of the Contractor.