INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3-4	SUMMARY OF QUANTITIES
5-6	EXISTING AND PROPOSED TYPICAL SECTIONS
7-8	ROADWAY PLAN AND PROFILE
9	PAVEMENT MARKING PLANS
10-27	BRIDGE DECK REPAIR PLANS
28	BUTT JOINT AND HMA TAPER DETAILS
29	DETAILS FOR STEEL PLATE BEAM GUARDRAIL ADJACENT TO CURB AND GUTTER; SHOULDER WIDENING FOR TBT. TY. 1 SPL.
30	TRAFFIC CONTROL AND PROTECTION, FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
31	RAISED REFLECTIVE PAVEMENT MARKERS
32	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
33	ARTERIAL ROAD INFORMATION SIGNING

STATE STANDARDS

000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS

420401-06 BRIDGE APPROACH PAVEMENT

~~503001 CONCRETE PARAPET SLIP FORM OPTION~~

515001-02 NAME PLATE FOR BRIDGES

630001-07 STEEL PLATE BEAM GUARDRAIL

631031-06 TRAFFIC BARRIER TERMINAL, TYPE 6

701006-02 OFF ROAD OPERATIONS 2L, 2W, 4.5m (15') TO PAVEMENT EDGE FOR SPEEDS GREATER THAN OR EQUAL TO 45 MPH

701206-01 LANE CLOSURE 2L, 2W, NIGHT ONLY ON-ROAD TO 600mm (24") OFF-ROAD FOR SPEEDS GREATER THAN OR EQUAL TO 45 MPH

701321-09 LANE CLOSURE 2L, 2W BRIDGE REPAIR WITH BARRIER

701901 TRAFFIC CONTROL DEVICES

704001-04 TEMPORARY CONCRETE BARRIER

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 OR "CUAN" (CHICAGO UTILITY ALERT NETWORK) AT 312-744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC TELEPHONE AND GAS FACILITIES (48 HOURS PRIOR TO NOTIFICATION BEING REQUIRED).

10 FEET (3 METERS) TRANSITIONS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER AND MEDIAN ITEMS OF WORK TO EXISTING CURB AND GUTTERS AND MEDIANS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITION SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PORPOSED ITEMS OF WORK SPECIFIED.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITIES AND THE VILLAGE OF FRANKFORT.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE CONTRACTOR CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR CORY JUCUIS AT 847-705-4470 A MINIMUM OF 72 HOURS PRIOR TO START OF WORK.

WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1 1/2 INCHES (40 MM) WHERE THE SPEED LIMIT IS 45 MPH (80 KM/H). WITH WRITTEN APPROVAL FROM THE ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES (75 MM) MAY BE ALLOWED IF THE EDGE OF THE MACHINE SLOPED A MINIMUM 1:3 (V:H).

BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT), IN ACCORDANCE WITH THE "BUTT JOINT AND BITUMINOUS TAPER DETAILS" SHEET INCLUDED IN THE PLANS, UNLESS OTHERWISE SPECIFIED.