


SECTION THRU EXPANSION JOINT

* Furnish in segments of 20 ft. maximum length. Maximum space between installed segments shall be 3/16". Seal space with Silicone Sealant suitable for Structural Steel.

** Cut retainer bars in sidewalk or median 6" short of the sidewalk or median face.



PREFORMED JOINT SEAL

BILL OF MATERIAL

Item	Unit	Total
Preformed Joint Seal 2 1/2"	foot	66

DESIGNED	BAN
CHECKED	JOH
DRAWN	TC/TD
CHECKED	BAN

PREFORMED JOINT DETAIL
ILLINOIS ROUTE 78 OVER
MAUVAISE TERRE CREEK
F.A.P. 614 SEC. 148BR-2
MORGAN COUNTY
STATION 16+34.85
STR. NO. 069-0005

HUTCHISON ENGINEERING, INC.
JACKSONVILLE, ILLINOIS
 Rev: _____ Date: _____