



GENERAL NOTES:

1. Temporary Drainage - This work consists of furnishing and installing a 3 (75) PVC pipe in the proposed inlet to facilitate drainage off the pavement prior to the placement of bituminous surface course.
2. Adequate pavement drainage shall be maintained during all phases of construction.
3. The PVC pipe is to be filled with mortar prior to surface course placement.
4. This detail applies to all inlet types.

All dimensions are in inches (millimeters) unless otherwise noted.

01-01-97	RENUM. B-4.11, NEW REVISION BOX	T.P.
12-01-98	CORRECT GENERAL NOTE	J.A.
10-16-06	REVISED TO 2007 SPEC.	M.A.

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

TEMPORARY INLET DRAINAGE TREATMENT

NOT TO SCALE

CADD STD. 602401-D4

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	7-2 ; 6-1	HENDERSON	976	562
				CONTRACT NO. 68409
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		