
STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

PLANS FOR PROPOSED HIGHWAY

F.A.P. 330 U.S. ROUTE 12/20/45 (LAGRANGE ROAD) IL. ROUTE 171 (ARCHER AVENUE) TO NORTH OF CAL SAG CHANNEL AND ORLAND TOWNSHIP IN UNINCORPORATED COOK COUNTY **SECTION: (102 & 102X) LS** LANDSCAPING /FOREST MANAGEMENT **COOK COUNTY** C-91-227-05



SCALE: 1"=1300"

GROSS LENGTH OF PROJECT: 4,25 MILES NET LENGTH OF PROJECT: 4,25 MILES

330 (102 & 102X) LS

SECTION

D-91-227-05

TOTAL SHEET SHEETS NO.

COUNTY

соок



STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS SUBMITTED OCT. 26 20 05 Diane M. O'kegle/or DEPUTY DIRECTOR OF HIGHWAYS, REGION ENGINEER December 9, 20 05 Muke time & ENGINEER OF DESIGN AND ENVIRONMENT December 9, 20 05 Price HOLLED
DEPUTY DIRECTOR OF HIGHWAYS, CHIEF ENGINEER

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

INDEX OF SHEETS


- TITLE SHEET LOCATION MAPS INDEX OF SHEETS HIGHWAY STANDARDS
- 2 SUMMARY OF QUANTITIES
- SCHEDULE OF LANDSCAPE ITEMS
- CALENDAR OF LANDSCAPE CONSTRUCTION AND **ESTABLISHMENT WORK**
- 5--9 LANDSCAPING PLANS U.S. 12/20/45 (LA GRANGE ROAD)
- RAMP F LANDSCAPE PLAN
- 11 TREE MITIGATION PLAN SCHEDULE OF QUANTITIES (TREE MITIGATION SITE ONLY)
- 12 FPDCC DEVELOPMENT PLAN TREE GROUPING KEY A

13--14 TREE GROUPING KEYS B - E

LIST OF IDOT HIGHWAY STANDARDS

701001-01 702001-05 701101-01 701006-01 701106 - Ol 701311-02 701426-02

IMPROVEMENT IS LOCATED IN THE VILLAGE OF WILLOW SPRINGS AND UNINCORPORATED COOK COUNTY



ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123

CONTRACT NO. 62969

c:βprojectsβcvrshtsβe_cover.dgn

 F.A RTE.	SECTION		COUN	ΤY	TOTAL SHEETS	SHEET NO.
330_	(1Q2_&_1Q2_X)		COOK		14	2_
FED.	ROAD DIST. NO. 1	ILL	INOIS	HIG	HWAY PRO	JECT
D-91	-227-05					

	SUMMARY OF QUANTITIES			ļ		T	TION TYPE	T	· · · · · · · · · · · · · · · · · · ·
			TOTAL.	URBAN				<u> </u>	
CODE NO	ITEM	UNIT	QUANTITIES	100% STATE					
				Y003					
0101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5	-				
5000400	NITROGEN FERTILIZER NUTRIENT	POUND	155	155					
5000750	MOWING	ACRE	24	24					
5200200	SUPPLEMENTAL WATERING	UNIT	60	60					
7100100	MOBILIZATION	L SUM	1	1				:	
2002516	TREE, CARPINUS CAROLINIANA (AMERICAN HORNBEAM), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	3					-
2006712	TREE, QUERCUS MACROCARPA (BUR OAK), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	14	14					
2007114	TREE, QUERCUS RUBRA (RED OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	14	14					
2016614	TREE, QUERCUS ELLIPSOIDALIS (HILL'S OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	14.	14					
2000562	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 4' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	50	- 50					
2001164	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 5' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	8	8					
2000524	SHRUB, ARONIA MELANOCARPA (BLACK CHOKE BERRY), 2' HEIGHT, BALLED AND BURLAPPED	EACH	50	50				-	
2001124	SHRUB, CEPHALANTHUS OCCIDENTALIS (BUTTON BUSH), 2' HEIGHT, BALLED AND BURLAPPED	EACH	10	10					
2002024	SHRUB, CORYLUS AMERICANA (AMERICAN FILBERT), 2' HEIGHT, BALLED AND BURLAPPED	EACH	490	490					
2003348	SHRUB, HAMAMELIS VIRGINIANA (COMMON WITCHHAZEL), 4' HEIGHT, BALLED AND BURLAPPED	EACH	50	50					
2006024	SHRUB, RHUS TYPHINA (STAGHORN SUMAC), 2' HEIGHT, CONTAINER	EACH	20	20					
2C09418	SHRUB, SALIX HUMILIS (PRAIRIE WILLOW), 18" HEIGHT, CONTAINER	EACH	150	150					
2009624	SHRUB, SAMBUCUS CANADENSIS (AMERICAN ELDER), 2' HEIGHT, CONTAINER	EACH	75	75					
2001560	EVERGREEN, JUNIPERUS VIRGINIANA (EASTERN RED CEDAR), 5' HEIGHT, BALLED AND BURLAPPED	EACH	48	48					

						CONSTRUCT	ION TYPE O	ODE.		
	SUMMARY OF QUANTITIES		-	LIRBAN		CONSTRUCT	ION THE	.002		ŀ
0005 110	7771	UNIT	TOTAL QUANTITIES	100/.STATE	:					
CODE NO	ITEM	UNII	QUANTITIES	Y003						
										
D2003848	EVERGREEN, THUJA OCCIDENTALIS TECHNY (TECHNY ARBORVITAE), 4' HEIGHT, BALLED AND BURLAPPED	EACH	67	67				i		
X0322856	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL	GALLON	2. 5	2. 5				-		
X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	160	160						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1						
Z0064800	SELECTIVE CLEARING	UNIT	103. 9	103. 9						
A2C02663	TREE, CELTIS OCCIDENTALIS (HACKBERRY), CONTAINER GROWN, 3 - GALLON	EACH	70	70						
A2C03563	TREE, JUGLANS NIGRA (BLACK WALNUT), CONTRINER GROWN, 3 - GRLLON	EACH	70	70				-		
A2004163	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), CONTAINER GROUN, 3 - GRULOH	EACH	140	140						
A2C04963	TREE, QUERCUS ALBA (WHITE OAK), CONTAINER GROWN, 3- GALLON	EACH	180	180						
A1C05263	TREE, QUERCUS ELLIPSOIDALIS (HILL'S OAK), CONTAINER GROWN, 3 - GALLON	EACH	40	40						
AJ(05363	TREE, QUERCUS IMBRICARIA (SHINGLE OAK), CONTAINER GROWN, 3-6A440N	EACH	120	120						
A2C05663	TREE, QUERCUS MACROCARPA (BUR OAK), GONTAINER GROWN, 3 - GALLON	EACH	450	450		-	-			
A2C06163	TREE, QUERCUS RUBRA (RED OAK), CONTAINER GROWN, 3 - GALLON	EACH	190	190						
 A2C07263	TREE, TILIA AMERICANA (AMERICAN LINDEN), CONTAINER GROWN, 3-GALLON	EACH	140	140				,		
							-			
	-									

	REVISION	s i	ILL
	NAME	DATE	SL
Rev.			

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
U.S. RTE. 12/24/45
(LA GRANGE ROAD)

SCHEDULE OF LANDSCAPE ITEMS										
ITEM	UNIT	TOTAL	SHEE [*]	6	7	8	9	10	11	
SHADE TREES Carpinus caroliniana (American Hornbeam), 2" Caliper, Balled & Burlapped	EACH	3		3						
Celtis occidentalis (Hackberry), Container Grown, 3-Gallon	EACH	70							70	
Juglans nigra (Black Walnut), Container Grown, 3-Gallon	EACH	70							70	
Ostrya virginiana (American Hophornbeam), Container Grown, 3-Gallon	EACH	140					60		80	
Quercus alba (White Oak), Container Grown, 3-Gallon	EACH	270				50	50		170	
Quercus ellipsoidalis (Hill's Oak), 1-3/4" Caliper, Balled & Burlapped	EACH	14	:					14		
Quercus ellipsoidalis (Hill's Oak), Container Grown, 3-Gallon	EACH	40							40	
Quercus imbricaria (Shingle Oak), Container Grown, 3-Gallon	EACH	120					60		60	
Quercus macrocarpa (Bur Oak),1-1/2" Caliper, Balled & Burlapped	EACH	14						14	040	
Quercus macrocarpa (Bur Oak), Container Grown, 3-Gallon	EACH	360					50	44	310	
Quercus rubra (Red Oak), 1-3/4" Caliper, Balled & Burlapped	EACH	14	-			50	50	14	90	
Quercus rubra (Red Oak), Container Grown, 3-Gallon	EACH	190				50	30		90	
Tilia americana (American Linden), Container Grown, 3-Gallon	EACH	140				50			90	
INTERMEDIATE TREES Amelanchier canadensis (Shadblow Serviceberry), 4' Height, Shrub Form, B & B	EACH	50					50			
Cercis canadensis (Eastern Redbud), 5' Height, Clump Form, Balled & Burlapped	EACH	8	8							
SHRUBS Aronia melanocarpa (Black Chokeberry), 2' Height, Balled & Burlapped	EACH	50						50		
Cephalanthus occidentalis (Buttonbush), 2' Height, Balled & Burlapped	EACH	10		10						
Corylus americana (American Filbert), 2' Height, Balled & Burlapped	EACH	490	200			200		90		
Hamamelis virginiana (Common Witchhazel), 2' Height, Balled & Burlapped	EACH	50					50			
Rhus typhina (Staghorn Sumac), 2' Height, Container	EACH	20		20						
Salix humilis (Prairie Willow), 18" Height, Container	EACH	150						150		
Sambucas canadensis (American Elder), 2' Height, Container	EACH	75						75		
EVERGREENS Juniperus virginiana (Eastern Red Cedar), 5' Height, Balled & Burlapped	EACH	48						48		
Thuja occidentalis Techny (Techny Arborvitae), 4' Height, Balled & Burlapped	EACH	67						67		
OTHER Spleeting Clearing	UNIT	103.9	3.9		7.5	25	67.5			
Selective Clearing	UNIT	103.9	3.9		1.5	2.0	01.0			

F. A. RYE.	SECTION	COUNTY	TOTAL	SHEET
330	102&102X) LS	соок	14	3
STA.		TO STA.		-

FED. ROAD DIST. NO 7 ILLINOIS FED AID PROJECT

D-91-227-05

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

VILLAGE WATER, SEWER MAINS AND OTHER UTILITIES MAY BE LOCATED IN THE LANDSCAPE AREA. THE ACTUAL LOCATION OF PROPOSED LANDSCAPING WILL BE ADJUSTED IN THE FIELD TO AVOID UTILITIES. THE VILLAGE OF WILLOW SPRINGS AND THE FOREST PRESERVE DISTRICT OF COOK COUNTY ARE NOT PART OF "JULLIE." THE CONTRACTOR SHALL CONTACT THE RESPECTIVE VILLAGES TO LOCATE THEIR UTILITIES.

THE CONTRACTOR WILL NOT BE ALLOWED TO PROCEED WITH ANY PLANTING WORK UNTIL ALL UTILITY OWNERS FIELD LOCATE THEIR FACILITIES WHICH MAY INTERFERE WITH LANDSCAPING OPERATIONS

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY OR FOREST PRESERVE HOLDINGS WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT OR THE FOREST PRESERVE DISTRICT OF COOK COUNTY.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4155 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

UNDERBRUSH OR DEBRIS AT PLANTING LOCATIONS SHALL BE REMOVED AND DISPOSED OF IN ACCORDANCE WITH SECTION 201 OF THE STANDARD SPECIFICATIONS. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT THE COSTS SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT UNIT PRICES FOR THE CONSTRUCTION ITEMS INVOLVED, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE CONTRACTOR SHALL PROTECT ALL EXISTING PLANT MATERIAL FROM DAMAGE FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF EXISTING PLANT MATERIAL AND THE REPAIR OR REPLACEMENT OF EXISTING PLANT MATERIAL DAMAGED BY THE CONTRACTOR SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 201 OF THE STANDARD SPECIFICATIONS UNLESS OTHERWISE NOTED.

THE CONTRACTOR SHALL ORDER ALL CONTAINER TREES IMMEDIATELY FOLLOWING EXECUTION OF THE CONTRACT TO ASSURE AVAILABILITY OF THE PLANT MATERIAL FOR SPRING PLANTING.

THE RESIDENT ENGINEER IN COORDINATION WITH THE DISTRICT LANDSCAPE ARCHITECT WILL STAKE ALL TREE PLANTINGS AT THE TREE MITIGATION SITE. UNLESS OTHERWISE NOTIFIED, THE CONTRACTOR SHALL PROVIDE AN ADEQUATE NUMBER OF LATHES SEVERAL WEEKS PRIOR TO THE SCHEDULED TREE PLANTING.

WHERE MULCH BEDS ARE SPECIFIED, ALL EXISTING GRASS, WEEDS, AND DEBRIS ARE TO BE REMOVED AND THE BEDS TILLED TO A DEPTH OF 6 INCHES PRIOR TO PLACING PROPOSED PLANTS. FOLLOWING PLANTING, BEDS SHALL BE MULCHED TO A DEPTH OF 4 INCHES. THIS WORK WILL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR THE PLANTING ITEMS.

SCHEDULE OF LANDSCAPE
ITEMS

GENERAL NOTES

SCALE: VERT. DRAWN BY
DATE

DATE

OTHER CHECKED BY

SYE.	SECTION	COUNT	Υ .	SHEETS	SHEET NO
330	(102&102X)LS	coo	Κ .	14	4
STA.		TO STA			
FED. N	OAD DIST NO 7	SULINOIS	gen	ALD OBOU	

CALENDAR OF CONSTRUCTION AND ESTABLISHMENT WORK

	YEAR	WORK D	ATES TO	TREE MITIG	ATION SITE	CORRID	OR SITE
	2005- 2006	Prior to	start of ork	Layout of mowing areas by ID0	OT and others		·
				Mowing designated areas by c			
				Layout of tree planting location	ns by IDOT and others		
Phase I	YEAR	WORK D	ATES TO	CONSTRUCTION WORK	ESTABLISHMENT WORK	CONSTRUCTION WORK	ESTABLISHMENT WORK
	2006	TROM	March 15			Selective Clearing	
		Thawed Soil	Apr. 1	Period of establishment plant care required for woody plants.*		Period of establishment plant care required for woody plants.*	
		Thawed Soil	Apr.15	Finish installation of all container trees by April 15 . Apply Pre-emergent Granular Herbicide.	1) Supplemental Watering of woody plants if required by Engineer. 2) Weed spray of non-selective, non-residual herbicide around planted trees if required by Engineer.	Finish installation of all container trees by April 15 . Apply Pre-emergent Granular Herbicide.	1) Supplemental Watering of woody plants if required by Engineer. 2) Weed spray of non-selective, non-residual herbicide around planted trees if required by Engineer
		Apr. 1	Apr. 15	Period of establishment plant care required for woody plants.*		Period of establishment plant care required for woody plants.*	
		Арі	ril 17	Certification to the Bureau of Mand eligible for a May 15, 200	Maintenance that all container 6 period of establishment inspe	trees have been installed and ection.	are in a live healthy condition
		Thawed Soil	Apr. 30			Install evergreens.	
		Apr. 15	Apr. 30			Period of establishment plant care required for woody plants.*	
J		May 1	May 15			Period of establishment plant care required for woody plants.*	
		May 15	May 31	Installation of all required replacement container trees and all required clean up shall be completed by this date. Apply Pre-Emergent Granular Herbicide.		1) Installation of all required replacement container trees and all required clean up shal be completed by this date. Apply Pre-Emergent Granular Herbicide. 2) Period of establishment plant care required for woody plants.*	
Phase I		Thawed Soil	May 31			Finish installation of all woody plants by May 15. Apply Pre-Emergent Granular Herbicide.	

se II		WORK	DATES	TREE MITICATION SITE	CORRIDOR SITE
	YEAR	FROM	ТО	TREE MITIGATION SITE	CONNIDOR SITE
	2006	Jui	ne 1		Certification to the Bureau of Maintenance that all woody plants have been installed and are in a live healthy condition and eligible for a September 2006 period of establishment inspection.
		June 1	June 15		Period of establishment plant care required for woody plants.*
		June 15	June 30		Period of establishment plant care required for woody plants.*
		July 1	July 15		Period of establishment plant care required for woody plants.*
		July 15	July 31		Period of establishment plant care required for woody plants.*
		Aug. 1	Aug. 15		Period of establishment plant care required for woody plants.*
		Aug. 15	Aug. 31		Period of establishment plant care required for woody plants.*
		Sept. 1	Sept. 15		Period of establishment plant care required for woody plants.*
se II		Sept. 15	Sept. 30		Period of establishment plant care required for woody plants.*

Phase III	YEAR		DATES	CONSTRUCTION WORK	ESTABLISHMENT WORK	CONSTRUCTION WORK	ESTABLISHMENT WORK
	2007	Thawed Soil	May 15			Installation of all required replacement woody plants, and all required clean up of woody plants shall be completed by this date.	Apply Pre-Emergent Granular Herbicide to all woody plants.
		May 15	May 31				Mow turf areas to a turf height
Phase III							of 3 inches.

^{*} Weeding, watering and other work which is necessary to maintain health and satisfactory appearance of the planting is included in the cost of the contract.


ILLINOIS DEPARTMENT OF TRANSPORTATION

CALENDAR OF CONSTRUCTION AND ESTABLISHMENT WORK REVISIONS ... DATE

SCALE: VERT. HORIZ.


DRAWN BY

CHECKED BY




STA.	140+00	, ·	TO STA.	165+00	
330	(102 & 102)	() LS	COOK	14	6
FAP RTE.	SECTION		COUNTY	TOTAL	SHEE










ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT NO. 1 SCHAUMBURG

> LANDSCAPING PLAN U.S. ROUTE 45


SCALE AS SHOWN
DATE OCT 25, 2005

DRAWN BY BSB CHECKED BY CES



330	(102		5+00	LS	COOK TO STA.	210+00	8
_		_	102X)		2221	14	
FAP RTÉ.		SE	CT10N		COUNTY	TOTAL SHEETS	SHEE





ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

LANDSCAPING PLAN U.S. ROUTE 45


SCALE AS SHOWN
DATE OCT 25, 2005

SCALE IN FEET

DRAWN BY BSB
CHECKED BY CES

STA.		2	10+00		TO STA.	223+00	
330	(102	&	102X)	LS	COOK	14	9
FAP RIS.		SE	CTION		COUNTY	TOTAL SHEETS	SHEET






ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT NO. 1 SCHAUMBURG

LANDSCAPING PLAN
U.S. ROUTE 45


SCALE AS SHOWN
DATE OCT 25, 2005

SCALE IN FEET

DRAWN BY BSB
CHECKED BY CES



F. A. SECTION		COUNTY		TOTAL SHEETS	SHEE
330	(102&102X)LS	соок	T	14	11
STA.		TO STA.			
FED. RC	AD DIST NO 7	ILLINOIS	FEO	AID PROJ	ЕСТ



ITEM	HABITAT	GROUP	QUANTITY OF GROUPS	QUANTITY PER GROUP	UNIT	TOTAL
Celtis occidentalis (Hackberry), CONTAINE R. GROWN, 3 GALLON	LOWLAND MESIC	D	7	10	EACH	70
Juglans nigra (Black Walnut), CONTAINER GROWN, 3 GALLON	LOWLAND MESIC	D	7	10	EACH	70
Ostrya virginiana (American Hophornbeam),CoมTA มมศ GRown, 3GAL	UPLAND MESIC	В	8	10	EACH	80
Quercus alba (White Oak), CONTAINER GROWN, 3 GALLON	UPLAND MESIC UPLAND MESIC	B C	8 9	10	EACH	80
Quercus imbricaria (Shingle Oak), CONTAINER GROWN, 3 GALLON	LOWLAND WET	E	6	10	EACH	90 60
Quercus ellipsoidalis (Hill's Oak), CONTAINER GROWN, 3 GALLON	UPLAND DRY	A	4	10	EACH	40
Quercus macrocarpa (Bur Oak), CONTAINER GROWN, 3 GALLON	UPLAND DRY	А	4	10	EACH	40
	UPLAND MESIC	В	8	10		80
	LOWLAND MESIC LOWLAND WET	D E	6	10 20		70 120
Quercus rubra (Red Oak), CONTAINER GROWN, 3 GALLON	UPLAND MESIC	С	9	10	EACH	90
Filia americana (American Linden), CONTAINER GROWN, 3 GALLON	UPLAND MESIC	С	9	10	EACH	90
		·		TOTAL	EACH	980

ILLINOIS DEPARTMENT OF TRANSPORTATION


TREE MITIGATION PLAN

REVISIONS NAME DATE SCHEDULE OF QUANTITIES (TREE MITIGATION SITE)

SCALE: VERT.

DRAWN BY CHECKED BY

F. A. RTE.	SECTION	COUNTY	TOTAL	SHEET
330	(102&102X)LS	COOK	14	12
STA.		TO STA.		




FOREST PRESERVE DISTRICT OF **COOK COUNTY**

ORLAND TRACT DEVELOPMENT PLAN



GENERAL AREA OF REFORESTATION



A - UPLAND DRY **BUR/HILLS OAK**


+ Quercus macrocarpa (Bur Oak) 10 Each

× Quercus ellipsoidalis (Hills Oak) 10 Each

Total 20 Each

REVISIO	ONS	FPDCC DEVELOPMENT PLAN			
NAME	DATE	LLAN			
		TREE GROUPIN	IG KEY A		
		SCALE: VERT.	DRAWN BY		
		1	CHECKED BY		

F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET
330	(102&102X)LS	соок	14	13
STA.		TO STA.		



B – UPLAND MESIC

WHITE/BUR OAK

× Quercus alba (White Oak)


10 Each

+ Quercus macrocarpa (Bur Oak)

10 Each

o Ostrya virginiana (Hophornbeam) 10 Each

Total 30 Each



C - UPLAND MESIC

RED/WHITE OAK

+ Quercus rubra (Red Oak)

10 Each

× Quercus alba (White Oak)

10 Each

• Tilia americana (American Linden) 10 Each

Total 30 Each


ILLINOIS DEPARTMENT OF TRANSPORTATION TREE GROUPING

REVISIONS SCALE: VERT. HORIZ.

KEYS B&C

DRAWN BY CHECKED BY

F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET
330	(102&102X)LS	COOK		14
STA.		TO STA		



D – LOWLAND MESIC WALNUT-HACKBERRY-BUR OAK

10 Each


Juglans nigra (Black Walnut)Celtis occidentalis (Common Hackberry)

10 Each

+ Quercus macrocarpa (Bur Oak)

10 Each

Total 30 Each



E - LOWLAND WET **BUR/SHINGLE OAK**

+ Quercus macrocarpa (Bur Oak)

20 Each

• Quercus imbricaria (Shingle Oak)

<u>10 Each</u>

Total 30 Each

			ILLINOIS DE	PARTMENT OF TRANSPORTATION
i	REVISIO	NS	TDEE	CDOUDING
	NAME	DATE	1	GROUPING
			KEYS	D&E
	-			
			SCALE: VERT. HORIZ.	DRAWN BY
			DATE	CHECKED BY