
STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

ILLINOIS CONTRACT NO. 72881

D-96-036-22



INDEX OF SHEETS


- **COVER SHEET**
- 2 **GENERAL NOTES AND COMMITMENTS**
- 3 **SUMMARY OF QUANTITIES**
- SCHEDULES OF QUANTITIES
- 5 TYPICAL SECTIONS
- STAGING PLAN 6
- STRUCTURE PLANS 7-12


PROPOSED HIGHWAY PLANS

FAP ROUTE 510 (IL 96) SECTION (119BR) BRR, BJR, I BRIDGE JOINT REPLACEMENT HANCOCK COUNTY

C-96-044-22

EXISTING SN 034-0054 SINGLE SPAN 67'-8" BK-BK ABUTMENTS 33" P.P.C DECK BEAMS ON REINFORCED CONCRETE CLOSED ABUTMENTS OVER TYSON CREEK





AUGUST 31 20 23

NOVEMBER 30 20 23

PROJECT MANAGER: CONSULTANT 217-782-6990

ENGINEERING SCALES, REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS

ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION

GROSS LENGTH = 22 FT. = 0.004 MILE NET LENGTH = 22 FT. = 0.004 MILE



PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUBMITTED September

December 9, 202

PROJECT ENGINEER: BRIAN LANINGHAM 217-782-6990

CONTRACT NO. 72881

1-800-892-0123

 \circ

GENERAL NOTES

- 1. ALL SAW CUTS NECESSARY TO COMPLETE THE WORK DETAILED IN THESE PLANS SHALL BE INCLUDED IN THE COST FOR THE VARIOUS PAY ITEMS INVOLVED
- THE CONTRACTOR SHALL SUBMIT A SEQUENCE OF CONSTRUCTION FOR APPROVAL TO THE RESIDENT ENGINEER BEFORE THIS PROJECT IS STARTED.
- 3. IDOT DISTRICT 6 OPERATIONS TRAFFIC SIGNAL SECTION SHALL BE CONTACTED AT (217) 785-5306 FOR CONTROLLER PROGRAMMING AND TIMING APPROVAL PRIOR TO ACTIVATING THE TEMPORARY BRIDGE TRAFFIC SIGNALS.

LIST OF STANDARDS

| 000001-08 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
|-----------|---|
| 001001-02 | AREAS OF REINFORCEMENT BARS |
| 001006 | DECIMAL OF AN INCH AND OF A FOOT |
| 420001-10 | PAVEMENT JOINTS |
| 701001-02 | OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 M) AWAY |
| 701006-05 | OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 M) TO 24" (600 MM) FROM PAVEMENT EDGE |
| 701301-04 | LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS |
| 701316-13 | LANE CLOSURE, 2L, 2W, BRIDGE REPAIR, FOR SPEEDS ≥45 MPH |
| 701901-08 | TRAFFIC CONTROL DEVICES |
| 780001-05 | TYPICAL PAVEMENT MARKINGS |
| | |

COMMITMENTS

THERE ARE NO COMMITMENTS.

| | MENT OF TRANSPO VISION OF HIGHWA DISTRICT 6 | |
|----------|---|-----------------|
| EXAMINED | July 12 | 20 22 |
| | ENGINE | R OF OPERATIONS |
| EXAMINED | August 1 L Z Z | |
| | ENGINEER OF PROJECT | IMPLEMENTATION |
| EXAMINED | August 22 | 20 22 |
| | PA Madre | م |

STATE OF ILLINOIS

REV. - MS

| - | | |
|------|--|------|
| 1:12 | KUHN & TRELLO | USER |
| AME | CONSULTING ENGINEERS A Limited Liability Company | |
| Z | 10g N. 7th Street, 3rd Floor Springfield, IL 62701 Phone: 217-679-0044 | PLOT |
| E | Phone: 217-679-0044 Professional Design Firm No. 184-006516 | PLOT |

| USER NAME = myoung | DESIGNED JS | REVISED - |
|--------------------------|-------------------|-----------|
| | DRAWN - MMY | REVISED - |
| PLOT SCALE = 2.000 / in. | CHECKED JS | REVISED - |
| PLOT DATE = 8/30/2022 | DATE - 04/21/2022 | REVISED + |

SCALE:

TO STA.

ENGINEER OF PROGRAM DEVELOPMENT

| | · | | | 100% STATE |
|----------|---|--------|----------|-------------|
| | | | | BRIDGE |
| CODE | | | TOTAL | 0047 |
| NO. | ITEM | UNIT | QUANTITY | SN 034-0054 |
| | | | | |
| 50102400 | CONCRETE REMOVAL | CU YD | 2.7 | 2.7 |
| | | | | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 2.6 | 2.6 |
| | | | | |
| 50300300 | PROTECTIVE COAT | SQ YD | 8 | 8 |
| | | | | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 410 | 410 |
| | | | | |
| 50800515 | BAR SPLICERS | EACH | 7 | 7 |
| | | | | |
| 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 39 | 39 |
| | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| | | | 1 | |
| 70100100 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701316 | EACH | 1 | 1 |
| | | | 2: | |
| 70106500 | TEMPORARY BRIDGE TRAFFIC SIGNALS | EACH | 1 | 1 |
| | | | | |
| 70106700 | TEMPORARY RUMBLE STRIPS | EACH | 6 | 6 |
| - | | | | |
| 70107025 | CHANGEABLE MESSAGE SIGN | CAL DA | 30 | 30 |
| | | | i i | |
| 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 48 | 48 |
| | | | 11 | |
| 70300150 | SHORT TERM PAVEMENT MARKING REMOVAL | SQ FT | 16 | 16 |
| | | | | |
| 78001120 | PAINT PAVEMENT MARKING = LINE 5" | FOOT | 394 | 394 |
| | | | | |

* SPECIALTY ITEM

| 1046,030 IboT D6 | | | |
|--|--------------------------|-----------------|-----------|
| KUHN & TRELLO | USER NAME = myoung | DESIGNED JS | REVISED = |
| CONSULTING ENGINEERS A Limited Liability Company | | DRAWN - MMY | REVISED - |
| 109 N. 7th Street, 3rd Floor Springfield, IL 62701 Phone: 217-679-0044 | PLOT SCALE = 2.000 / in. | CHECKED JS | REVISED - |
| Phone: 217-679-0044 Professional Design Firm No. 184-006516 | PLOT DATE = 8/30/2022 | DATE 04/21/2022 | REVISED 4 |

| STATE OF | ILLINOIS |
|-----------------|---------------|
| DEPARTMENT OF T | RANSPORTATION |

SCALE:

6-00634-0000

| | | | | | | | F.A.P. RTE. | SECTION | | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------------------|-------|---|------|--------|------------------|---------|----------------|----------|--------|-----------|-----------------|--------------|
| SUMMARY OF QUANTITIES | | | | 510 | (119BR) BRR, BJR | , I | HANCOCK | 12 | 3 | | | |
| | | | | | | | | | | CONTRACT | NO. 72 | 2881 |
| | SHEET | 1 | OF 1 | SHEETS | STA. | TO STA. | | ILLINOIS | FED. A | D PROJECT | | |

| | | | | 6-00634-0000 |
|----------|-------------------------------------|-------|----------|--------------|
| | | | | |
| ¥ | | | | 100% STATE |
| | | | | BR I DGE |
| CODE | | | TOTAL | 0047 |
| NO. | ITEM | UNIT | QUANTITY | SN 034-0054 |
| | | | | |
| 78300201 | PAVEMENT MARKING REMOVAL - GRINDING | SQ FT | 164 | 164 |
| | | | | |
| X0323992 | HELICAL GROUND ANCHORS | EACH | 2 | 2 |
| | | | | |
| X7200201 | WIDTH RESTRICTION SIGNING | L SUM | 1 | 1 |

PAVEMENT MARKING SCHEDULE

| LOCATION | | COMMENT | SHORT TERM PAVEMENT MARKING | SHORT TERM PAVEMENT MARKING REMOVAL | | AVEMENT 5 - LINE 5" | PAVEMENT MARKING REMOVAL - GRINDING |
|------------|--------------|------------|-----------------------------------|--|------|------------------------|--|
| | | | 70300100 | 70300150 | 7800 | 1120 | 78300201 |
| STATION TO | STATION | | FOOT | SQ FT | FOOT | FOOT | SQ FT |
| | | | | | _ | | |
| 91+36 | 92+73 | LT EDGE | | | 137 | | 57 |
| 91-58 | 92+95 | RT EDGE | | | 137 | | 57 |
| 89+74 | 94+63 | CENTERLINE | 48 | 16 | | 120 | 50 |
| | | | | | | | |
| T | OTAL THIS SH | EET | 48 | 16 | 3 | 94 | 164 |

KUHN & TRELLO
CONSULTING ENGINEERS
A Limited Liability Company
A Professional Design Firm No. 184-006516

 USER NAME
 = myoung
 DESIGNED
 JS
 REVISED

 DRAWN
 MMY
 REVISED


 PLOT SCALE
 = 2.000 ' / in.
 CHECKED
 JS
 REVISED

 PLOT DATE
 = 8/30/2022
 DATE
 04/21/2022
 REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE:

PTB 199-030 - WO3D - Hancock County 72881\CADData\CADsheets\D6



TYPICAL SECTION (SN 034-0054)

STA. 90+80.00 TO STA. 91+47.50 RT/LT BRIDGE SN 034-0054 OMISSION/REPAIR STA. 91+47.50 TO STA. 92+15.16 STA. 92+15.16 TO STA. 92+80 RT/LT

- 1) EXISTING CONCRETE PAVEMENT
- 2) EXISTING HOT-MIX ASPHALT OVERLAY 5 1/4" & VARIES
- (3) EXISTING HOT-MIX ASPHALT WIDENING 9"
- 4 EXISTING HOT-MIX ASPHALT SURFACE COURSE, SUPERPAVE, N50 (1 1/2")
- 5 EXISTING HOT-MIX ASPHALT SHOULDERS, 8"


| - | | |
|-------|---|---|
| 1:12 | KUHN & TRELLO | - |
| NAME: | CONSULTING ENGINEERS A Limited Liability Company | |
| EN | 209 N. 7th Street, 3rd Floor Springfield, JL 62701 | _ |
| Ē | Professional Design Firm No. 184-006516 | = |

| USER NAME = myoung | DESIGNED - JS | REVISED - |
|----------------------------|-------------------|-----------|
| | DRAWN - MMY | REVISED - |
| PLOT SCALE = 4:0 ':" / in. | CHECKED - JS | REVISED - |
| PLOT DATE = 8/30/2022 | DATE - 04/21/2022 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE:

| | | | | | RTE | SECT |
|---------|-------|---------|-----|--------|-----|-----------|
| | TYPIC | CAL SEC | HON | | 510 | (119BR) E |
| | | | | | | |
| CHEET 1 | OF 1 | сысстс | CTA | TO CTA | | |



Existing Structure: GENERAL NOTES SN 034-00547 is a single span 67'-8" bk. to bk. abutments, 33'-0" O. to O. deck. Superstructure is 33" PPC deck beams on reinforced concrete closed abutments. All structural steel shall conform to AASHTO Classification M-270 Gr. 50, unless otherwise noted. Fasteners shall be $\frac{3}{4}$ " Ø, open holes $\frac{13}{16}$ " Ø, unless otherwise noted. Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor Replace polymer concrete and silicone expansion joint seal at South Abutment with shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments Preformed Joint Strip Seal. prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work. Reinforcement bars designated (E) shall be epoxy coated. Existing reinforcement bars extending into the removal area shall be cleaned, straightened and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Removal. Joint openings shall be adjusted according to Article 520.04 of the Std. Specs. when the deck is poured at an ambient 33" P.P.C. Beams temperature other than 50° F. For Staging Details, see Sheet 2 of 6. The Contractor shall use extreme care during concrete removal operations so as not to damage the existing PPC Deck The deck surface shall have its final finish tined according to Article 420.09(e)(1) of the Standard Specifications. Cost included with Concrete Superstructure. For Soil boring logs, see Sheet 6 of 6. Anchorage not **ELEVATION** shown for clarity Replace expansion joint with Preformed 32°39'00" Joint Strip Seal Roadway to out & Stage Construction Line Stage Removal Φ^{B-2} $lackbox{\Phi}_{B-1}$ Remove and replace Wingwall curbs, each end Stabilization See Sheet 5 of 6. TOTAL BILL OF MATERIALS Bk. of Bk. of STRUCTURAL AND N. Abut. S. Abut. 67'-8" Bk. to Bk. of Abut. ITEM UNIT QUANTITY Concrete Removal 2.7 Cu. Yd. STEVEN P. NEGANGARD NUMBER NUMBER O81-005284 Concrete Superstructure Cu. Yd. 2.6 PLAN Reinforcement Bars, Epoxy Coated Pound 410 Bar Splicers Each Preformed Joint Strip Seal Foot 39 Protective Coat Sq. Yd. Helical Ground Anchors Each * On new concrete surfaces Steven Negargard Date: August 31, 2022 Expires: November 30, 2024 KUHN & TRELLO DESIGNED - SPN REVISED **GENERAL PLAN AND ELEVATION** SECTION COUNTY **STATE OF ILLINOIS** CHECKED - MJT REVISED 510 (119BR) BRR, BJR, I HANCOCK 12 **STRUCTURE NO. 034-0054** DRAWN REVISED **DEPARTMENT OF TRANSPORTATION** CONTRACT NO. 72881

SHEET 1 OF 6 SHEETS


12/5/2022 8:28:59 AM

PLOT DATE =

CHECKED -

SPN/MJT

REVISED



8/30/2022 5:25:25 P


STANDARD BAR SPLICER ASSEMBLY PLAN

(All components shall be provided from one supplier)

Threaded splicer bar length = min. lap length + $1\frac{1}{2}$ " + thread length

* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.


| Location | Bar size | No. assemblies required | Minimum Iap length |
|-------------|-------------|----------------------------|-----------------------|
| Bridge Deck | #5 | 3 | 3'-6" |
| Hatch block | #5 | 4 | 3'-6" |
| | | | |
| | | | |
| | | | |



INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt "B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.

(E): Indicates epoxy coating.



STANDARD MECHANICAL SPLICER

| Location | Bar size | No. assemblies required |
|----------|-------------|----------------------------|
| | | |
| | | |
| | | |

Notes:

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.

All reinforcement shall be lapped and tied to the splicer bars.

Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications.

See approved list of bar splicer assemblies and mechanical splicers for alternatives.


BSD-1

1-1-2020

| : | KUHN & TRELLO | USER NAME = | DESIGNED - SPN | REVISED - |
|---|--|--------------|-------------------|-----------|
| | CONSULTING ENGINEERS A Limited Liability Company 109 N. 7th Street, 3rd Floor Saringfield, 11 6 2721 | | CHECKED - MJT | REVISED - |
| 2 | 109 N. 7th Street, 3rd Floor Springfield, JL 62701 | PLOT SCALE = | DRAWN - MMY | REVISED - |
| i | Phoné: 217-679-0044 Professional Design Firm No. 184-006516 | PLOT DATE = | CHECKED - SPN/MJT | REVISED - |

WOSD - Hancock County /2881/CADData\CADSneets\U340U34-72881-0U3-UK


MODEL: Default FILE NAME: J:\21046.03D IDOT



FOR SKEWS > 30°

* ¾" Ø x 6" Studs 1'-0" (8 per side 39" parapet) (10 per side 44" parapet) ¾" Embedded plate full depth ¾" Embedded plate, full depth 1/2" Parapet sliding plate 3/8" Ø Countersunk bolts 1'-0" (10 per side 39" parapet) (12 per side 44" parapet) Direction of traffic

SECTION B-B



Notes:

on the locking edge rail chosen by the Contractor. Deck and parapet lengths shown elsewhere in the plans are dimensioned to the concrete opening, not the joint opening, and are based on the rolled locking edge rail. If the Contractor elects to use a different locking edge rail, dimensional adjustments may be required. One exception to this would be the strip seal joint at the end of the precast bridge approach slab. For these cases the pavement connector length shall be adjusted, not the length of the bridge approach slab.

The strip seal shall be made continuous and shall have a minimum thickness of $\frac{1}{4}$ ". The configuration of the strip

are not permitted. The gland shall be sized for a maximum

The locking edge rails depicted are configured for typical

applications and are conceptual only. The actual configuration

of the locking edge rails and matching strip seal may vary from

manufacturer to manufacturer provided they fit the application

however, will not be allowed. Locking edge rails may exceed the

4½" maximum depth provided the anchorage system is revised


according to the manufacturer's recommendation. The manufacturer's recommended installation methods

and meet the minimum anchorage shown. Flanged edge rails,

seal shall match the configuration of the locking edge rails. Open or "webbed" strip seal gland configurations

rated movement of 4 inches.


PLAN AT PARAPET




 $FOR SKEWS \le 30^{\circ}$

SECTION AT PARAPET

(Skews > 30° shown. Skews ≤ 30° similar except as shown in plan view.)




DETAIL A



TRIMETRIC VIEW (Showing embedded plates only)


Locking edge rail at 50° F Top of concrete — Strip seal angled/bent studs with horizontal studs) at 50° F $\frac{3}{6}$ " ϕ threaded rods in $\frac{1}{16}$ " ϕ holes at ± 4 '-0" cts.

SHOWING WELDED RAIL JOINT



LOCKING EDGE RAILS

** Back gouge not required if complete joint penetration is verified by mock-up.



LOCKING EDGE RAIL SPLICE

The inside of the locking edge rail groove shall be free of weld residue. Rolled rail shown, welded rail similar.

BILL OF MATERIAL

| Item | Unit | Total | |
|----------------------------|------|-------|--|
| Preformed Joint Strip Seal | Foot | 39 | |
| | | | |

Locking edge railat 50° F Top of concrete Strip seal at 50°

SHOWING ROLLED RAIL JOINT

SECTION A-A

* Granular or solid flux filled headed studs conforming to Article 1006.32 of the Std. Specs., automatically end welded.

for holding the proper joint opening based on

miss studs. All rods shall be burned, or sawed

off flush with the plates after concrete is set.

the temperature during the deck pour. Place to


* $\frac{5}{8}$ " Ø x 6" studs @ 6" cts. (alternate

KUHN & TRELLO DESIGNED -REVISED -CHECKED - MJT REVISED DRAWN REVISED PLOT DATE = CHECKED -SPN/MJT REVISED

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION PREFORMED JOINT STRIP SEAL **STRUCTURE NO. 034-0054**

SECTION COUNTY 510 (119BR) BRR, BJR, I HANCOCK 12 10 CONTRACT NO. 72881

SHEET 4 OF 6 SHEETS



STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

SECTION

(119BR) BRR, BJR, I

510

COUNTY

HANCOCK

12 11

CONTRACT NO. 72881

WINGWALL STABILIZATION DETAILS

STRUCTURE NO. 034-0054

SHEET 5 OF 6 SHEETS

FILE NAME: 1:1210

31/2022 12:24:44 PM

KUHN & TRELLO

PLOT DATE =

DESIGNED - SPN

CHECKED - MJT

SPN/MJT

DRAWN

CHECKED -

REVISED

REVISED

REVISED

REVISED

, M NO. B. D. 187 REV. P-80 Str. ' L of ' FORM NO. B. D. 127 REV. 2-60 SIR 1 of 2 Sir. FORM HO. B. D. 187 MEV. P-60 5h. 2 of 2 5h. BRIDGE FOUNDATION DORING LOG BRIDGE FOUNDATION CORING LOG BRIDGE FOUNDATION DORING LOG BRIDGE IL Rt. 96 over PROJECT. BRIDGE IL Rt. 96 over BRIDGE IL Rt. 96 over 08-04-76 PROJECT_ Dato_ PROJECT_ ROITE FA-510 (formerly FA-82) D.E. Rring ROUTE FA-82 Tyson Creek ROUTE FA-82 Boned By D.E. Bruun Tysom Creek SEC. 119 BR 91 + 85<u>+</u> R.W. Baker Checked By R.W. Baker 119 BR R.W.Baker SEC. 119 BR COUNTY Hancock Hancock COUNTWANCOCK t/s.f. Surface Water El. \$∕s. f. Elevation COUNTY.... Surface Water El. t/2.f. 1/5.1 Surface Water El. Qu 1/s. f. Boring No. 3 + 34 Qu t/s. Groundwater El. at Boring No.___1 Dry 2 Groundwater El. et Completion Groundwater El. at z Station 90+82 Offset 15' RT CL Rdwy. Completion Q. Station.... õ 92+65 Hole Ë Station 16 RT CL Rdwy. Ö Officet 9.5' RT CL Rdwy. After ____ Hours After .___ Hours After ____ Hours Offsat_ Bround Surface Gray Silt Loam Moist (Hard) Ground Surface Ground Surface 571.7 0 Yellow-Brown Silty Clay Loam (Till) Brown Silty Clay Loam Moist (Stiff) Gray Silty Clay (Till)
Damp (Hard) 41 1.6S 16 Red & Gray mottled Damp (Hard) 547.9 43 Silty Clay (Till) Moist (Stiff) Moist (Stiff) **- 2**5 Boring Completed - 25 -- 25 546.4 38 3.55 22 Gray 19 4.5\$ 14 1.8B Silt LOam Moist (Very Stiff) 567.4 - 5 566.2⁻⁵ Yellow & Brown Silt Loam Moist (Stiff) Reddish-Brown Silty Clay Loam 39 1.45 15 Silt Loam 3.1s 4.1P Moist (Hard) Clay Loam (Till) Moist (Stiff) Damp (Very Stiff) 542 430 -30 564.2 -30 Grav Brown Silt Silty Clay Loam
Damp (Stiff) 26 Loam (Till) 33 2.35 Moist (Very Stiff) 1.4S 12 14 Damp (Stiff) Gravel (Cherty) -10 - 10 Moist (Medium) 561.2 Brown Gravel Gray Sand (Fine, Cherty) Damp (Very Dense) Silt Loam Damp (Loose) Moist (Very Stiff) -35 559.2 -35 -35 Sand & Gravel (Cherty) 33 Loam (T111) Wet (Loose) Silty Clay Loam (Till) Very Moist (Stiff) Silty Clay (Till) Moist (Hard) w/sand, gravel.& chert frags. 534.9 - 15 Moist (Very Stiff) Silty Clay (Till) thru. Gray Moist (Very Stiff) Silt Loam Residuum 48 Damp (Very Stiff) 6.4B Moist (Hard) w/pieces chert & Limestone thru. Silty Clay Loam (Till) 554.2 Damp (Hard) -40 -40 Gray Limestone Grav Auger refusal at 40' Limestone w/interbedded shale_ 48 3.55 W/silt loam throughout 552.4 -20 Boring Completed -- 20 -20 Silt Loam Moist (Hard) 39 4.3P -45 -45 - 45 Boring Completed N-Standard Ponetration Tost-N-Standard Ponetration Test-Qu-Unconfined Compressive Type failure: Qu-Unconfined Compressive Qu-Unconfined Compressive N-Standard Ponetration Test-Type failure: Type failure: Blows per foot to drive 2" Strongth - t/sf B - Bulge Failure Blows per fact to drive 2" Strongth-t/sf B - Bulge Failure Blows per foot to drive 2" Strongth - t/sf B - Bulgo Failure O.D. Split Spoon Sampler 12" with S - Shear Fallure w-Water Centent-percentage O.D. Split Spoon Sampler 12" with 5 - Shear Fallure O.D. Split Spoon Sampler 12" with S - Shoar Failure w -- Water Content -- percentage w-Water Content-percentage 140# hammer falling 30". . E - Estimated Value of oven dry weight - %. NR-No Recovery 140# hammer falling 30". 140# hammer falling 30". ' E - Estimated Value E-Estimated Value BS - DEFORE SEATING of oven dry walpht - %. of oven dry weight - %. P - Penetrometer DS - BEFORE SEATING BS - BEFORE SEATING P - Penatrometer P -- Penatrometer NR-No Recovery NR-No Recovery

KUHN & TRELLO

CONSULTING ENGINEERS
A Limited Liability Company
100 N. This Street, 174 floor
Springfield, 15 25701

Professional Design Eigen No. 34-0656

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS
STRUCTURE NO. 034-0054

SHEET 6 OF 6 SHEETS

 F.A.P. RTE.
 SECTION
 COUNTY SHEETS NO.
 SHEETS NO.

 510
 (119BR) BRR, BJR, I
 HANCOCK 12
 12
 12

 CONTRACT NO. 72881

 ILLINOIS FED. AID PROJECT