

SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENING

WORK ZONE EXIT OPENING






NOTES

- 1. THE ARROWBOARD, THE FLAGGER AHEAD SIGN AND THE TRUCKS LEAVING HIGHWAY SIGN SHALL BE REMOVED OR TURNED AWAY FROM TRAFFIC AND THE EXIT AND ENTRY OPENINGS SHALL BE CLOSED WHEN THE FLAGGING OPERATION CEASES. NON OPERATING EQUIPMENT SHALL COMPLY WITH ARTICLE 701.11
- 2. WORK ZONE EXIT OPENINGS SHOULD BE A MINIMUM OF ONE HALF MILE APART.
- 3. EXITING THE WORK ZONE AT ANY PLACE OTHER THAN AT A WORK ZONE EXIT OPENING WILL BE PROHIBITED.
- 4. ALL VEHICLES SHALL ENTER THE WORK ZONE AT ENTRY OPENINGS, USING THEIR TURN SIGNALS TO WARN MOTORISTS

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN

ARTERIAL ROAD INFORMATIONAL SIGN



NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

TC-18, LATEST REVISION DATE: 12-09

TC-22, LATEST REVISION DATE: 01-31-07

10 10, 2711201 11211			ON								GHA #4085.8628				
FILE NAME =	USER NAME = ZACH WALLSTEN	DESIGNED - JRD	REVISED -		DISTRICT 1 STANDARD DETAILS					F.A.P.	SECTION	COUNTY	TOTAL	SHEET NO.	
4085.862-866-DT1.dwg		DRAWN - ZCW	REVISED -	STATE OF						VARIES	2010-005TS	соок	32	32	
	PLOT SCALE = 1" = .0833'	CHECKED - KLB	REVISED -	DEPARTMENT OF T	RANSPORTATION	STANDARD DETAILS						C-18 & TC-22	CONTRACT	T#: 60K	K23
	PLOT DATE = 10/12/2010	DATE - 10/12/2010	REVISED -			SCALE: N.A.	SHEET NO. OF	SHEET NO. OF SHEETS STA. TO STA.				ILLINOIS FED. A	AID PROJECT		