

SCHEDULE OF QUANTITIES
F.A.I. 74

PARTIAL DEPTH PATCHING (cont.)

STATION	REMARKS OR STRUCTURE NUMBER	DIRECTION	LANE	PRIORITY (1 = HIGHEST 3 = LOWEST)	LENGTH (ft)	WIDTH (ft)	APPROX. PARTIAL DEPTH REMOVAL THICKNESS (INCH)	EXISTING OVERLAY THICKNESS (4 3/4" or less) (Inch)	PARTIAL DEPTH REMOVAL, VARIABLE DEPTH X4422000 (sq. yd)	PARTIAL DEPTH REMOVAL, 5" 44022037 (sq. yd)	PARTIAL DEPTH PATCHING X4421000 (tons)
PIATT CO:											
1191+50	0043	WESTBOUND	DRIVING	1	8.00	12.00	5 TO 1.5	11"	10.7		1.9
1190+77	0043	WESTBOUND	DRIVING	1	25.00	12.00	5 TO 1.5	11"	33.3		6.1
1188+42	0043	WESTBOUND	DRIVING	1	25.00	12.00	5 TO 1.5	11"	33.3		6.1
1188+27	0043	WESTBOUND	DRIVING	1	8.00	12.00	5 TO 1.5	11"	10.7		1.9
1188+00	0043	WESTBOUND	DRIVING	1	8.00	12.00	5 TO 1.5	11"	10.7		1.9
1080+50	NO	WESTBOUND	DRIVING	3	8.00	12.00	5.00	11"		10.7	3.0
1053+11	NO	WESTBOUND	DRIVING	3	10.00	12.00	5.00	5 1/2"		13.3	3.7
961+90	NO	WESTBOUND	DRIVING	3	6.00	12.00	5.00	5 1/2"		8.0	2.2
924+90	0038	WESTBOUND	DRIVING	1	15.00	12.00	5 TO 1.5	5 1/2"	20.0		3.6
924+56	0038	WESTBOUND	DRIVING	1	40.00	12.00	5 TO 1.5	5 1/2"	53.3		9.7
921+44	0038	WESTBOUND	DRIVING	1	70.00	12.00	5 TO 1.5	5 1/2"	93.3		17.0
921+03	0037	EASTBOUND	DRIVING	1	75.00	12.00	5 TO 1.5	5 1/2"	100.0		18.2
924+07	0037	EASTBOUND	DRIVING	1	48.00	12.00	5 TO 1.5	5 1/2"	64.0		11.6
933+00	NO	EASTBOUND	DRIVING	3	6.00	12.00	5.00	5 1/2"		8.0	2.2
1187+90	0042	EASTBOUND	DRIVING	1	6.00	12.00	5 TO 1.5	11"	8.0		1.5
1188+42	0042	EASTBOUND	DRIVING	1	150.00	12.00	5 TO 1.5	11"	200.0		36.4
1190+77	0042	EASTBOUND	DRIVING	1	35.00	12.00	5 TO 1.5	11"	46.7		8.5
1191+50	0042	EASTBOUND	DRIVING	1	6.00	12.00	5 TO 1.5	11"	8.0		1.5
1245+04	NO	EASTBOUND	DRIVING	3	6.00	12.00	5.00	11"		8.0	2.2
1257+71	NO	EASTBOUND	DRIVING	3	6.00	12.00	5.00	6 1/2"		8.0	2.2
PIATT TOTAL									692.0	56.0	141.6
USE									692.0	56.0	142.0
TOTAL									1403.0	192.0	307.0