VEO49 **TOTAL SHEETS: 14** 

# CONSTRUCTION PLANS FOR VERMILION REGIONAL AIRPORT


**VERMILION REGIONAL AIRPORT AUTHORITY** DANVILLE, ILLINOIS


> **ILLINOIS PROJECT DNV-4232** SBG PROJECT 3-17-SBGP-XX

# REHABILITATE LIGHTS ON **RUNWAY 16/34**

ADDITIVE ALTERNATE #1: REHABILITATE LIGHTS ON TAXIWAY D ADDITIVE ALTERNATE #2: INSTALL COUNTERPOISE ON TAXIWAY D ADDITIVE ALTERNATE #3: LED UPGRADE

# **JANUARY 3, 2013**







VERMILION COUNTY AIRPORT AUTHORITY VERMILION COUNTY AIRPORT DANVILLE, ILLINOIS




CRAWFORD MURPHY & TILLY, INC. CONSULTING ENGINEERS

■ SPRINGFIELD, IL ■ AURORA, IL ■ST. LOUIS, MO

SUBMITTED BY TORKE

CMT JOB NUMBER 09042-02-00



MAXIMUM EQUIPMENT HEIGHT = 25' **GROUND FREQUENCY 122.70 MHz** COMMON GROUND ALLIANCE www.call811.com or Phone: 811 VERMILLION REGIONAL AIRPORT TOWNSHIP: 20 NORTH RANGE: 11 WEST SECTION: 15 COUNTY: VERMILLION

CIVIL TOWNSHIP:

J.U.L.I.E. JOINT UTILITY LOCATING

# **SUMMARY OF QUANTITIES**

BASE BID					
ITEM# DESCRIPTION UNIT QUANT					
AR108158	1/C #8 5KV UG CABLE IN UD	L.F.	8,650		
AR108706	1/C #6 COUNTERPOISE	L.F.	10,650		
AR800250	2-1/C #8 5KV UG CABLE IN UD	L.F.	2,900		
AR125415	MITL - BASE MOUNTED	EACH	3		
AR125442	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	4		
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	2		
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	2		
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	1		
AR125505	MIRL, STAKE MOUNTED	EACH	22		
AR125510	MIRL, BASE MOUNTED	EACH	16		
AR125545	MI THRESHOLD LIGHT BASE MOUNTED	EACH	14		
AR125565	SPLICE CAN	EACH	3		
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	43		
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	8		
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	9		

	ADDITIVE ALTERNATE 1					
ITEM#	DESCRIPTION	UNIT	QUANTITY			
AS108158	1/C #8 5KV UG CABLE IN UD	L.F.	2,700			
AS800250	2-1/C #8 5KV UG CABLE IN UD	L.F.	265			
AS125410	MITL - STAKE MOUNTED	EACH	27			
AS125415	MITL - BASE MOUNTED	EACH	3			
AS125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	1			
AS125901	REMOVE STAKE MOUNTED LIGHT	EACH	23			
AS125902	REMOVE BASE MOUNTED LIGHT	EACH	4			
AS125904	REMOVE TAXI GUIDANCE SIGN	EACH	1			

ADDITIVE ALTERNATE 2				
ITEM#	DESCRIPTION	UNIT	QUANTITY	
AT108706	1/C #6 COUNTERPOISE	LF	2,700	

	ADDITIVE ALTERNATE 3					
ITEM#	DESCRIPTION	UNIT	QUANTITY			
AU125417	MITL LED UPGRADE	EACH	33			
AU125462	SIGN LED UPGRADE	EACH	10			
AU125511	MIRL LED UPGRADE	EACH	38			
AU125546	MI THRESHOLD LIGHT LED UPGRADE	EACH	14			

INDEX OF SHEETS						
SHEET NO.	SHEET NO. SHEET TITLE					
01	COVER SHEET					
02	SUMMARY OF QUANTITIES					
03	SITE PLAN					
04	CONSTRUCTION SAFETY PHASING PLAN NOTES					
05	CONSTRUCTION ACTIVITY PLAN PHASE 1					
06	CONSTRUCTION ACTIVITY PLAN PHASE 2					
07	CONSTRUCTION ACTIVITY PLAN PHASE 3					
08	ELECTRICAL SITE PLAN 1					
09	ELECTRICAL SITE PLAN 2					
10	ELECTRICAL SITE PLAN 3					
11	ELECTRICAL SITE PLAN 4					
12	ELECTRICAL DETAILS 1					
13	ELECTRICAL DETAILS 2					
14	SIGN DETAIL AND SCHEDULE					

K:\DanvilleAp\1304201\Draw\Sheets FILE: SUMQUANT.dwg UPDATE BY: TJ Heovisides PLOT DATE: 1/23/2014 1:33 PM

# VE049

REVISIONS						
NUMBER	BY	DATE				

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

SUMMARY OF QUANTITIES

REHABILITATE LIGHTS ON RUNWAY 16/34

CRAWFORD, MARPHY & TILLY, NC. CONSULTING ENGNEERS License No. 184-000613


VERMILION REGIONAL AIRPORT AUTHORITY VERMILION REGIONAL AIRPORT DANVILLE, ILLINOIS



DESIGN BY: TJH СМТ DRAWN BY: CHECKED BY: APPROVED BY: DATE: JANUARY 3, 2014 JOB No: 13042-01

> IL. PROJ. NO. DNV-4234 PROJ. NO. 3-17-SBGP-XX

SHEET 02 OF 14 SHEETS



REVISIONS					
NUMBER	BY	DATE			

JANUARY 3, 2014

## 1. GENERAL

- THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL FOLLOW THE REQUIREMENTS OF THE AIRPORT'S APPROVED CONSTRUCTION SAFETY AND PHASING PLAN (CSPP), FAA AC 150/5370-2F, AND ALL AIRPORT SAFETY AND SECURITY **REQUIREMENTS**
- 2. PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL SUBMIT TO THE AIRPORT FOR APPROVAL A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) IN ACCORDANCE WITH FAA AC 150/5370-2F. NO CONSTRUCTION ACTIVITY SHALL BEGIN UNTIL THE AIRPORT HAS APPROVED THE SPCD
- THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER
- A MINIMUM OF 10 DAYS PRIOR TO THE NOTICE TO PROCEED. THE CONTRACTOR SHALL PROVIDE A LIST OF SUBCONTRACTORS AND MATERIAL SUPPLIERS.
- ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED ON THIS SHEET SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT UNLESS A SPECIFIC PAY ITEM IS PROVIDED.
- THE CONTRACTOR SHALL BACKFILL ALL SAFETY AREAS DISTURBED AT ACTIVE PAVEMENTS AT THE END OF EACH WORK

# 2. COORDINATION

- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ATTEND A PRECONSTRUCTION CONFERENCE WITH THE AIRPORT, RESIDENT ENGINEER, AND ILLINOIS DIVISION OF AERONAUTICS (IDA). THE COST OF PREPARING FOR AND ATTENDING THE PRECONSTRUCTION CONFERENCE SHALL BE INCIDENTAL TO THE CONTRACT.
- ON OR BEFORE THE PRECONSTRUCTION CONFERENCE. THE CONTRACTOR SHALL SUBMIT A PROPOSED SCHEDULE FOR THE PROJECT. THE SCHEDULE SHALL INCLUDE A START AND COMPLETION DATE FOR EACH ITEM OF WORK. THE SCHEDULE SHALL BE UPDATED ON A WEEKLY BASIS. ALL COSTS ASSOCIATED WITH THE SCHEDULE SHALL BE INCIDENTAL TO THE CONTRACT.
- DURING CONSTRUCTION THE CONTRACTOR SHALL ATTEND A WEEKLY COORDINATION MEETING WITH THE AIRPORT STAFF AND RESIDENT ENGINEER. ALL COSTS ASSOCIATED WITH ATTENDING THE WEEKLY MEETING SHALL BE INCIDENTAL TO THE CONTRACT.
- IT IS ANTICIPATED THAT THE AIRPORT WILL HAVE MULTIPLE CONSTRUCTION PROJECTS THAT WILL REQUIRE RUNWAY CLOSURES. THE CONTRACTOR SHALL COORDINATE THE CONSTRUCTION SCHEDULE/PHASING CLOSELY WITH OTHER CONTRACTORS PRIOR TO THE START OF CONSTRUCTION. FINAL AUTHORITY IN THE APPROVAL OF CONSTRUCTION SEQUENCING LIES WITH THE AIRPORT

# 3. PHASING

- TOTAL CONTRACT TIME SHALL BE AS FOLLOWS: BASE BID = 48 CALENDAR DAYS. ADDITIVE ALTERNATE 1 = 13 CALENDAR DAYS ADDITIVE ALTERNATE 2 = 3 CALENDAR DAYS ADDITIVE ALTERNATE 3 = 0 CALENDAR DAYS
- PHASING SHALL BE AS NOTED BELOW AND AS SHOWN ON THE CONSTRUCTION ACTIVITY PLAN (CAP) SHEETS.

# 4. AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY

- ALL RUNWAYS, TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE CONSTRUCTION ACTIVITY PLANS.
- WHEN CONFLICTS ARISE BETWEEN CONSTRUCTION ACTIVITIES AND AIRCRAFT OPERATIONS AND SAFETY, AIRCRAFT OPERATIONS AND SAFETY SHALL TAKE PRECEDENCE AND SHALL GOVERN. FINAL AUTHORITY IN THE APPROVAL OF CONSTRUCTION SEQUENCING LIES WITH THE AIRPORT
- ALL CONSTRUCTION TRAFFIC SHALL IMMEDIATELY YIELD TO ONCOMING AIRCRAFT AT ALL TIMES.

# 5. CONTRACTOR ACCESS

- CONTRACTOR ACCESS SHALL BE AS NOTED BELOW AND AS SHOWN ON THE SITE PLAN AND CONSTRUCTION ACTIVITY PLAN
- THE CONTRACTOR IS TO ACCESS THE SITE USING THE GATES
- CONTRACTOR SHALL MAINTAIN LIST OF NAMES, DRIVER'S LICENSE NUMBER, TRUCK LICENSE PLATE NUMBER AND NAME OF TRUCKING COMPANY TO THE PRIME CONTRACTOR PRIOR TO ENTERING THE JOBSITE
- CONTRACTOR WORK CREWS MUST MONITOR THE UNICOM AT ALL TIMES WHEN INSIDE THE AIRPORT OPERATIONS AREA (AOA). THE CONTRACTOR SHALL SUPPLY ALL APPROPRIATE RADIOS NÉEDED FOR COMMUNICATIONS. BE AWARE OF TENANT AIRCRAFT MOVEMENT NEAR THE WORK AREAS.
- THE CONTRACTORS STORAGE AND STAGING AREA WILL BE AS SHOWN IN THE SITE PLAN.
- THE CONTRACTOR SHALL KEEP A RECORD OF THE NAMES OF ALL EMPLOYEES ENTERING THE JOB SITE ON A DAILY BASIS. A RECORD OF EACH SUBCONTRACTOR ENTERING THE JOB SITE SHALL ALSO BE KEPT BY THE CONTRACTOR
- WHEN THE CONTRACTOR IS NOT WORKING, EQUIPMENT SHALL BE STORED AT THE STAGING AREA.
- THE CONTRACTOR WILL BE PERMITTED TO STORE EQUIPMENT AND MATERIALS ONLY AT THE LOCATIONS SHOWN. PARKED **FOLIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE** SURFACES DEFINED BY F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE.
- THE CONTRACTOR SHALL THOROUGHLY CLEAN ALL CONSTRUCTION AREAS AND HAUL ROUTES WHICH WILL BE OPENED TO AIR TRAFFIC TO THE SATISFACTION OF AIRPORT OPERATIONS OR THE RESIDENT ENGINEER. A HANDHELD POWER AIR BLOWER SHALL BE ON SITE AT AND AVAILABLE FOR USED AT ALL TIMES WHEN ACTIVE PAVEMENTS ARE UTILIZED FOR CONSTRUCTION TRAFFIC.
- ALL PAVEMENTS, DRIVES OR ANY OTHER AREAS LITILIZED BY THE CONTRACTOR FOR HAUL ROADS OR STORAGE AREAS SHALL BE MAINTAINED AND REPAIRED TO THE SAME CONDITION OR BETTER THAN THEY WERE PRIOR TO BEGINNING CONSTRUCTION. NO ADDITIONAL COMPENSATION WILL BE MADE TO THE CONTRACTOR
- ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR SHALL BE PROPERLY TRAINED BY THE CONTRACTOR

# 6. WILDLIFE MANAGEMENT

- THE CONTRACTOR SHALL NOTIFY AIRPORT OPERATIONS OR THE RESIDENT ENGINEER IF ANY WILDLIFE IS SEEN ENTERING THE
- CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE CONTRACTOR IS NOT WORKING
- THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING FOOD SCRAPS IN APPROVED CONTRACTOR PROVIDED

# 7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

- THE CONTRACTOR SHALL PICK UP FOREIGN OBJECT DEBRIS (FOD) SEEN ON THE AIRFIELD PAVEMENTS
- THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES PRIOR TO DRIVING ON AIRFIELD PAVEMENTS.

# 8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT

THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA SHEETS (MSDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE.

# 9. NOTIFICATION OF CONSTRUCTION ACTIVITIES

- THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT PERSON AND PHONE NUMBER.
- THE CONTRACTOR SHALL GIVE A MINIMUM OF 14 DAYS NOTICE TO AIRPORT OPERATIONS PRIOR TO CLOSING ANY PAVEMENTS SO THAT PROPER NOTAMS MAY BE ISSUED BY THE AIRPORT AND THE AIRPORT MAY COORDINATE CLOSURES WITH TENANTS/FREQUENT AIRPORT USERS.
- FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT GREATER THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT THE TYPE OF EQUIPMENT, TOTAL HEIGHT, AND LOCATION WHERE THE EQUIPMENT WILL BE USED. THE AIRPORT WILL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY NO EQUIPMENT WITH A HEIGHT GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS RECEIVED.
- IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL CALL
- CONTACTS FOR THIS PROJECT ARE AS DISCUSSED IN THE PRE-CONSTRUCTION MEETING.

# 10. INSPECTION REQUIREMENTS

- THE CONTRACTOR SHALL INSPECT THE JOBSITE DAILY TO ENSURE COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX 3 OF FAA AC 150/5370-2F MAY BE USED TO AID IN THE INSPECTIONS
- THE CONTRACTOR AND AIRPORT SHALL ATTEND AN INSPECTION OF EACH PHASE WORK AREA PRIOR TO OPENING THE AREA TO AIRPORT OPERATIONS.

# 11. UNDERGROUND UTILITIES

- IT WILL BE NECESSARY FOR THE CONTRACTOR TO MAKE HIS OWN FIELD INVESTIGATION TO DETERMINE THE EXACT LOCATION OF THE UNDERGROUND UTILITIES AT CRITICAL POINTS. THE LOCATION OF LINDERGROUND LITILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION
- BEFORE INITIATING ANY DIGGING, DRILLING OR EXCAVATING ON THE AIRPORT PROPERTY, THE CONTRACTOR SHALL CALL J.U.L.I.E. AND CONTACT THE LOCAL FAA OFFICE TO ARRANGE FOR UTILITY LOCATES. SEE SECTION 70-17 OF THE SPECIAL PROVISIONS FOR UTILITY CONTACT INFORMATION

# 12. PENALTIES

NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT BUILES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT IN FINES AS ALLOWED BY LAW.

# 13. SPECIAL CONDITIONS

ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE CONTRACTOR. SEE THE COORDINATION NOTES FOR ADDITIONAL INFORMATION

# 14. RUNWAY AND TAXIWAY VISUAL AIDS

- PROJECT WILL REQUIRE THE CLOSURE OF RUNWAY 16/34 FOR THE DURATION OF THE CONTRACT. THE CONTRACTOR SHALL USE MARKING, LIGHTING, AND SIGNS THAT FOLLOW THE REQUIREMENTS OF FAA AC 150/5370-2F
- BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE CONSTRUCTION ACTIVITY PLAN SHEET

# 15. MARKING AND SIGNS FOR ACCESS ROUTES

BARRICADES AND SIGNS SHALL BE USED ALONG THE CONTRACTOR'S ACCESS ROUTE AS DETAILED ON THIS SHEET AND THE CONSTRUCTION ACTIVITY PLAN SHEET

# 16. HAZARD MARKING AND LIGHTING

- THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS AND ASSOCIATED LIGHTING OF OPEN TRENCHES. EXCAVATIONS, TEMPORARY STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT.
- ALL CONSTRUCTION EQUIPMENT SHALL BE FLAGGED AND/OR LIGHTED IN ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2F AND 150/5210-5C AT ALL TIMES WHILE OPERATING ON AIRPORT PROPERTY. THE MAXIMUM EQUIPMENT HEIGHT IS 25'.
- BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE CONSTRUCTION ACTIVITY PLAN SHEET OR AS DIRECTED BY
- THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED LIGHTS AND FLAG PLACEMENT

# 17. PROTECTION


- ALL WORK REQUIRED ON AN ACTIVE TAXIWAY OR INSIDE OF AN ACTIVE TAXIWAY OBJECT FREE AREA, WHICH EXTENDS 93' FROM THE TAXIWAY CENTERLINE, WILL REQUIRE THE TAXIWAY TO BE CLOSED. THE CONTRACTOR SHALL COORDINATE WITH THE AIRPORT A MINIMUM OF 72 HOURS PRIOR TO THE REQUESTED CLOSURE TIME.
- ALL WORK REQUIRED INSIDE OF RUNWAY SAFETY AREAS, WHICH EXTENDS 250' FROM THE RUNWAY CENTERLINE, WILL REQUIRE THE RUNWAY TO BE CLOSED. THE CONTRACTOR SHALL COORDINATE WITH THE AIRPORT AS INDICATED ON THE CONSTRUCTION ACTIVITY PLANS PRIOR TO THE REQUESTED CLOSURE TIME.

# 18. OTHER LIMITATIONS ON CONSTRUCTION

- 1. IF DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE AIRPORT, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL VEHICLES, PERSONNEL AND EQUIPMENT.
- BROKEN CONCRETE, BROKEN ASPHALT, AND OTHER MISCELLANEOUS DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS OTHERWISE SPECIFIED

ILE: CSPPN.dwg JPDATE BY: TJ Heavisides PLOT DATE: 1/13/2014 10:48 AM

# **VE049**



THIS BAR IS FOLIAL TO 2 AT FULL SCALE (34X22).

# RUNWAY 16/34 PHASING PLAN . AIRPORT AUTHORITY SIONAL AIRPORT E, ILLINOIS LIGHTS ON F N SAFETY I NOTES REGIONAL A

REHABILITATE L VERMILION R VERMI


CRAWFO



DESIGN BY: TJH CMT DRAWN BY: CHECKED BY: AJB APPROVED BY: CFT JANUARY 3, 2014 JOB No: 13042-01

> IL. PROJ. NO. DNV-4234 PROJ. NO. 3-17-SBGP-XX

SHEET 04 OF 14 SHEETS




# GENERAL CONSTRUCTION SCHEDULING/PHASING NOTES

- THE AIRPORT IS SCHEDULED TO HAVE AN EVENT ON JUNE 17TH, 2014 WHICH REQUIRES THE FULL SERVICE OF THE AIRPORT WITHOUT DISRUPTION FROM CONSTRUCTION OPERATIONS. THEREFORE, JUNE 23RD SHALL BE THE EARLIEST DATE CONSIDERED FOR THE COMMENCEMENT OF THIS PROJECT.
- 2. THE CONTRACTOR SHALL COORDINATE THE SCHEDULE AND PHASING OF THIS PROJECT CLOSELY WITH OTHER CONTRACTORS ON SITE. IT IS OF PARTICULAR CONCERN THAT CONSTRUCTION SCHEDULING BE COORDINATED WITH THE AIRPORT AND THE CONTRACTOR FOR THE "RELOCATE TAXIWAY C AND WIDEN FILLETS" PROJECT AS THAT PROJECT REQUIRES THE CLOSURE OF RUNWAY 3/21. CONSTRUCTION OF THE TWO PROJECTS MAY NOT BE CONCURRENT IF THEY RESULT IN THE CLOSURE OF BOTH RUNWAY 3/21 AND RUNWAY 16/34 FOR LONGER THAN THE SPECIFIED RUNWAY 3/21 CLOSURE ON CONSTRUCTION ACTIVITY PLAN 3 OF THIS PROJECT.
- 3. PHASES 1 THROUGH 3 MAY BE INTERCHANGEABLE PROVIDED THAT THE CONTRACTOR PROVIDES A WRITTEN REQUEST TO REVISE THE PHASING WITH SUFFICIENT TIME FOR THE AIRPORT TO REVIEW AND ISSUE APPROPRIATE NOTIFICATIONS BASED ON CLOSURE REQUIREMENTS. THE AIRPORT SHALL HAVE THE FINAL SAY REGARDING CONSTRUCTION PHASING.
- 4. SHOULD THE "RELOCATE TAXIWAY C AND WIDEN FILLETS" PROJECT BEGIN PRIOR TO THE COMMENCEMENT OF THIS PROJECT, THE CONTRACTOR SHALL SCHEDULE TO COMPLETE PHASES 3A AND 3B DURING THE RUNWAY 3/21 CLOSURE FOR THE "RELOCATE TAXIWAY C AND WIDEN FILLETS" PROJECT. THE CONTRACTOR SHALL ALSO HAVE THE OPTION TO COMPLETE PHASE 3C AT THAT TIME PROVIDED THAT WORK IN PHASES 3A AND 3B ARE COMPLETED WITHIN THE ALLOTTED RUNWAY 3/21 CLOSURE TIME (AND PROVIDED THAT THE RELATED ADDITIVE ALTERNATE WORK IS AWARDED). AFTER THE COMPLETION OF PHASE 3, THE PROJECT SHALL BE SUSPENDED UNTIL THE COMPLETION OF THE "RELOCATE TAXIWAY C AND WIDEN FILLETS" PROJECT AND RUNWAY 3/21 HAS BEEN BE-OPENED.

# PHASE 1 NOTES

- 1. THE CONTRACTOR SHALL CLOSE RUNWAY 16/34 FOR THE DURATION OF THIS PHASE.
- THE CONTRACTOR MUST PROVIDE A YELLOW "X" AT EACH END OF THE RUNWAY IN ORDER TO CLOSE THAT RUNWAY (SEE CONSTRUCTION ACTIVITY PLAN 2).
- 3. THE CONTRACTOR MUST PROVIDE A YELLOW "X" ON TAXIWAY D AT THE INTERSECTION OF RUNWAY 3/21 (SEE DETAIL ON CONSTRUCTION ACTIVITY PLAN 3).
- 4. THE CONTRACTOR SHALL PROVIDE A FLAGGER WHEN OPERATIONS REQUIRE CROSSING ACTIVE RUNWAY 3/21. THE CONTRACTOR SHALL PLAN AND CONDUCT HIS WORK IN SUCH A MANNER THAT RUNWAY CROSSINGS ARE LIMITED TO THE FEWEST POSSIBLE CROSSINGS EACH DAY.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTINUOUSLY CLEANING ACTIVE AIRFIELD PAVEMENTS WHICH ARE CROSSED BY HIS VEHICLES ACCESSING THE WORK OR DEPARTING THE WORK IMMEDIATELY FOLLOWING SAID VEHICLE.
- 6. WORK SHALL NOT BE COMPLETED WITHIN 250' FROM THE CENTERLINE OF AN ACTIVE RUNWAY. WORK WITHIN 250' OF RUNWAY 3/21 SHALL REQUIRE THE CLOSURE OF THAT RUNWAY AND SHALL BE AS NOTED ON CONSTRUCTION ACTIVITY PLAN 3.
- BARRICADES SHOWN ON THIS SHEET SHALL BE PLACED AT 250' FROM A RUNWAY CENTERLINE OR 100' FROM A TAXIWAY CENTERLINE.
- 8. THE CONTRACTOR SHALL PLACE A TEMPORARY STOP SIGN AT THE INTERSECTION OF THE AIRFIELD APRON TO ALERT CONSTRUCTION TRAFFIC TO YIELD TO AIRPORT OPERATIONS. ALL COSTS ASSOCIATED WITH THE SIGN SHALL BE INCIDENTAL TO THE PROJECT.



FLASHER BARRICADE DETAIL


# FLASHER BARRICADE NOTES

- 1. FLASHERS TO BE BATTERY OPERATED. LENS TO BE RED AND BE ABLE TO ROTATE 90 DEGREES.
- 2. SANDBAGS TO BE PLACED ON EACH SUPPORT BRACE AS REQUIRED TO PREVENT DISPLACEMENT BY WIND, JET OR PROP BLAST.
- 3. NO SEPARATE PAYMENT WILL BE MADE FOR THIS ITEM. COSTS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 4. PLACE AT 15' INTERVALS.

FILE: CAP1.dwg UPDATE BY: TJ Heavisides PLOT DATE: 1/13/2014 10:48 AM

> DNVBase\_StatePlane Baselines

# **VE049**



THIS BAR IS EQUAL TO 2 AT FULL SCALE (34X22).

AIRPORT AUTHORITY
GONAL AIRPORT
GONAL AIRPORT
GON RUNWAY 16/34
TIVITY PLAN PHASE 1

REHABILITATE LIGHTS ON RUNWAY 16/3
ONSTRUCTION ACTIVITY PLAN PHA

Ŭ

© Copyright CMT, Inc.

RD, MURPHY & TILLY, INC.
FING ENGINEERS

REGIONAL A

VERMILION F VERMI

CRAWFO

DESIGN BY:

DESIGN BY: TJH

DRAWN BY: CMT

CHECKED BY: AJB


APPROVED BY: CET

DATE: JANUARY 3, 2014

JOB No: 13042-01


PROJ. NO. 3-17-SBGP-XX

SHEET 05 OF 14 SHEETS



# PHASE 2 NOTES

- 1. THE CONTRACTOR SHALL CLOSE RUNWAY 16/34 FOR THE DURATION OF THIS PHASE.
- 2. THE CONTRACTOR MUST PROVIDE A YELLOW "X" AT EACH END OF THE RUNWAY IN ORDER TO CLOSE THAT RUNWAY.
- 3. THE CONTRACTOR SHALL PROVIDE A FLAGGER WHEN OPERATIONS REQUIRE CROSSING ACTIVE RUNWAY 3/21. THE CONTRACTOR SHALL PLAN AND CONDUCT HIS WORK IN SUCH A MANNER THAT RUNWAY CROSSINGS ARE LIMITED TO THE FEWEST POSSIBLE CROSSINGS EACH DAY.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTINUOUSLY CLEANING ACTIVE AIRFIELD PAVEMENTS WHICH ARE CROSSED BY HIS VEHICLES ACCESSING THE WORK OR DEPARTING THE WORK IMMEDIATELY FOLLOWING SAID VEHICLE.
- 5. WORK SHALL NOT BE COMPLETED WITHIN 250' FROM THE CENTERLINE OF AN ACTIVE RUNWAY.
  WORK WITHIN 250' OF RUNWAY 3/21 SHALL REQUIRE THE CLOSURE OF THAT RUNWAY AND SHALL
  BE AS NOTED ON CONSTRUCTION ACTIVITY PLAN 3.
- BARRICADES SHOWN ON THIS SHEET SHALL BE PLACED AT 250' FROM A RUNWAY CENTERLINE OR 100' FROM A TAXIWAY CENTERLINE.
- WORK IN PHASE 2 MAY BE COMPLETED CONCURRENTLY WITH WORK IN PHASE 1 PROVIDED THAT THE WORK IS MANAGED AS TWO SEPARATE PHASES AND THE NUMBER OF RUNWAY CROSSINGS ARE NOT INCREASED.



# CLOSED RUNWAY MARKER DETAIL

# NOTES

- 1. MARKERS SHALL BE SOLID YELLOW.
- 2. MARKERS SHALL BE PAINTED BURLAP, PLYWOOD OR OTHER APPROVED SOLID MATERIALS.
- 3. CONTRACTOR SHALL MAINTAIN MARKERS.
- COST OF FURNISHING, INSTALLING, MAINTAINING, RELOCATING AND REMOVING MARKERS SHALL BE INCIDENTAL TO THE CONTRACT.
- 5. MARKERS SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS.
- 6. PORTABLE CLOSED RUNWAY MARKERS SHALL BE PROVIDED BY THE AIRPORT FOR USE ON RUNWAY 3/21. THE MARKERS SHALL BE INSTALLED, OPERATED AND MAINTAINED BY THE CONTRACTOR DURING THE LENGTH OF THE RUNWAY CLOSURE. ALL COSTS ASSOCIATED WITH THE PORTABLE CLOSED RUNWAY MARKERS SHALL BE INCIDENTAL TO THE CONTRACT.

FILE: CAP2.dwg UPDATE BY: TJ Heavisides PLOT DATE: 1/13/2014 10:48 AM

DNVBase\_StatePlane Baselines

# VE049

REVISIONS						
NUMBER BY DATE						
0	1	2				

THIS BAR IS EQUAL TO 2' AT FULL SCALE (34X22).

2

# VERMILION REGIONAL AIRPORT AUTHORITY VERMILION REGIONAL AIRPORT DANVILLE, ILLINOIS REHABILITATE LIGHTS ON RUNWAY 16/34 ONSTRUCTION ACTIVITY PLAN PHASI


CRAWFORD, MURPHY & TILLY, III CONSULTING ENGINEERS





DESIGN BY: TJH
DRAWN BY: CMT
CHECKED BY: AJB
APPROVED BY: CET
DATE: JANUARY 3, 2014
JOB No: 13042-01


IL. PROJ. NO. DNV-4234 PROJ. NO. 3-17-SBGP-XX


SHEET 06 OF 14 SHEETS














# NOTES


- CABLES SHALL NOT BE LESS THAN 24" DEEP. ENCASE ISOLATION TRANSFORMER, L-823 CONNECTORS, AND 2 FOOT MINIMUM OF L-824 CABLE SLACK IN SAND BACKFILL.
- 2. LIGHT FIXTURES SHALL BE AS INDICATED IN THE TABLE ON THIS SHEET AND SHALL BE CONTINGENT UPON THE AWARD OF EACH ADDITIVE ALTERNATE.
- 3. UNIT DUCT SHALL BE TERMINATED AT L-823 CONNECTORS AND SEALED TO MAKE WATERTIGHT.
- DO NOT INSTALL ANGLE IRON STAKE BY DRIVING. MAKE ELECTRICAL CONNECTIONS AND BACKFILL AROUND THE STAKE WITH EARTH PASSING THE 1-INCH SIEVE. COMPACT AS REQUIRED TO PROVIDE FIRM SUPPORT FOR STAKE, AND TO THE SATISFACTION OF THE
- 5. COUNTERPOISE SHALL BE INSTALLED HALF WAY BETWEEN THE NEW EDGE LIGHT CIRCUIT AND THE EDGE OF THE RUNWAY/TAXIWAY PAVEMENT.
- SEE VEGETATION CONTROL RING DETAIL ON ELECTRICAL DETAILS SHEET 2 TO BE PLACED AROUND EACH LIGHT.

# **NOTES**

- 1. THE LIGHT FIXTURE SHALL BE BONDED TO THE LIGHT BASE INTERNAL GROUND LUG VIA A #6 AWG STRANDED COPPER WIRE RATED FOR 600 VOLTS WITH GREEN XHHW INSULATION. THE GROUND WIRE LENGTH SHALL BE SUFFICIENT TO ALLOW THE REMOVAL OF THE LIGHT FIXTURE FROM THE LIGHT BASE FOR ROUTINE MAINTENANCE. SEE THE LIGHT FIXTURE MANUFACTURER'S INSTRUCTIONS FOR PROPER METHODS OF ATTACHING THIS
- 2. LIGHT FIXTURES SHALL BE AS INDICATED IN THE TABLE ON THIS SHEET AND SHALL BE CONTINGENT UPON THE AWARD OF EACH ADDITIVE ALTERNATE.
- 3. UNIT DUCT SHALL BE TERMINATED AT L-823 CONNECTORS AND SEALED TO MAKE WATERTIGHT.
- 4. COUNTERPOISE SHALL BE INSTALLED HALF WAY BETWEEN THE NEW EDGE LIGHT CIRCUIT AND THE EDGE OF THE RUNWAY/TAXIWAY PAVEMENT.
- 5. SEE VEGETATION CONTROL RING DETAIL ON ELECTRICAL DETAILS SHEET 2 TO BE PLACED AROUND EACH LIGHT.

LIGHT DESCRIPTION	FAA LIGHT FIXTURE TYPE	LAMP DESCRIPTION	TRANSFORMER TYPE	WATTAGE	TRANSFORMER PRI/SEC	CONTRACT
MEDIUM INTENSITY RUNWAY LIGHT	L-861	INCAN. 6.6A	L-830-1	30/45	6.6A/6.6A	BASE BID
MEDIUM INTENSITY RUNWAY LIGHT (LED)	L-861(L)	LED W/HEATER	L-830-1	30/45	6.6A/6.6A	ADD. ALT. 3
MEDIUM INTENSITY TAXIWAY LIGHT	L-861T	INCAN. 6.6A	L-830-1	30/45	6.6A/6.6A	ADD. ALT. 1
MEDIUM INTENSITY TAXIWAY LIGHT (LED)	L-861T(L)	LED W/HEATER	L-830-1	30/45*	6.6A/6.6A	ADD. ALT. 3

\*NOTE: WATTAGE MAY BE 20/25 AS RECOMMENDED BY THE MANUFACTURER.




NOTES:

1. CONTRACTOR SHALL CONNECT HOMERUN CABLES TO XFMR & SINGLE CONNECTOR IN UNIT DUCT W/ L-823 CONNECTORS IN PROPOSED BASE MOUNTED LIGHT.

2. CONTRACTOR SHALL PROVIDE ADDITIONAL HUB ON EDGE LIGHT CAN.

**SCHEMATIC** N.T.S.



# LIGHT IDENTIFICATION DETAIL N.T.S.


# NOTES

INSTALL A NONCORROSIVE DISC OF 2" MINIMUM DIAMETER WITH THE NUMBER PERMANENTLY STAMPED, CUT OUT, OR ENGRAVED UNDER THE HEAD OF THE BASE PLATE BOLT OR ATTACHED TO LIGHT FLANGE WITH SET SCREW.

LEGENDS SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY. CONTRACTOR TO COORDINATE LEGEND WITH AIRPORT.

THE CONTRACTOR SHALL NUMBER THE EXISTING/PROPOSED LIGHTS AND SIGNS IN EACH CIRCUIT STARTING AT THE HOMERUN CONTINUING AROUND THE ENTIRE CIRCUIT BACK TO THE HOMERUN.

AIRFIELD SIGNS SHALL BE TAGGED & NUMBERED.



# **VE049 REVISIONS** NUMBER BY

(:\DanvilleAp\1304201\Draw\Sheets FILE: ELECDETL1.dwg UPDATE BY: TJ Heavisides PLOT DATE: 1/13/2014 10:49 AM

DATE

S

DETAIL

ELECTRICAL

THIS BAR IS EQUAL TO 2' AT FULL SCALE (34X22).

AIRPORT AUTHORITY IONAL AIRPORT, ILLINOIS

RUNWAY N O LIGHTS REGIONAL A **EHABILITATE** VERMILION R VERMI

CRAWFO


JOB No:

DESIGN BY: TJH DRAWN BY: CMT CHECKED BY AJB APPROVED BY: CET JANUARY 3, 2014

> IL. PROJ. NO. DNV-4234 PROJ. NO. 3-17-SBGP-XX

13042-01

SHEET 12 OF 14 SHEETS



# SIGNAGE SCHEDULE


	5.5. #.152 55. 122 522							
SIGN#	SIDE	NEW SIGN LEGEND	WHITE WITH BLACK OUTLINE ON RED BACKGROUND	BLACK LEGEND ON YELLOW BACKGROUND	YELLOW LEGEND ON BLACK BACKGROUND	NUMBER OF CHARACTERS	NEW POWER CIRCUIT	NOTES
1	NE SW	B 16	16		В	3	RWY 16/34	NEW SIGN
2	N S	← B		← в		2	RWY 16/34	NEW SIGN
3	N S	$_{\text{A}}\rightarrow$		$A  \longrightarrow $		2	RWY 16/34	NEW SIGN
4	N S	<b>←</b> A		<b>←</b> A		2	RWY 16/34	NEW SIGN
5	N S	21-3	21-3			4	RWY 3/21	NEW SIGN
6	NE SW	34-16	34-16			5	RWY 16/34	NEW SIGN
7	N S	3-21	3-21			4	RWY 3/21	NEW SIGN
8	N S	$D \to$		extstyle  o		2	RWY 16/34	NEW SIGN
9	E W	D 34	34		D	3	RWY 16/34	NEW SIGN
10	NW SE	34 <b>↑</b> D 3−21	3-21	34 ↑	D	5	RWY 3/21	NEW SIGN (ADD. ALT. 1)


# AIRFIELD SIGN NOTES


- 1. TRANSFORMER WATTAGE SHALL BE AS REQUIRED BY SIGN MANUFACTURER.
- 2. SIGN LEGEND SHALL BE AS SHOWN IN THE PLANS.
- 3. SIGNS SHALL BE SIZE 2, STYLE 2 OR 3 , CLASS 2.
- 4. SEE "NEW BASE MOUNTED EDGE LIGHT" DETAIL FOR GROUNDING DETAILS.
- 5. RUNWAY DISTANCE REMAINING SIGNS SHALL BE SIZE "X" SIGNS.

# NOTES


- SIGN SCHEDULE MAY BE SUBJECT TO FAA APPROVAL OF THE SIGNAGE PLAN.
- 2. CHANGES TO NEW LEGENDS MAY OCCUR SUBJECT TO 1 ABOVE.
- 3. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS WITH NEW LEGENDS FOR APPROVAL PRIOR TO STARTING MANUFACTURE.
- 4. EXISTING SIGNS ARE LUMACURVE.
- 5. RUNWAY 3/21 CIRCUIT IS A STYLE 3 CIRCUIT. ALL OTHER SIGNS NOT INSTALLED ON THE RUNWAY 3/21 CIRCUIT SHALL BE STYLE 2.







# SECTION B-B



# **ELECTRICAL CONNECTION DETAIL**

T.S.

11....

**VE049** REVISIONS BY DATE THIS BAR IS EQUAL TO 2' AT FULL SCALE (34X22). VERMILION REGIONAL AIRPORT AUTHORITY VERMILION REGIONAL AIRPORT DANVILLE, ILLINOIS SCHEDUL RUNWAY N O AND LIGHTS DETAIL REHABILITATE SIGN CRAWFORD, CONSULTING DESIGN BY: TJH DRAWN BY: CMT CHECKED BY: AJB APPROVED BY: JANUARY 3, 2014 JOB No: 13042-01 IL. PROJ. NO. DNV-4234 PROJ. NO. 3-17-SBGP-XX SHEET 14 OF 14 SHEETS

FILE: SIGNDETL.dwg UPDATE BY: TJ Heavisides PLOT DATE: 1/13/2014 10:49 AM