

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000-2A	DRAINAGE 7007
20101100	TREE TRUNK PROTECTION	EACH	5		5
20200100	EARTH EXCAVATION	CU YD	5		5
20201006	GRADING AND SHAPING SHOULDERS	UNIT	54	54	
20800150	TRENCH BACKFILL	CU YD	313		313
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	150	150	
25000300	SEEDING, CLASS 3	ACRE	0.1		0.1
25100630	EROSION CONTROL BLANKET	SQ YD	108		108
25200110	SODDING, SALT TOLERANT	SQ YD	150	150	
25200700	SODDING, SPECIAL	SQ YD	40		40
28000400	PERIMETER EROSION BARRIER	FOOT	19,000		19,000
28000510	INLET FILTERS	EACH	4		4
28100105	STONE RIPRAP, CLASS A3	SQ YD	4		4
28200200	FILTER FABRIC	SQ YD	4		4
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	77		77
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	195	33	162
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	143	35	108
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	56.1	56	0.1
40600300	AGGREGATE (PRIME COAT)	TON	278	278	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	104	104	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	25	25	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,198	1,198	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	240	240	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	15		15
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	23	4	19
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6,792	6,780	12
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	17	17	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	500	500	
44000100	PAVEMENT REMOVAL	SQ YD	77		77
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	69,160	69,160	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	212	50	162
44000600	SIDEWALK REMOVAL	SQ FT	500	500	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	900	900	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1,450	1,450	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	680	680	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	450	450	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	100	100	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	165	165	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1		1
55040340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	340		340
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,500	2,500	

* DENOTES SPECIALTY ITEM



Ciiorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = alou	DESIGNED - AL	REVISED -
	DRAWN - AL	REVISED -
PLOT SCALE = 1:2000' / 1 IN.	CHECKED - SNS	REVISED -
PLOT DATE = 12/15/2009	DATE - 12/11/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 7 /159TH STREET
IL 53 (INDEPENDENCE BLVD) TO I-355 (VETERANS MEMORIAL TOLLWAY)
SUMMARY OF QUANTITIES
SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	(535 B-6R & 536) RS-4	WILL	35	4
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60H62	

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000-2A	DRAINAGE 7007
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3		3
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1		1
60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	65	65	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	227		227
63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	25		25
63200310	GUARDRAIL REMOVAL	FOOT	25		25
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,330	7,330	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3,900	3,900	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	78,230	78,230	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	21,270	21,270	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,020	1,020	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	7,110	7,110	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2,850	2,850	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18,100	18,100	
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,300	1,300	
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	44,000	44,000	
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	7,090	7,090	
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	340	340	
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,370	2,370	
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	950	950	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	820	820	
78300200	RAISED REFLECTIVE PAVEMENT_MARKER REMOVAL	EACH	780	780	
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	4,050	4,050	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103	
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,730	2,730	
XX005656	INLET FILTER CLEANING	EACH	4		4
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	105	105	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	