

SIGNING PLAN NOTES:

- 1. REMOVE SIGN PANEL ASSEMBLY TYPE A, REMOVE SIGN PANEL TYPE 1, ORNAMENTAL STREET SIGN POST, COMPLETE, RETURN SIGN BLADES TO CITY PUBLIC WORKS. SEE DETAIL 6, SHEET 51, SPECIAL PROVISIONS AND SIGN SCHEDULE
- 2. REMOVE SIGN PANEL ASSEMBLY TYPE A OR TYPE B, REMOVE SIGN PANEL-TYPE 1 OR TYPE 2, RELOCATE SIGN PANEL ASSEMBLY- TYPE A OR TYPE B. RELOCATE SIGN PANEL- TYPE 1 OR TYPE 2, SIGN POST (SPECIAL) - FURNISH AND INSTALL DECORATIVE POSTS FOR REGULATORY SIGNS. REPLACE ALL POSTS WITH DECORATIVE ROUND BLACK POZ-LOC POLES. ALL EXISTING SIGN PANELS TO BE REMOVED AND CLEANED, THEN TO HAVE BLACK 3M VINYL APPLIED TO THE BACK AND INSTALLED ON NEW POLES. SEE DETAIL 5, SHEET 51. THE SIGN SCHEDULE AND PLANS.
- 3. REMOVE SIGN PANEL TYPE 1 OR TYPE 2, RELOCATE SIGN PANEL TYPE 1 OR TYPE 2SIGNS ATTACHED TO LIGHTPOLES AND TRAFFIC POSTS TO BE REMOVED, CLEANED AND THEN TO HAVE BLACK 3M VINYL APPLIED TO BACK, AND BE RE-ATTACHED USING NEW BLACK STAINLESS STEEL BANDING STRAPS AND HARDWARE. SEE DETAIL 5, SHEET 51, THE SIGN SCHEDULE AND PLANS.

CONSTRUCTION GENERAL NOTES:

A. CONTRACTOR SHALL TAKE ALL PRECAUTIONS NOT TO DAMAGE UTILITIES. ANY AND ALL DAMAGE WILL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER. EXISTING UTILITIES SHOWN ON THE PLAN ARE FOR REFERENCE ONLY AND ARE NOT GUARANTEED TO BE ACCURATE OR COMPLETE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE AND VERIFY ALL UTILITIES WITHIN THE PROJECT LIMITS AND TO ADJUST ACCORDINGLY.


STREET SIGN LEGEND

*SEE SHEET 5 FOR SIGN SCHEDULE, NOTE WHEN MULTIPLE SIGNS ARE LISTED, THE FIRST LETTER IS THE UPPER MOUNTED SIGN



J, EE SIGN ON BLACK DECORATIVE POST, SEE NOTE 22 THIS SHEET, DETAIL 5 SHEET 51, AND THE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION

SIGN MOUNTED ON WOOD POLE, TRAFFIC LIGHT POLE OR STREET LIGHT POLE, SEE NOTE 23 THIS SHEET, DETAIL 5 SHEET 51, AND THE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION



- SITE SURVEY PROVIDED BY: ROBINSON ENGINEERING, INC. 17000 South Park Avenue South Holland, Illinois 60473 (708) 331-6700
- * SEE ALSO CONSTRUCTION PLAN SHEETS 20-33 AND **GENERAL NOTES SHEET 3**

FILE NAME = pri_signing plan - IDOT P22	LICED NAME -	DESIGNED — BCL REVISED —						F.A.P.			TOTAL	
TILE INVINCE - DIT_SIGNING Plant - IDO1 F22	USER NAME =	DESIGNED BCL	REVISED		SIGNING PLAN				DTE	SECTION	COUNTY	SHEETS
PLANNING RESOURCES INC. 400 West Liberty Price Price Office See 1225 Whogens, Blant digital Price See 1225		CHECKED KLG	REVISED	STATE OF ILLINOIS				TIL.			STILLIO	
	PLOT SCALE = 1°= 20'		REVISED —	DEPARTMENT OF TRANSPORTATION				29	09-00056-00-LS	COOK	62	
		DRAWN — BCL/RJA							CONTRACT NO. 633			
	PLOT DATE = 12/17/2009	CHECKED KLG/LMV	REVISED		SCALE: 1"= 20"	SHEET NO. 33C OF 62 SHEETS	STA. 1+00	TO STA. 27+00	FED. BOAD D	IST. NO. 1 ILLINOIS FE		
			· · · · · · · · · · · · · · · · · · ·									,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,