
DO NOT USE WITH DISTRICT FOR EXPOSED PIPE".

CONCRETE THRUST BLOCK BILL OF MATERIALS

PIPE SIZE	Х	Y	CLASS SI CONCRETE cu. yd. (m³)
12(300)	24(600)	24(600)	0.2(0.2)
15(375)	27(675)	27(675)	0.3(0.2)
18(450)	30(750)	30(750)	0.3(0.2)
24(600)	36(900)	36(900)	0.4(0.3)
30(750)	3′-6″ (1.07m)	3′-6′′ (1.07m)	0.8(0.6)

The contract unit price each for CONCRETE THRUST BLOCK shall include the cost of excavation, CLASS SI CONCRETE and compacted backfill.



CALC. BY: DATE: CHECKED BY:_

QUANTITY CALCULATIONS ARE ON FILE AT THE DISTRICT 4 OFFICE; BUREAU OF PROJECT IMPLEMENTATION; DOCUMENTATION SECTION

FILE NAME =

QUANTITIES

.. VD:strict Standards 604-611.dgn

USER NAME = Plotted by new6	DESIGNED	-	REVISED	~	
	DRAWN	-	REVISED	-	
PLOT SCALE = 100.0000 '/ IN.	CHECKED	*	REVISED	-	
PLOT DATE = 7/29/2008	DATE	*	REVISED	*	

CONCRETE THRUST BLOCKS

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

All dimensions are in inches (millimeters) unless otherwise noted.

	UAIL		<u> </u>
	1-1-97	RENUM. J-10.04, NEW REVISION BOX.	T.P.
		ADDED QUANTITY CALCULATION BOX.	
	10-16-06	REVISED TO 2007 SPEC.	M.A.
)			
•			T
			I
_	11	7074	CHECT

609001-D4

	E	DISTRIC	T STAI	VDARDS	
US	150	OVER	LITTLE	FARM	CREEK

SHEET NO. OF SHEETS STA.

A.U. TE.	SECTION			COUNTY	TOTAL	SHEET NO.		
757	(1058)	BR-2,	(1058)	BR-3	TAZEWELL	113	133	
					CONTRACT	NO. 6	8086	