Stage removal line 1'-6" Stage const. line —Embankment (See roadway plans) Limits of select fill — -Geotextile soil reinforcement, typ. 1'-0" 3'-0"

SECTION A-A

Temp. soil retention system

IL Route 108 &

Stage const. line


STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

−1'' ¢ Steel pipe


Wood wedge

to maintain


vertical face




1. Place form brace system on completed reinforcement level; back from the finished fabric face a distance of 13 to 2 the geotextile reinforcement spacing.



2. Position fabric so that the required geotextile re-embedment length extends over the top of the form brace and the design reinforcement width is placed with no slack against the previous level.




3. Compact select fill material in lifts to final lift height, create (±3") depression in zone where re-embedment length will be located and place additional height of compacted select fill against form brace.



4. Fold geotextile re-embedment length back over form brace into zone where depression was made in select fill and place additional select fill (±3") to embed geotextile and bring to final lift height.



5. Pull form brace outward allowing geotextile face to slightly readjust to form tight round face level with plan reinforcement spacing.



2'' x 14'' (nominal)

SECTION A-A

timber planks

38" x 3'-0"

1'' ♦ hole

to aid in

3g'' Stiffener

3'-0"

TEMPORARY GEOTEXTILE WALL CONSTRUCTION SEQUENCE

The geotextile soil reinforcement shall have a minimum allowable tensile strength (T min.) of 20 lb./in. as determined by the procedure described in the Special Provision. The computations supporting the determination of (T min.) shall be submitted to the engineer for approval.

PLAN

Sta. 1068+35.00 Elev. 519.07

Stage removal line-

DESIGNED Jay D. Edwards Mike D. Rolape CHECKED h.t. duong DRAWN JDE/MDR CHECKED

25'-8" Stage I soil retention syste

Limits of exist. structure

> TEMPORARY GEOTEXTILE FORM BRACE DETAIL

PLAN

This is a suggested detail, the Contractor is responsible for the design of the form brace system to be used.

GEOTEXTILE RETAINING WALL STRUCTURE NO. 031-2012

	SHEET NO.3	F.A.P. RTE.	SECTION			COUNTY	TOTAL SHEETS	SHEET NO.	
		761	104-BR-2			GREENE	82.	26	
	11 SHEETS					CONTRACT	NTRACT NO. 76987		
		FED. ROAD DIST. NO ILLINOIS FED. AI) PROJECT				

0312012-76987.dgn 01/15/2009 2:35:48 PM