DATE					
ВҮ					
	SURVEYED	PLOTTED	NOTE BOOK TEMPI ATE	ARFAS	AREAS CHECKED
INTOTOO	CALCLINAL SI RVEYED	SURVEY	NOTE BOOK		NO.

LEGEND

5"	EVERGREEN (5" DIA)		FOUND CONCRETE MONUMENT	W	WATER LINE
8″	DECIDUOUS (8" DIA)	o ^w w	WATER METER		GAS LINE
Ø	EVERGREEN SHRUB	O ^{GM}	GAS METER	OHE	OVERHEAD ELECTRIC LINE
•	SHRUB	Owv	WATER VALVE	T	TELEPHONE LINE
abla	FIRE HYDRANT	OGV	GAS VALVE	CTV	CABLE TV LINE
þ	SIGN	(TBA)	TO BE ADJUSTED		STORM SEWER
•	BOLLARD	(TBR)	TO BE REMOVED		SANITARY SEWER
	POWER POLE	(TBR&R)	TO BE REMOVED & RELOCATED		LIGHT POLE
	POWER POLE WITH DOWN GUY	(TBR&RBO)	TO BE REMOVED & RELOCATED BY OTHERS	0	STORM SEWER MANHOLE
—x——x——	FENCE	DND	DO NOT DISTURB	0	SANITARY SEWER MANHOLE
	BENCH MARK	P	PROPERTY LINE	0	CATCH BASIN
«~-~»	DITCH/SWALE		EXIST R.O.W. LINE	Constant	INLET
P	EXISTING MAILBOX	\otimes	WOOD POST		

GENERAL NOTES:

ILLINOIS STATE LAW REQUIRES A 48-HR NOTICE BE CIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING JULILE. OR FOR NON-JULILE. MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS. HIGHWAY STANDARD 424001.

STORM / SANITARY SEWERS

 AMEREN IP 2600 N. CENTER STREET P.O. BOX 378 MARYVILLE, IL 62062 (800) 750-6890 GAS

* AT&T / SBC 203 GOETHE COLLINSVILLE, IL 62234 (618) 233-3191

CABLE TELEVISION

TELEPHONE

WATER

• CHARTER COMMUNICATIONS, INC 200 W. DIVISION STREET MARYVILLE, IL 62062 (618) 345-8121

• SOUTHWESTERN ELECTRIC COMPANY P.O. BOX 549 GREENVILLE, IL 62246 (618) 830-9362 FLECTRIC

* IL. AMERICAN WATER COMPANY 100 N. WATERWORKS DR. P.O. BOX 24020 BELLEYILLE, IL 62223 (618) 227-7450

(MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY*. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY) FOR UTILITY LOCATION PURPOSES, THIS PROJECT IS LOCATED IN SECTIONS 35 & 36 OF TOWNSHIP 4 NORTH, RANGE 8 WEST OF THE THIRD PRINCIPAL MERIDIAN.

TREES SHALL BE PRESERVED THROUGH OUT THIS SECTION AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER. REMOVAL OF AGGREGATE MATERIAL AND OIL AND CHIP BITUMINOUS MATERIAL SHALL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

THE CONTRACTOR SHALL CONSTRUCT PAVEMENT SO THAT FLOW ALONG CURBS AND/OR GUITERS IS MAINTAINED, INCLUDING FLOW THROUGH INTERSECTIONS, AROUND CURB RETURNS AND TO EXISTING INLETS.

THE TOP OF PROPOSED P.C.C. CURB/CURB AND GUTTER SHALL BE CONSTRUCTED AT THE SAME ELEVATION AS THE TOP OF THE EXISTING CURB/CURB AND GUTTER. THIS SHALL BE DONE IN ORDER TO MAINTAIN THE EXISTING DRAINAGE PATTERN TO THE EXISTING INLETS AND TO MAINTAIN THE EXISTING PROFILE.

THE CONTRACTOR SHALL ADJUST WATER VALVES, AND OTHER ITEMS LOCATED WITHIN THE EXISTING ROADWAY TO MATCH THE PROPOSED ROADWAY SURFACE. THIS WORK SHALL BE CONSIDERED INCLUDED IN THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ALL AREAS DISTURBED WITH IN THE CONSTRUCTION LIMITS SHALL BE SEEDED WITH CLASS I SEEDING AND MULCH, AS DIRECTED BY THE ENGINNER, AND SHALL BE PART OF CONTRACT. ALL DISTURBED AREAS BEYOUND THE CONSTRUCTION LIMITS ARE THE RESPONSIBILITY OF THE CONTRACTOR.

A CURB RAMP SHALL BE CONSTRUCTED AT ALL INTERSECTIONS WHERE SIDEWALK IS PRESENT. RAMP SHALL BE CONSTRUCTED ACCORDING TO

CHANGES IN THE VERTICAL OR HORIZONTAL DIMENSIONS OF GUTTERS, CURBS, OR CURB AND GUTTERS, WHEN TRANSITIONS FROM ONE TYPE TO ANOTHER AS SHOWN IN THE PLANS, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR THE TYPE DESIGNATED IN THE PLAN SCHEDULE.

THE THICKNESS OF H-M-A MIXTURES SHOWN ON THE PLANS IS THE AVERAGE THICKNESS, DEVIATIONS FROM THE AVERAGE THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE H-M-A MIXTURE IS PLACED.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

WHERE PROPOSED CONCRETE PAVEMENT OR PCC CURB AND GUTTER IS TO BE CONSTRUCTED ADJACENT TO EXISTING CONCRETE PAVEMENT OR PCC CURB AND GUTTER, THE CONTRATOR SHALL DRILL AND GROUT NO. 6 X 30 EPOXY COATED THE BARS AT 30" CENTERS. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF PCC PAVEMENT 8" (JOINTED) OR COMBINATION CONCRETE CURB AND GUTTER AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE REMOVAL OF ANY CURB/CURB AND GUTTER SHALL ALSO INCLUDE THE DISCONDECTION OF THE EXISTING CURB/CURB AND GUTTER FROM ANY REINFORCEMENT OR COLLATERAL MATERIAL THAT MAY BE PRESENTLY ATTACHED. THERE SHALL NOT BE ANY ADDITIONAL RENUMERATION BUT THIS WORK SHALL BE CONSIDERED AS INCLUDED IN THE REMOVAL ITEM.

THE FOLLOWING CONSTANTS WERE USED IN THE CALCULATION OF QUANTITIES

HOT-MIX ASPHALT
BITUMINOUS MATERIALS (PRIME COAT)
112 LBS/S.Y./INCH
0.07 GAL/S.Y. (PAVED SURFACE)
0.25 GAL/S.Y. (AGGREGATE SURFACE)

AGGREGATE (PRIME COAT) GRANULAR MATERIALS

2 TONS/ACRE 3 LBS/S.Y. 2.05 TONS/C.Y.

ALL MANHOLE AND INLET LOCATIONS NOTED IN THE PLANS REFER TO THE BARREL SECTION OF THE STRUCTURES.

"ROAD CONSTRUCTION AHEAD" SIGNS (48"X48") SHALL BE PLACED AT THE BEGINNING AND END OF THE PROJECT PLUS THE INTERSECTING SIDE ROADS, AND WILL BE CONSIDERED INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR AN ON-SITE INSPECTION PRIOR TO SUBMITTING A BID ON THIS PROJECT. UPON RECEIPT OF A BID, IT SHALL BE ASSUMED THAT THE CONTRACTOR IS FULLY FAMILIAR WITH

OPEN STOCKPILING OF H-M-A MIXTURES AT TRANSFER POINTS, WHETHER JOB SITE OR PLANT SITE, WILL NOT BE PERMITTED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE FIRE DEPARTMENT AND POLICE DEPARTMENT OF THE RESPECTIVE MUNICIPALITY ANY TIME NORMAL TRAFFIC FLOW ON ANY STREET OR ROAD IS TO BE INTERRUPTED, HOWEVER BRIEFLY.

VILLAGE OF GLEN CARBON POLICE DEPARTMENT 618-288-7226 (NON-EMERGENCY) VILLAGE OF GLEN CARBON FIRE DEPARTMENT 618-288-1220 (NON-EMERGENCY) MADISON COUNTY SHERIFF DEPARTMENT 618-692-4433 (NON-EMERGENCY)

DWG. NO.

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT: PIONEER TRAIL & JO LEE DRIVE MIXTURE USE AC/PG RAP % (MAX) BINDER PG 64-22 DESIGN AIR VOIDS
MIX COMPOSITION
(GRADATION MIXTURE) 4.0% @ Ndes=70 4.0% @ Ndes=70 FRICTION AGG MIXTURE C MIXTURE B

RTE. SECTION

CONTRACT NO. 97368

COUNTY 8899 05-00026-01-RP MADISON 81 2

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

CONSULTING EMOINEERS AND LAND SURVEYORS 2108 Stein Street. P.A. Dat 1252 2108 Stein Street. P.A. Dat 1252				GENERAL NOTES F.A.U. ROUTE 8899 GLEN CROSSING ROAD PHASE 2 GLEN CARBON, ILLINOIS SECTION No. 05-40026-01-RP				
			SCALE:					
NO.	DATE	BY	REMARKS		N.T.S.			
				DSN. BY:	BFK	DATE:	11/1/08	SHI
				DWN. BY:	JJB	DATE:	11/1/08	1 -
				CHK'D:	BFK	DATE:	11/1/08	1 4

SHEET 2

JOB NO. E070614B DGN. NAME: GENNOTES OF 81 SHTS