

STRUCTURE REMOVAL AND ADJUSTMENT SCHEDULE

LOCATION	INLET TO BE REMOVED (EACH)	MANHOLE TO BE ADJUSTED (EACH)	INLET TO BE ADJUSTED WITH NEW TYPE 1 F&CL (EACH)
GLEN CROSSING ROAD - PHASE 2			
STA. 50+09.35 - 17.89' LT		1	
STA. 53+94.78 - 15.90' LT		1	
STA. 74+98.97 - 19.92' LT			1
STA. 75+27.04 - 15.72' RT	1		
TOTAL	1	2	1

DRIVEWAY PAVEMENT REMOVAL SCHEDULE

LOCATION	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	CONCRETE REMOVAL (CU YD)
GLEN CROSSING ROAD - PHASE 2		
STA. 37+09.76 LT	61.6	
STA. 38+66.95 LT	53.9	
STA. 38+77.06 RT	36.7	
STA. 44+67.85 LT	24.8	
STA. 50+08.08 LT	30.3	
STA. 52+57.87 RT	62.0	
STA. 54+90.53 LT	37.0	
STA. 55+19.44 RT	54.6	
STA. 56+74.96 LT	208.5	
STA. 61+28.47 LT	34.0	
STA. 61+91.44 LT	20.6	44.1
STA. 62+97.75 RT	67.5	
STA. 63+01.68 LT	49.7	
STA. 64+25.74 LT	20.4	
STA. 65+29.50 RT	49.2	
STA. 66+74.02 RT	196.3	
STA. 70+26.86 RT	218.3	
STA. 74+73.21 RT	216.3	
TOTAL	1442	44

SIDEWALK REMOVAL SCHEDULE

LOCATION	SIDEWALK REMOVAL (SQ FT)
GLEN CROSSING ROAD - PHASE 2	
STA. 66+38.21 - 25.04' RT TO STA. 66+58.62 - 48.40' RT	322.9
STA. 74+96.65 - 22.98' RT TO STA. 75+38.45 - 22.68' RT	191.6
TOTAL	515

PAVEMENT REMOVAL SCHEDULE


LOCATION	PAVEMENT REMOVAL (SQ YD)
GLEN CROSSING ROAD - PHASE 2	
STA. 36+81.24 TO STA. 38+81.24	539
STA. 72+71.42 TO STA. 75+50.00	643
JO LEE DRIVE	
STA. 200+10.83 TO STA. 200+26.07	50
TOTAL	1182

CURB REMOVAL SCHEDULE

LOCATION	CURB TYPE B (FOOT)
GLEN CROSSING ROAD - PHASE 2	
STA. 66+42.99 - 15.80' RT TO STA. 66+59.12 - 48.39' RT	38
STA. 66+88.91 - 48.61' RT TO STA. 67+06.68 - 14.59' RT	40
STA. 69+98.36 - 17.27' RT TO STA. 70+12.80 - 50.02' RT	37
STA. 70+44.34 - 47.84' RT TO STA. 70+67.99 - 16.94' RT	40
STA. 74+31.50 - 11.20' RT TO STA. 74+58.46 - 63.08' RT	67
STA. 74+92.30 - 61.94' RT TO STA. 75+16.60 - 13.13' RT	63
TOTAL	285

DATE	
BY	
SURVEYED	
PLOTTED	
NOTE BOOK	
TEMPLATE	
AREAS	
CHECKED	
NO.	

DATE	
BY	
ORIGINAL SURVEYED	
PLOTTED	
NOTE BOOK	
TEMPLATE	
AREAS	
CHECKED	
NO.	

 Juneau Associates, Inc. P.C. CONSULTING ENGINEERS AND LAND SURVEYORS 2100 Stone Street, P.O. Box 1325 Rockton, IL 61151-0132 Phone: (815) 397-1400 / (815) 397-5532 Fax: (815) 397-5541	QUANTITY SCHEDULES F.A.U. ROUTE 8899 GLEN CROSSING ROAD PHASE 2 GLEN CARBON, ILLINOIS SECTION No. 07-00026-02-RP																					
	SCALE: N.T.S.																					
<table border="1"> <thead> <tr> <th colspan="4">REVISIONS</th> </tr> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> <th>REMARKS</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>	REVISIONS				NO.	DATE	BY	REMARKS													DSN. BY: BFK DATE: 2/15/08 DWN. BY: JJB DATE: 2/15/08 CHK'D: BFK DATE: 2/15/08	SHEET 19 OF 81 SHTS
REVISIONS																						
NO.	DATE	BY	REMARKS																			
DWG. NO.	JOB NO. E070614B DGN. NAME: oomsch																					