



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 25, 2020

SUBJECT: FAU 2593 (Woodward Avenue)
Section 19-00082-00-RS (Woodridge)
DuPage County
Contract No. 61G27
Item 120
March 6, 2020 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised sheets 3, 20 - 24 of the Plans**
- 3. Revised the Table of Contents**
- 4. Revised page 38 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

STATE OF ILLINOIS
SPECIAL PROVISIONS
WOODWARD AVENUE RESURFACING

TABLE OF CONTENTS

PROJECT LOCATION	1
PROJECT DESCRIPTION.....	1
MAINTENANCE OF ROADWAYS.....	1
TRAFFIC CONTROL PLAN	2
ADJUSTMENTS AND RECONSTRUCTIONS.....	2
PUBLIC CONVENIENCE AND SAFETY (DIST 1).....	3
TEMPORARY INFORMATION SIGNING	4
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (DISTRICT 1).....	5
FRICTION AGGREGATE (D-1)	6
GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (D-1).....	9
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D-1).....	11
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (D-1)	21
AGGREGATE SUBGRADE IMPROVEMENT (D-1)	31
STATUS OF UTILITIES (D-1).....	34
CONSTRUCTION LAYOUT SPECIAL FOR RESURFACING WITH ADA AND STAND ALONE ADA (D-1)	35
AVAILABLE REPORTS	36
DIRT ON PAVEMENT OR STRUCTURES	37
TREE ROOT PRUNING.....	37
SODDING, SALT TOLERANT	38
CLASS D PATCHES	38
WATER SUPPLY/USAGE	38
CONSTRUCTION OPERATIONS.....	38
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	39
SECTION 602, 603 AND 604 – ADJUSTING FRAMES AND GRATES OF DRAINAGE AND UTILITY STRUCTURES AND FRAMES, GRATES, AND MEDIAN INLETS	41
SANITARY MANHOLES TO BE ADJUSTED, SPECIAL	41
TACTILE/DETECTABLE WARNING SURFACE.....	42
DRIVEWAY REMOVAL AND REPLACEMENT	42
PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL.....	42
FRAMES AND LIDS TO BE ADJUSTED (SPECIAL).....	43
CONCRETE CURB, TYPE B (SPECIAL)	44
HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3”	44
HOT-MIX ASPHALT DRIVEWAY PAVEMENT REMOVAL.....	44
DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED (SPECIAL)	45
DRAINAGE STRUCTURES TO BE CLEANED	46
DETECTOR LOOP REPLACEMENT AND/OR INSTALLATION (ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS)	47

"A copy of a letter of qualification shall be provided to the Engineer for inspection."

Add the following after the second paragraph of Article 201.06 of the Standard Specifications:

"All cut roots exposed shall be cleared from the site and disposed of without any additional compensation for the work."

~~SODDING, SALT TOLERANT~~

~~Work shall be in accordance with Section 252 of the Standard Specifications, except that the sod shall be rolled to promote better soil contact prior to watering.~~

~~Add the following after the first paragraph of Article 252.01 of the Standard Specifications.~~

~~"All areas in that portion of the parkway adjacent to curb replacement sections, sidewalk replacement sections, sanitary or storm sewer replacement, or water main installations disturbed during construction shall be restored."~~

~~**Method of Measurement and Basis of Payment.** This work shall be paid for as Sodding, Salt Tolerant per square yard. Topsoil shall be paid for separately as Topsoil Furnish and Place, 4".~~

CLASS D PATCHES

Work shall be in accordance to Section 442 of the Standard Specifications except for:

The cost of full-depth machine sawing shall be included in the unit price of this item and no additional compensation will be given for this work.

Revise the fourth paragraph of Article 442.05 of the Standard Specification to read:

"The unit cost of this item shall include the disposal of materials resulting from the removal of the existing pavement and unsuitable and unstable materials.

WATER SUPPLY/USAGE

The independent use of private water spigots is strictly prohibited. The Contractor shall be responsible for obtaining water from an approved source (fire hydrant with meter attached located in at the Public Works Maintenance Yard). It is the Contractor's responsibility to obtain water at this location and complete required paperwork for tracking water usage. There is no cost to the contractor for water used as part of this Village Project.

CONSTRUCTION OPERATIONS