



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 24, 2020

SUBJECT: FAP Route 623 (US6/IL71)
Project NHPP-STP-9JWU(998)
Section (3,30X-1,2)RS-4&SW
LaSalle County
Contract No. 66J48
Item No. 150, March 6, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents to the Special Provisions.
2. Revised pages 18 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
DELAYED START OF MULTIPLE CONTRACTS.....	1
VIBRATORY ROLLER RESTRICTION	2
CROSSING STRUCTURES WITH MATERIAL TRANSFER DEVICE	2
MATERIAL TRANSFER DEVICE (BDE)	3
PERMANENT SURVEY MARKERS, TYPE I.....	4
FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) AND WATER VALVES TO BE ADJUSTED, SPECIAL	4
TRAFFIC CONTROL PLAN.....	5
EQUIPMENT ILLUMINATION	6
TEMPORARY INFORMATION SIGNING	6
LOOP DETECTOR TESTING.....	7
INDUCTIVE LOOP DETECTOR.....	8
PEDESTRIAN PUSH-BUTTON.....	9
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	9
VIDEO DETECTION SYSTEM.....	9
PREPARATION AND RESTORATION OF SIDEWALK WORK AREAS.....	18
DRAINAGE MITIGATION ON MILLING AND RESURFACING PROJECTS	19
MAXIMUM DROP-OFFS FOR TWO-LANE, TWO-WAY TRAFFIC.....	19
MODIFY EXISTING CONTROLLER AND CABINET.....	20
TRAFFIC CONTROL IN THE VICINITY OF A RAILROAD GRADE CROSSING	20
RAILROAD PROTECTIVE LIABILITY INSURANCE	21
RIGHT OF ENTRY TO ILLINOIS RAILWAY PROPERTY, DOT/AAR NO. 065 106 B CONTRACT 66J48.....	22
HOT – MIX ASPHALT SURFACE REMOVAL AT THE ILLINOIS RAILWAY GRADE CROSSING, DOT/AAR NO. 065 106 B.	23
RAILROAD PROTECTIVE LIABILITY INSURANCE (5 AND 10) (BDE)	24
RIGHT OF ENTRY TO CSX TRANSPORTATION PROPERTY, DOT/AAR NO. 603 811 R, CONTRACT 66J48	25
HOT – MIX ASPHALT SURFACE REMOVAL AT THE CSX TRANSPORTATION GRADE CROSSING, DOT/AAR NO. 603 811 R.	25

Revised 2/24/2020

Once all hardware is installed, connected and functional, it shall be possible to configure the video detection system for a typical 4-approach, 8-phase intersection in 15 minutes or less.

Warranty, Service, and Support, The video detection system shall be provided with the following warranty, service, and support options.

Warranty.

- The manufacturer shall warrant the video detection system for a minimum of six (6) years.

Service.

- Ongoing software support by the manufacturer will include software updates of the video sensor, communications interface panel, and management software. These updates will be provided free of charge during the warranty period. The manufacturer will maintain a program for technical support and software updates following expiration of the warranty period. This program will be available to the contracting agency in the form of a separate agreement for continuing support.

Support.

- A quick-start guide, installation guide, application notes, and other materials shall be available from the manufacturer to assist in product installation and setup for various applications. In addition, training online or in person shall be available.
- Training shall be available to personnel of the contracting agency in application design, operation, setup, and maintenance of the video detection system.
- Manufacturer shall provide a tech support website, support email address and a 1-800 number for technical support.

Basis of Payment. This work will be paid for at the contract unit price EACH for VIDEO DETECTION SYSTEM COMPLETE, which price shall be payment in full for the labor and parts, including pipe extension and 3/C cable, to install a complete Video Detection System.

PREPARATION AND RESTORATION OF SIDEWALK WORK AREAS

Furnished excavation and earth excavation necessary to complete sidewalk work will not be paid for separately, but it shall be included in the cost of the sidewalk pay items.

The Contractor shall restore the sidewalk work area as specified in Article 104.06 of the Standard Specifications. All damage to mowed lawns shall be replaced with an approved sod, and all damage to unmowed fields shall be seeded. This work will not be paid for separately, but shall be included in the cost of the associated sidewalk pay items. Restoration items include, but are not limited to, furnished excavation, earth excavation, seeding, sodding, fertilizer nutrients, and erosion control blanket.

Revised 2/24/2020