LETTERING FOR NAME PLATE

STATION BUILT 200 BY STATE OF ILLINOIS RTE. SEC. FA PROJECT LOADING HS 20 STR. NO.

SEE STD. 515001

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE NOTED.

LETTERING FOR NAME PLATE

REVISED 10-15-04

89.4

TREE REPLACEMENT SCHEDULE

SECTION COUNTY 549 OGLE STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

CONTRACT NO. 64B44

90.4

CODE NUMBER	SCIENTIFIC NAME	COMMON NAME	SIZE	UNIT	QUANTITY
B2004814	MALUS SARGENTII	SARGENT CRABAPPLE	1-3/4"	EACH	15
B2005014	MALUS SNOWDRIFT	SNOWDRIFT CRABAPPLE	1-3/4"	EACH	15

MITIGATED TREES SHALL BE PLANTED ALONG FAI-39 NORTHBOUND, EAST SIDE, BETWEEN MP 111 TO MP 112 IN OGLE COUNTY LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT MULCH SHALL BE HARDWOOD WOOD CHIPS, 5 FOOT WIDTH, 4 INCHES THICK WITH WEED BARRIER FABRIC

FOR QUESTIONS PLEASE CALL RICHARD MAGGI AT (815)-284-5404

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE NOTED.

TREE REPLACEMENT SCHEDULE

STOP LINE SIGN FOR **TEMPORARY SIGNALS**



SIZE: 600(24) x 600(24)

100(4) CAPITAL LETTERS - BLACK

13(1/2) BORDER - BLACK

WHITE REFLECTIVE - TYPE AP HIGH INTENSITY PRISMATIC SHEETING

GENERAL NOTE:

THIS SIGN SHALL BE INSTALLED AT THE STOP LINE AS DIRECTED BY ENGINEER.

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE NOTED.

REVISED 8-10-05

STOP LINE SIGN FOR TEMPORARY SIGNALS

99.4