

INDEX

1	COVER
2	INDEX/STANDARDS/SIGNATURES
3-4	QUANTITIES
5	TYPICAL SECTIONS
6-13	PLAN
14-21	PAVEMENT MARKING
22	BUTT JOINT DETAILS

STANDARDS

442201-03	701311-02
701001-01	701421-01
701006-02	701426-02
701011-01	701901
701201-02	780001-01
701301-02	781001-02
701306-01	

NOTES:

SIZE AND LOCATION OF PATCHES TO BE DETERMINED IN THE FIELD BY THE RESIDENT ENGINEER.

NO PASSING ZONES TO BE FIELD VERIFIED BY THE BUREAU OF OPERATIONS. THE RESIDENT ENGINEER SHALL NOTIFY THE BUREAU OF OPERATIONS 14 DAYS PRIOR TO PERMANENT PAVEMENT MARKING.

MILLINGS FROM THIS PROJECT SHALL BE DELIVERED TO THE I.D.O.T. RIVERTON YARD - CONTACT PERSON - MICHAEL McDERMOTT (217)836-4785.

<p>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6</p>	
EXAMINED	<p>Dec 18 20 07</p> <p><i>[Signature]</i> ENGINEER OF OPERATIONS</p>
EXAMINED	<p>Dec 11 20 07</p> <p><i>[Signature]</i> ENGINEER OF PROGRAM IMPLEMENTATION</p>
EXAMINED	<p>Dec 12 20 07</p> <p><i>[Signature]</i> ENGINEER OF PROGRAM DEVELOPMENT</p>

MIXTURE REQUIREMENTS	
THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT	
MIXTURE USE(S):	H.M.A. S.C., MIX D, N70
AC/PG	BS PG 64-22
DESIGN AIR VOIDS:	4.0% @ N DESIGN = 70
MIXTURE COMP:	IL 9.5 OR 12.5
FRICTION AGG:	MIX "D"

INDEX/STANDARDS/SIGNATURES
FAU 7998 (I-55 W.F.R.)
SECTION (110X-2)RS-3
SANGAMON COUNTY