CONTRACT NO. 76961

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1780	27-1BR-1	CLINTON	69	10A
STA. 6+00	TO STA. 12+00			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SEE DETAIL SHEET NO. 22
FOR LAYOUT OF RIPRAP
SEE CROSS SECTION SHEETS
NO. 62 & 63 FOR PAY ITEMS
AND QUANTITIES.
TYPICAL FOR ALL LOCATIONS.

MATCHLINE STA 389+00 = STA 6+00

CONSTRUCTION LIMITS
HMA SHOULDER
STEEL PLATE BEAM GUARDRAIL, TYPE A
GUARDRAIL REMOVAL
BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) - 53.5 SQ YD
EARTH WIDENING FOR GUARDRAIL PLACEMENT
TBT, TYPE 6
BRIDGE APPROACH PAVEMENT 107 SQ YD
PC STA 8+29.26
PT STA 386+70.74
¢ OLD US 50
10+00 385+00
15'
13'
3'
GUARDRAIL REMOVAL
TBT, TYPE 6
STEEL PLATE BEAM GUARDRAIL, TYPE A
HMA SHOULDER
CONSTRUCTION LIMITS
EARTH WIDENING FOR GUARDRAIL PLACEMENT

MATCHLINE STA 383+00 = STA 12+00

CONSTRUCTION LIMITS
BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) - 53.5 SQ YD
GUARDRAIL REMOVAL
TBT, TYPE 6
BRIDGE APPROACH PAVEMENT 107 SQ YD
EARTH WIDENING FOR GUARDRAIL PLACEMENT
STEEL PLATE BEAM GUARDRAIL, TYPE A
HMA SHOULDER
TBT, TYPE 6
GUARDRAIL REMOVAL
STEEL PLATE BEAM GUARDRAIL, TYPE A
HMA SHOULDER
EARTH WIDENING FOR GUARDRAIL PLACEMENT
CONSTRUCTION LIMITS

PROP. CURVE ROADCL.-I
PI STA. = 5+61.66
Δ = 1° 21' 06" (LT)
D = 0° 15' 09"
R = 22,687.46'
T = 267.63'
L = 535.23'
E = 1.58'
e = -----
T.R. = -----
S.E. RUN = -----
P.C. STA = 2+94.03

EXIST. CURVE C1
PI STA. = 389+38.37
Δ = 1° 21' 06" (RT)
D = 0° 15' 09"
R = 22,687.46'
T = 267.63'
L = 535.23'
E = 1.58'
e = -----
T.R. = -----
S.E. RUN = -----
P.C. STA = 386+70.74

CHANNEL EXCAVATION
6550 CU YDS

SCALE: 1" = 20'

PROFILE

200.00' V.C.
+0.35%
+1.27%
VPI STA. 6+20.00
ELEVATION 448.35
400.00' V.C.
+1.27%
-1.34%
VPI STA. 9+20.00
ELEVATION 452.15
PROPOSED PROFILE
EXISTING PROFILE
434.00
424.00
430.00
424.50

6+00	6+50	7+00	7+50	8+00	8+50	9+00	9+50	10+00	10+50	11+00	11+50	12+00
448.28 / 448.43	448.29 / 448.58	448.32 / 448.75	448.34 / 448.94	448.37 / 449.15	448.41 / 449.37	448.40 / 449.62	448.39 / 449.86	448.39 / 450.07	448.43 / 450.26	448.51 / 450.42	448.63 / 450.56	448.62 / 450.67	448.61 / 450.75	448.60 / 450.81	448.59 / 450.84	448.58 / 450.85	448.57 / 450.83	448.56 / 450.78	448.55 / 450.71	448.54 / 450.61	448.53 / 450.49	448.36 / 450.34	448.24 / 450.16	448.14 / 449.96	448.10 / 449.73	448.06 / 449.48	448.07 / 449.22	448.08 / 448.99	448.11 / 448.77	448.13 / 448.58

460 455 450 445 440 435 430 425 420

435.89 435.50 436.32 436.92 431.96 429.78 423.90 424.62

PLOT DATE = 2/25/2008
FILE NAME = c:\projects\roadfiles\plan\plan18285.dgn
PLOT SCALE = 1.0000 '/ IN.
PLOT STYLE = default.ctb
USER NAME = default

Added Sheet 2-26-08