



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 24, 2025

SUBJECT: FAI Route 290 (I-290 at Leavitt Street)  
Project NHPP-CIH0(915)  
Section 2021-120-BR  
Cook County  
Contract No. 62P43  
Item No. 18, March 7, 2025 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page vi of the Table of Contents to the Special Provisions.
3. Revised pages 3 and 167 of the Special Provisions.
4. Added pages 486-487 to the Special Provisions.
5. Revised sheets 1, 2, 5, 27, 29, 30, 32, 33, 49 and 94 of the Plans.
6. Added sheet 3A to the Plans.
7. Deleted duplicate sheet 16 from the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

PERFORMANCE GRADED ASPHALT BINDER (BDE) .....	434
PREFORMED PLASTIC PAVEMENT MARKING (BDE) .....	439
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) .....	440
SEEDING (BDE) .....	441
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE) .....	446
SIGN PANELS AND APPURTENANCES (BDE) .....	449
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE) .....	449
STEEL COST ADJUSTMENT (BDE) .....	450
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) .....	453
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) .....	453
SUBMISSION OF BIDDERS LIST INFORMATION (BDE) .....	454
SUBMISSION OF PAYROLL RECORDS (BDE) .....	454
SURFACE TESTING OF PAVEMENTS – IRI (BDE) .....	455
TRAINING SPECIAL PROVISIONS (BDE) .....	461
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.	463
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) .....	465
WEEKLY DBE TRUCKING REPORTS (BDE) .....	465
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) .....	466
PROJECT LABOR AGREEMENT .....	468
COOPERATION BETWEEN CONTRACTORS .....	486
COORDINATION WITH ADJACENT AND/OR OVERLAPPING CONTRACTS .....	487

## **STATUS OF UTILITIES (D1)**

Effective: June 1, 2016

Revised: October 16, 2024

Utility companies and/or municipal owners located within the construction limits of this project have provided the following information regarding their facilities and the proposed improvements. The tables below contain a description of specific conflicts to be resolved and/or facilities which will require some action on the part of the Department's contractor to proceed with work. Each table entry includes an identification of the action necessary and, if applicable, the estimated duration required for the resolution.

### **UTILITIES TO BE ADJUSTED**

Conflicts noted below have been identified by following the suggested staging plan included in the contract. The company has been notified of all conflicts and will be required to obtain the necessary permits to complete their work; in some instances, resolution will be a function of the construction staging. The responsible agency must relocate, or complete new installations as noted below; this work has been deemed necessary to be complete for the Department's contractor to then work in the stage under which the item has been listed.

### **Closure**

<b>STAGE / LOCATION</b>	<b>TYPE</b>	<b>DESCRIPTION</b>	<b>RESPONSIBLE AGENCY</b>	<b>DURATION OF TIME</b>
Leavitt Street bridge and approaches	Telephone	Telephone cable in conduit attached to the bridge has been permanently relocated to S. Western Ave. Permit is required for removal of four duct facility with asbestos on Leavitt Street bridge.	<b>AT&amp;T</b>	7 days
	Lighting	Lighting cable in conduit and luminaires attached to the bridge will be removed and replaced.	<b>Contractor</b>	N/A
	Electric	Electric cable in conduit attached to the bridge from Sta. 100+63 LT to	<b>ComEd</b>	<b>60 days Revised February 24, 2025</b>

**LUMINAIRE, LED, (SPECIAL) (CITY OF CHICAGO)**

Revised: 1/22/2025

Material Specifications: 1351, 1608, 1632

Standard Drawings: none

**Description.** This item shall consist of furnishing and installing a LED street light luminaire of the output noted on the plans with external smart node.

**Materials.** Luminaires shall meet the requirements of Material Specification 1632. External smart lighting nodes shall meet the requirements of Material Specification 1608. Pole wire shall meet the requirements of Material Specification 1351.

**Installation.** This work shall meet the applicable requirements of Sections 801 and 821.03 of the Standard Specifications. Each luminaire shall be installed per the manufacturer's instructions. Luminaires shall be securely attached to the end of a two-inch diameter pipe arm and leveled to provide proper illumination.

Pole wiring shall be connected to the luminaire terminal block, or quick disconnect, in accordance with the Material Specifications and the manufacturer's recommendation. Pole wires shall be spliced to the field wires at the base of the pole using splicing methods approved by the Engineer, and as detailed under related special provisions. The pole wires shall be of sufficient length to connect the luminaire to the field wires at the base of the pole.

**Basis of Payment.** This work will be paid for at the contract unit price per each for LUMINAIRE, LED, (SPECIAL).

Revised February 24, 2025

## **COOPERATION BETWEEN CONTRACTORS**

Add the following to Article 105.08:

The Department reserves the right to have work performed by other contractors and by Department forces and to permit public utility companies and others to perform work during the progress and within the limits of or adjacent to the work. The Contractor shall conduct its work in a manner and shall cooperate with such other parties to cause as little interference as possible with such other work and as the Department may also direct. If there is a difference of opinion as to the respective rights of the Contractor and others doing work within the limits of or adjacent to the work, the Engineer will decide the order and coordination of the work. The Engineer's decision shall be final and binding on the Contractor. The Contractor shall make no claims against the Department for additional compensation due to delays or other conditions created by the operations of such other parties.

Coordination with Other Contractors. The Contractor is advised that certain operations will involve coordination with Department personnel and Contractors currently performing work on or adjacent to this project for the Department and other agencies. The Contractor shall cooperate to the fullest extent with the Department and the Contractors working on adjacent projects in compliance with Articles 105.07 and 105.08 of these Specifications.

The Department and the Engineer shall be notified in writing by the Contractor at least 48 hours prior to the start of any operation requiring cooperating with others. All other agencies, unless otherwise noted, will be notified in writing by the Contractor ten (10) days prior to the start of any such operation. The Contractor shall make no claims against the Department for additional compensation due to delays or other conditions created by the operations of such other parties.

Added February 24, 2025

## **COORDINATION WITH ADJACENT AND/OR OVERLAPPING CONTRACTS**

The Contractor's attention is directed to the fact that adjacent and overlapping contracts may be under construction during the duration of this Contract. These contracts may consist of, but are not limited to, the following bridge rehabilitation projects:

- Contract 62R61 – F.A.I. 290 (Interstate 290) at Laramie Avenue
- Contract 62U43 – F.A.I. 290 (Interstate 290) at Kostner Avenue
- Contract 62U41 – F.A.I. 290 (Interstate 290) at Keeler Avenue
- Contract 62U42 – F.A.I. 290 (Interstate 290) at Pulaski Road
- Contract 62K62 – F.A.I. 290 (Interstate 290) at Central Park Avenue
- Contract 62K65 – F.A.I. 290 (Interstate 290) at Sacramento Boulevard
- Contract 62U05 – F.A.I. 290 (Interstate 290) at Western Avenue
- Contract 62P75 – F.A.I. 290 (Interstate 290) at Ogden Avenue
- Contract 62K64 – F.A.I. 290 (Interstate 290) at Paulina Street
- Contract 62P44 – F.A.I. 290 (Interstate 290) at Ashland Avenue
- Contract 62U12 – F.A.I. 290 (Interstate 290) at Loomis Street

The I-290 Drainage Improvements contract (Contract No. T.B.D.) from the Des Plaines River to east of Austin Boulevard may be under construction during the duration of this contract as well. The Contractor shall coordinate proposed project start dates and sequence of construction with the Engineer and other Contractors to present an effective and timely schedule for successful completion of the project.

Added February 24, 2025