


_5____ **-2**→






PEDESTRIAN PHASE SINGLE ENTRY PHASE


DUAL ENTRY PHASE

LEGEND

NUMBER REFERS TO ASSOCIATED PHASE

PHASE DESIGNATION DIAGRAM





EMERGENCY VEHICLE PREEMPTION SEQUENCE

EMERGENCY VEHICLE PREEMPTORS						
EMERGENCY VEHICLE PREEMPTOR	3	4				
MOVEMENT		 				

I. D. O. T.								
TRAFFIC SIGNAL INSTALLATION								
ELECTRICAL SERVICE REQUIREMENTS								
TYPE	NO. LAMPS	WATTAGE 7		% OPERATIONS	TOTAL			
		INCAND.	LED		WATTAGE			
SIGNAL (RED)	12	1 35	17	0.50	102			
(YELLOW)	12	1 35	25	0.25	75			
(GREEN)	12	1 35	15	0.25	45			
ARROW	16	1 35	12	0.10	19			
PED. SIGNAL		90	25	1.00				
CONTROLLER	1	100	100	1.00	100			
ILLUM. SIGN		252	25	0.05				
VIDEO SYSTEM		150	-	1.00				
FLASHER LED								
				TOTAL =	341			

ENERGY COSTS-

BILLED TO: VILLAGE OF LAKEMOOR 28874 W. IL ROUTE 120, SUITE C & D

LAKEMOOR, IL 60051

ENERGY SUPPLY -

CONTACT TERRI BLECK PHONE 847-816-5239

COMMONWEALTH EDISON

SCHEDULE OF QUANTITIES

OUANTITY	LINITT	ITTU
<u>QUANTITY</u>	<u>UNIT</u>	<u>I TEM</u>
1	EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
8	EACH	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM
1	EACH	MODIFY EXISTING CONTROLLER CABINET
1	EACH	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT
1	EACH	UNINTERRUPTABLE POWER SUPPLY. SPECIAL
4	EACH	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED, RETROFIT
4	EACH	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED, RETROFIT
4	EACH	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED, RETROFIT

NO. 6 GREEN **↑** ↑ 0 ≺ ₽ **2** ≻ ∪ NO. 6 -GREEN ↑ ↑ O ≺ ¬ CO ≺ ₹ IL RTE. 120 ~ × v × v GREEN **CABLE PLAN**

RETROFIT ALL EXISTING SIGNAL HEADS TO L.E.D.

REMOVAL OF EXISTING TRAFFIC SIGNAL EQUIPMENT

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

8 EACH TRAFFIC SIGNAL BACKPLATE

TS# 22102 LAKEMOOR

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	DW	REVISED -		IL ROUTE 120 (BELVEDERE ROAD) AT DARRELL ROAD		F.A. RTE.	SECTION	COUNTY TOTAL SHEET	
	3		JDH	REVISED -	STATE OF ILLINOIS	SCHEDULE OF QUANTITIES, CABLE PLAN, PHASE DESIGNATION DIAGRAM AND EMERGENCY VEHICLE PREEMPTION SEQUENCE			2012-040TS	LAKE 60 39	
	PLOT SCALE = \$SCALE\$	CHECKED -	КММ	REVISED -	DEPARTMENT OF TRANSPORTATION	AND EWENGEINCT VEHICLE PREEWIFIION SEQUENCE			CONTRACT NO. 60185		
	PLOT DATE = 12/10/2012	DATE -		REVISED -		SCALE: N.T.S.	SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. A	AID PROJECT	