

### DRAINAGE STRUCTURE SCHEDULE

STRUCTURE NUMBER	STATION	OFFSET (FT)	STRUCTURE TYPE					DIA. (FT.)	FRAME & GRATE	INVERTS							RESTRICTOR ELEVATION	RESTRICTOR ELEVATION	TOP PLATE ELEVATION	RIM ELEVATION
			MH TYPE A	CB TYPE A	INL. TYPE A	CB TYPE C	FES			NORTH	NORTHWEST	WEST	SOUTHWEST	SOUTH	SOUTHEAST	EAST				
JOHNSBURG ROAD																				
1	102+50.00	-37.0		1				6	T8							809.29			817.23	
3	103+50.00	-37.0		1				6	T8			809.19				808.72			813.40	
5	104+00.00	-20.5			1			2	T11	809.15									814.92	
7	104+00.00	-40.0		1				6	T8			808.62		809.00		808.62			811.50	
8	104+26.82	-38.8		1				6	T11			808.58				808.58			813.31	
9	104+64.00	-37.0		1				6	T1CL			808.52				808.52	808.52-4"	809.60-6"	811.56	813.50
10A	105+18.00	-33.6					1	2.25	GRATE					807.50						
10B	105+18.00	29.9					1	2.25	GRATE	807.26										
11	104+80.00	-37.0					1	4X2	GRATE			808.50								
13	106+33.37	-16.5			1			2	T11	804.60										810.02
15	106+50.00	-37.0		1				4	T8				804.50			800.83				807.46
17	107+51.70	-27.6			1			2	T11	804.18										808.20
19	107+56.97	-36.9		1				5	T8			800.43		804.08		800.43				807.06
21	109+57.00	-34.0	1					5	T1CL			799.51		798.80		794.11				805.60
23	110+81.72	-24.5			1			2	T9	793.10										799.28
25	110+93.00	-35.0		1				5	T8			792.00		793.00		783.18				796.50
27	112+10.00	-43.0		1				5	T8			782.90				782.60				790.00
29	112+55.00	-45.7	1					6	T1CL			782.50				782.50				788.50
31	113+00.00	-53.0					1-30"	2.5	GRATE			782.41								
32	118+92.00	-24.4	1					4	T1CL			788.00		791.90		788.00				795.36
33	117+44.00	-24.4	1					4	T1CL			786.59		786.59		786.59				790.56
34	115+92.00	-24.4	1					4	T1CL			781.50		784.28		784.28				788.40
35	115+08.00	-24.5	1					4	T1CL				780.40		780.40					788.31
41	107+09.75	31.0					1	1							806.18					
43	108+25.00	31.0		1				4	T8			801.50				801.50				805.50
47	109+50.00	-24.5		1				4	T9				798.90			798.90				803.23
51	115+00.00	-47.5					1	3						777.21						
53	115+00.00	54.7					1	3		776.77										
54	115+00.00	-16.5	1					5	T1	777.10				776.79		780.20				788.22
55	116+00.00	-16.5		1				4	T9	784.38										788.28
56	117+50.00	-16.5		1				4	T9	786.69										790.59
57	119+00.00	-16.5		1				4	T9	792.00										795.51
58	120+50.00	-16.5		1				4	T9			789.47								799.78
61	123+50.00	-16.5			1			2	T9					797.38						800.38
63	123+50.00	16.5		1				4	T9	797.18				797.18						800.38
65	123+50.00	30.0	1					4	T1CL	797.08						796.44				802.77
67	125+00.00	30.0	1					4	T1CL	793.17			795.39			791.08				799.11
69	126+50.00	30.0	1					4	T1CL	786.75			788.99			785.54				792.80
71	127+50.00	29.5	1					4	T1CL	781.13			783.04			778.50				786.96
73	128+75.00	33.0	1					4	T1CL	773.48			775.00				768.97			778.50
75	129+50.00	24.8			1			4	T11	768.53										771.80
77	130+50.00	22.0	1					4	T1CL	762.07			759.37		762.15	757.57				765.51
79	131+25.00	36.1	1					4	T11	756.90			754.59		752.79					760.68
81	132+22.30	56.8					1	1.5			751.00									
91	125+00.00	-16.5			1			2	T9					793.45						796.72
93	125+00.00	16.5		1				4	T9	793.27				793.27						796.72
101	126+50.00	-16.5			1			2	T9					787.15						790.42
103	126+50.00	16.5		1				4	T9	786.95				786.85						790.42
111	127+50.00	-16.5			1			2	T9					781.48						784.75
113	127+50.00	16.5		1				4	T9	781.33				781.23						784.75
121	128+75.00	-16.5			1			2	T9					773.78						776.78
123	128+75.00	20.6		1				4	T9	773.58				773.58						776.70
131	129+50.00	-16.5		1				4	T11					768.73						772.00
133	129+50.00	19.3	1					5	T1CL	768.43			767.33	768.48		762.35				771.94
141	130+50.00	-16.5		1				4	T11					762.32						765.62
143	130+50.00	27.5			1			2	T11	762.23										765.37
147	130+60.00	38.3			1			2	T1OL			756.47								761.50

2/22/2013

COMPANY NAME: HRGreen  
 PROJECT CONTRACT: 2/20/2013 10:41:3 PM  
 CLIENT: 000622-dach.dgn  
 FILE NAME: pldf\_dwg\_m\_devlpdfrg  
 PLOT DRIVER: standard-frames.tbl  
 PLOT TABLE:

	USER NAME = whood	DESIGNED - JRM	REVISED -	<b>MCHENRY COUNTY DIVISION OF TRANSPORTATION</b>	<b>DRAINAGE SCHEDULE OF QUANTITIES JOHNSBURG ROAD</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	FILE NAME = 000622-dach.dgn	DRAWN - JPA	REVISED -		SCALE: N.T.S.	SHEET NO. 1 OF 4 SHEETS	STA.	TO STA.	168	05-00314-00-WR	MCHENRY	187
	PLOT SCALE = N.T.S.	CHECKED - TH	REVISED -					CONTRACT NO. 63515				
	PLOT DATE = 2/22/2013	DATE = 2/20/13	REVISED -					FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				