STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

PROPOSED HIGHWAY PLANS

FAP ROUTE 317 (US 24) SECTION (137BR, BR-1)BR PROJECT NHPP-0317(095) **FULTON COUNTY BRIDGE REPLACEMENT** C-94-032-07

DESCRIPTION OF WORK

FOR INDEX OF SHEETS, SEE SHEET NO. 2

THIS PROJECT CONSISTS OF REMOVING AND REPLACING TWO BRIDGES, ONE OVER LITTLE SISTER CREEK AND ONE OVER BIG SISTER CREEK. 3,100 FEET OF US 24 ROADWAY WILL ALSO BE IMPROVED. THE INTERSECTION OF GRAIN BIN RD/MUDD RD WITH US 24 WILL BE RELOCATED APPROXIMATELY 95 FEET TO THE WEST, CONSTRUCTION OF APPROXIMATELY 1,050 FEET OF GRAIN BIN RD AND 350 FEET OF MUDD RD WILL BE RECONSTRUCTED. THE PROJECT INCLUDES PAVEMENT WIDENING RESURFACING, GUARDRAIL IMPROVEMENTS, DRAINAGE IMPROVEMENTS, PAVEMENT MARKINGS, LANDSCAPING, CONSTRUCTION STAGING AND ALL INCIDENTAL AND COLLATERAL WORK NECESSARY TO COMPLETE THE IMPROVEMENT.


FOR LIST OF HIGHWAY STANDARDS, SEE SHEET NO. 2

TRAFFIC DATA

2009 ADT = 4150 SU = 4.2% MU=7.2% 2019 ADT = 6071/6024

DESIGN DESIGNATION

OTHER PRINCIPAL ARTERIAL




FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123 OR 811

PROJECT ENGINEER: OLUFEMI OLADEINDE (SDI) 312-551-9780 PROJECT MANAGER: RON NOLTE (IDOT) 309-671-3470

CATALOG NO: 033474-000

CONTRACT NO. 68699




LOCATION MAP




GROSS LENGTH = 3,000 FT. = 0.568 MILE NET LENGTH = 3,000 FT. = 0.568 MILE

SECTION FULTON 118 1 (1378R, 9R-1)8R CONTRACT NO. 68699

D-94-028-07





PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

#062-053701

REGISTERED

PROFESSIONAL

ENGINEER

OLUFEMI A. ONADEINDE, P.E., S.E.

NPDES Permit Required

