



- THE LIMESTONE/COMPOST DRAIN SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 615 OF THE SPECIAL PROVISIONS.
- 2. THE HIGHWALL SIDE AND BASE MUST BE CLEAR OF ALL DEBRIS AND SEDIMENT, TO THE SATISFACTION OF THE ENGINEER, PRIOR TO THE LIMESTONE/COMPOST DRAIN INSTALLATION. NO UNSUITABLE MATERIAL WILL BE ALLOWED WITH IN THE LIMESTONE/COMPOST DRAIN CORRIDOR, AS DIRECTED BY THE ENGINEER. ANY COST ASSOCIATED WITH THE REMOVAL OF UNSUITABLE MATERIAL PRIOR TO THE LIMESTONE/COMPOST DRAIN PLACEMENT, SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT PRICE FOR EARTH EXCAVATION.

3. COMPOST/CA-6 LAYER SHALL CONSIST ON A ⁵% MIXTURE. MIXING OF THESE MATERIALS SHALL BE DONE ON SITE, AND TO THE SATISFACTION OF THE ENGINEER.

- 4. THE CA-6/COMPOST LAYER SHALL BE CEASED AT A MAXIMUM DISTANCE OF 10 FEET FROM THE PROPOSED DRAIN OUTLETS. FROM THE POINT WHERE THE CA-6/COMPOST LAYER STOPS, THE LIMESTONE/COMPOST DRAIN TRENCH SHALL BE FILLED WITH CA-1 TO THE PROPOSED OUTLETS.
- 5. THE LIMESTONE/COMPOST DRAIN SHALL AT ALL TIMES BE COVER BY A MINIMUM OF 4 FEET OF COMPACTED FILL MATERIAL. THIS MATERIAL SHALL BE COMPACTED ACCORDING TO SECTION 205 OF THE SPECIAL PROVISIONS.
- 6. THE LIMESTONE/COMPOST DRAIN FLOW LINE MUST HAVE A SLIGHT FALL TOWARD THE PROPOSED OUTLETS, TO THE SATISFACTION
- 7. THE PROPOSED VENT SYSTEN SHALL HAVE A SOLID RISER A MINIMUM OF 4 FEET ABOVE PROPOSED GRADE. THIS RISER SHALL HAVE A SCREW ON CONNECTOR TO FACILATE CONVERSION ONTO SAMPLING WATER WELL.



LIMESTONE/COMPOST DRAIN OUTLET DETAIL B-24, TYPICAL SECTION, NOT TO SCALE



CONSTRUCTION SIGN

DETAIL C-24, NOT TO SCALE, EXACT LOCATION TO BE SET BY ENGINEER

Resources Department of Natural of State

Marshall Equipment - Phase V Reclamation Project AML-GSIE-0417 Saline County

>

₹ 24 Sheet Site

Details