

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
698	1 VBR	BUREAU	72	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

REMOVAL SCHEDULE					
LOCATION STA TO STA	LENGTH	BRIDGE APPR. PAV'T REMOVAL	PAV'T REMOVAL	COMB. CONC. CURB & GUTTER REMOVAL	SIDEWALK REMOVAL
	FEET	SQ YD	SQ YD	FEET	SQ YD
28+10 - 28+55	45			54	
28+10 - 28+60	50			73	
28+75 - 29+35	60			69	
28+85 - 29+35	50			65	
28+10 - 29+38	70		122		
28+10 - 29+38	90		173		
28+40 - 28+52	12				
28+95 - 29+35	40				
29+35 - 29+60	25	67			6.7
34+40 - 34+65	25	67			35
TOTAL		134	295	261	41.7

TRAFFIC CONTROL SCHEDULE				
STAGE	HOT-MIX ASPHALT BASE CSE. WIDEN. 9"	TEMPORARY PAVEMENT REMOVAL	TEMPORARY PAINT PAVEMENT MARKING 4" YELLOW	PAVEMENT MARKING REMOVAL
	SQ YD	SQ YD	FOOT	SQ FT
STAGE I	88	88	1200	750
STAGE II	132	132	1600	350
TOTAL	220	220	2800	1100

EPOXY PAINT PAVEMENT MARKING							
LOCATION	LENGTH	EPOXY PAINT PVMT MK MARKING LINE 4"		TEMPORARY PVMT MK MARKING LINE 4"		SHORT TERM PAVEMENT MARKING	WORK ZONE PAVT MARKING REMOVAL
		YELLOW	WHITE	YELLOW	WHITE	YELLOW	
	LIN FT	LIN FT		LIN FT		LIN FT	SQ FT
STA. 28+10 TO STA. 29+38	128	256	256	256	256	26	8.7
STA. 29+38 TO STA. 30+81	143.0	286	286	286	286	29	9.7
STA. 30+81 TO STA. 30+87	6.0	12	12	12	12	4	1.3
STA. 30+87 TO STA 31+17	30.0	60	60	60	60	6	2
STA. 31+17 TO STA. 33+47	230.0	460	460	460	460	46	15.3
STA. 33+47 TO STA. 33+77	30.0	60	60	60	60	6	2
STA. 33+77 TO STA. 33+83	6.0	12	12	12	12	4	1.3
STA. 33+83 TO STA. 34+65.75	82.8	166	166	166	166	50	16.7
STA 34+65.75 TO STA 35+00	34.3	69	69	69	69	21	7
TOTAL	690.0	1380	1380	1380	1380	192	64

APPROACH PAVEMENT						
LOCATION	LENGTH	WIDTH	AREA	BRIDGE APPROACH PAVEMENT (SPECIAL)	BRIDGE APPR. PVMT. CONNECTOR PCC	BRIDGE APPR. PVMT. CONNECTOR FLEXIBLE
	FEET	FEET	SQ .YD.	SQ. YD.	SQ. YD.	SQ.YD.
STA. 30+81 TO STA. 30+87	6	26	17.33		17.33	
STA. 30+87 TO STA 31+17	30	31.5	105	105		
STA. 31+17 TO STA. 33+47	230	30	766.67			
STA. 33+47 TO STA. 33+77	30	31.5	105	105		
STA. 33+77 TO STA. 33+83	6	26	17.33			17.33
TOTAL				210	17.33	17.33

• NOTE: SEE BRIDGE PLAN SHEET 12 OF 24 FOR DETAILS OF SPECIAL BRIDGE APPROACH PAVEMENT.
PAY ITEMS FOR REINFORCEMENT BARS EPOXY COATED AND CONCRETE SUPERSTRUCTURE INCLUDED ON THIS SHEET ARE FOR INFORMATION ONLY AND SHALL BE INCLUDED IN THE COST FOR BRIDGE APPROACH PAVEMENT (SPECIAL)

SEEDING & EROSION CONTROL SCHEDULE												
LOCATION	SIDE	SEEDING CL 2A	MULCH METHOD 2	NITROGEN FERTILIZER	PHOSPHORUS FERTILIZER	POTASSIUM FERTILIZER	SODDING	TEMPORARY EROSION CONTROL SEEDING	EROSION CONTROL BLANKET	TEMPORARY DITCH CHECK	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION
		ACRE	ACRE	POUNDS	POUNDS	POUNDS	SQ. YD.	POUNDS	SQ YD	EACH	FOOT	EACH
STA 28+10 TO STA 28+60	RT			0.4	0.4	0.4	31					
STA 28+10 TO STA 28+60	LT			0.4	0.4	0.4	28					
STA 29+00 TO STA 31+50	RT	0.15	1.2	13.5	13.5	13.5		120	726		308.5	
STA 29+00 TO STA 31+50	LT	0.11		9.9	9.9	9.9		88			297	
STA 32+85 TO STA 35+00	RT	0.17	1.4	15.3	15.3	15.3		136	822		260.5	
STA 32+85 TO STA 35+00	LT	0.18	1.4	16.2	16.2	16.2		144	870		257.5	
STA 31+52	RT											1
STA 31+52	LT											1
STA 31+25	LT									1		
TOTAL		0.61	4.00	55.70	55.70	55.70	59.00	488.00	2418.00	1.00	1123.50	2.00

1. NOTE: QUANTITY FOR TEMPORARY SEEDING AND MULCH AVAILABLE FOR 8 APPLICATIONS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE
OF QUANTITIES**SCALE: VERT.
HORIZ.
DATEDRAWN BY
CHECKED BY