

PLOT DATE = 4/23/2006
FILE NAME = #FILEL*
PLOT SCALE = #SCALE*
USER NAME = #USER*

CONTRACT NO.66361

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
698	1 VBR	BUREAU	72	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

EARTHWORK SCHEDULE

LOCATION BUREAU COUNTY	EARTH EXCAVATION	EARTH EX. ADJUSTED FOR SHRINKAGE (0.75)	EMBANKMENT	FURNISHED EXCAVATION
				WASTE(+) OR SHORTAGE(-)
	CU YD	CU YD	CU YD	CU YD
NORTH OF BRIDGE				
STA 28+00 TO STA 28+25	12	9.00	0.7	8.30
STA 28+25 TO STA 28+50	20.4	15.30	0.7	14.60
STA 28+50 TO STA 28+75	15.8	11.85	0	11.85
STA 28+75 TO STA 29+00	13.8	10.35	0	10.35
STA 29+00 TO STA 29+25	11.1	8.33	0	8.33
STA 29+25 TO STA 29+50	20.9	15.68	0	15.68
STA 29+50 TO STA 29+75	16.2	12.15	206.2	-194.05
STA 29+75 TO STA 30+00	0	0.00	508.7	-508.70
STA 30+00 TO STA 30+25	0	0.00	674.7	-674.70
STA 30+25 TO STA 30+50	0	0.00	826.4	-826.40
STA 30+50 TO STA 30+75	0	0.00	1092.2	-1092.20
STA 30+75 TO STA 31+00	0	0.00	1323.2	-1323.20
STA 31+00 TO STA 31+25	0	0.00	1248.9	-1248.90
STA 31+25 TO STA 31+50	0	0.00	563.6	-563.60
SOUTH OF BRIDGE				
STA 33+00 TO STA 33+25	0	0.00	531.5	-531.50
STA 33+25 TO STA 33+50	0	0.00	1692.1	-1692.10
STA 33+50 TO STA 33+75	0	0.00	2238.8	-2238.80
STA 33+75 TO STA 34+00	0	0.00	1983.3	-1983.30
STA 34+00 TO STA 34+25	0	0.00	1710.3	-1710.30
STA 34+25 TO STA 34+50	0	0.00	818.6	-818.60
STA 34+50 TO STA 34+75	0	0.00	13.4	-13.40
STA 34+75 TO STA 35+00	0	0.00	0	0.00
EXISTING FRONTAGE ROAD	103.2			
TOTAL	213.4	82.65	15433.3	-15350.65

*

*

* Pay Items

GUARDRAIL SCHEDULE

LOCATION	STEEL PLATE BEAM GUARD RAIL TYPE A	TRAFFIC BARRIER TERMINAL TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 6 (SPL.)	TRAFFIC BAR. TERM. TY 1 SPL TANGENT	BITUMINOUS FOR SPBGR 6" FOR STABILIZATION
	FOOT	EACH	EACH	EACH	SQ YD
NORTH EAST QUADRANT					
STA 29+85.75 TO STA 30+35.75				1	
STA 30+35.75 TO STA 30+85.75	50				30.2
STA 30+85.75 TO STA 31+17		1			
NORTH WEST QUADRANT					
STA 29+68.25 TO STA 30+18.25				1	
STA 30+18.25 TO STA 30+55.75	37.5				73.5
STA 30+55.75 TO STA 30+87			1		
SOUTH EAST QUADRANT					
STA 33+47 TO STA 33+78.25		1			56.9
STA 33+78.25 TO STA 34+65.75	87.5				
SOUTH WEST QUADRANT					
STA 33+77 TO STA 34+08.25			1		114.7
STA 34+08.25 TO STA 34+58.25	50				
TOTAL	225	2	2	2	275.3

CURB AND GUTTER SCHEDULE

LOCATION	CONCRETE C & G TY. B-6:12	CONCRETE C & G TY. B-6:24	TIE BARS 3/4"	GUTTER OUTLET TY. B
	FOOT	FOOT	EACH	EACH
STA 28+10 LT TO STA 28+50 LT	40		20	
STA 28+50 LT TO STA 28+98.5 LT		49	25	
STA. 28+70 RT C.E. MARINA		32		
STA 28+98.5 LT TO STA 29+37.75 LT		39		
STA 29+37.75 LT TO STA 30+87 LT		149	75	
STA 28+10 RT TO STA 28+25 RT	15		8	
STA 28+25 RT TO STA 28+60 RT		53	27	
STA 28+80 RT TO STA 28+95 RT		24	12	1
STA 28+98.5 TO STA 29+37.75		39		
STA 29+37.75 RT TO STA 30+87 RT		148	74	
TOTAL	55	533	241	1

ACCESS ROAD

LOCATION	LENGTH	WIDTH	AGGREGATE SURFACE COURSE TY. B, 8"	AGGREGATE SHOULDER TY B
	FEET	FEET	SQ YD	TON
WEST	128	12	170.7	29.2
NORTH	169	12	225.3	38.5
EAST	94	12	125.3	21.4
TOTAL			521.3	89.1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE
OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY