

PLOT DATE = 10/30/2005
FILE NAME = c:\projects\4596106\4596106\cover\70547.dgn
PLOT SCALE = 105.6824 ' / IN.
USER NAME = philiprj

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57&74	*	**	151	21

* D5 CABLE GUARD 2007-2
* * CHAMPAIGN, DEWITT & DOUGLAS

SCHEDULES OF QUANTITIES

X0325590 HIGH TENSION CABLE MEDIAN BARRIER TERMINALS

LOCATION (EACH)

DOUGLAS COUNTY

LOC #1 TUSCOLA (I-57 SBDL SHOULDER)

LT. STA 467+25 - 467+75 1.0
LT. STA 503+00 - 503+50 1.0

SUBTOTAL = 2.0

CHAMPAIGN COUNTY

LOC #2 PESOTUM (I-57 SBPL MEDIAN)

LT. STA 176+50 - 177+00 1.0
LT. STA 217+00 - 217+50 1.0
LT. STA 216+00 - 216+50 1.0
LT. STA 250+00 - 250+50 1.0

SUBTOTAL = 4.0

DEWITT COUNTY

LOC #3 FARMER CITY (I-74 EBPL MEDIAN)

RT. STA 712+00 - 712+50 1.0
RT. STA 726+00 - 726+50 1.0
RT. STA 725+00 - 725+50 1.0
RT. STA 743+50 - 744+00 1.0

SUBTOTAL = 4.0

TOTALS = 10.0

X0325589 HIGH TENSION CABLE MEDIAN BARRIER

LOCATION (FOOT)

DOUGLAS COUNTY

LOC #1 TUSCOLA (I-57 SBDL SHOULDER)

LT. STA 467+75 - 503+00 3525.0

SUBTOTAL = 3525.0

CHAMPAIGN COUNTY

LOC #2 PESOTUM (I-57 SBPL MEDIAN)

LT. STA 177+00 - 217+00 SOUTH RUN 4000.0
LT. STA 216+50 - 250+00 NORTH RUN 3350.0

SUBTOTAL = 7350.0

DEWITT COUNTY

LOC #2 FARMER CITY (I-74 EBPL MEDIAN)

RT. STA 712+50 - 726+00 WEST RUN 1350.0
RT. STA 725+50 - 743+50 EAST RUN 1800.0

SUBTOTAL = 3150.0

TOTALS = 14025.0