F.A.I. SECTION COUNTY TOTAL SHEET NO. 578.74 * ** 151 43

* D5 CABLE GUARD 2007-2

** CHAMPAIGN, DEWITT & DOUGLAS

Number

10


4


8

8


4

REMOVE AND REINSTALL GRATING FOR CONCRETE HEADWALL STATION 225 + 00





SECTION A-A



END VIEW OF GRATE
SECTION B-B

GENERAL NOTES

1. BOLTS AND NUTS SHALL CONFORM TO A.S.T.M. A 307. ALL BOLTS SHALL HAVE WASHERS AT EACH END. HOLES SHALL BE 1/16 "OVERSIZED UNLESS OTHERWISE NOTED EXCEPT IN CONCRETE WHICH SHALL BE 1/8" OVERSIZED.

3x3x1/4 Plate washer

3 x 3/4 bolts with nuts & 2 washers

5 x 1/2 bolts with nuts & 2 washers

6 x 1/2 bolts with nuts & 2 washers 9 1/2 x 3/4 bolts with nuts & 2 washers

13 1/2 x 3/4 bolts with nuts & 2 washers

Bolts, Nuts and Washers

- 2. ANGLES AND STEEL PLATES SHALL CONFORM TO A.A.S.H.T.O. M 183. STEEL PIPES SHALL CONFORM TO A.S.T.M. A 53, GRADE B OR A.S.T.M. A 501.
- 3. STEEL PIPES, ANGLES AND PLATES SHALL BE HOT DIPPED GALVANIZED CONFORMING TO THE REQUIREMENTS OF A.A.S.H.T.O. M 111.
- 4. BOLTS, NUTS AND WASHERS SHALL BE HOT DIPPED GALVANIZED CONFORMING TO THE REQUIREMENTS OF A.A.S.H.T.O. M 232.
- 5. EXISTING PLATES, ANGLES AND PIPES SHALL BE REMOVED AND RE-ERECTED ONTO PROPOSED HEADWALL AND WINGWALLS. CENTER SUPPORT AND FOUNDATION SHALL BE REMOVED AND RE-ERECTED. THE CONTRACTOR SHALL INSURE EXISTING PLATES, ANGLES, PIPES AND CENTER SUPPORT ARE NOT DAMAGED DURING CONSTRUCTION. ANY DAMAGE DURING CONSTRUCTION SHALL BE CONTRACTOR RESPONSIBILITY TO REPLACE, NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 6. ALL BOLTS, NUTS AND WASHERS SHALL BE REPLACED. NEW BOLTS, NUTS AND WASHERS WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT UNIT PRICE EACH FOR "REMOVE & RE-ERECT EXISTING GRATING 8" X 2" BOX CULVERT".
- 7. THE CONTRACTOR WILL BE RESPONSIBLE FOR CHECKING ALL STRUCTURE DIMENSIONS, GRATE DIMENSIONS, BOLT, NUT & WASHER DIMENSIONS AND PIPE LENGTHS TO INSURE EXISTING GRATING IS PROPERLY RE-ERECTED ONTO THE PROPOSED EXTENSION.
- 8. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR "REMOVE & RE-ERECT EXISTING GRATING 8' X 2' BOX CULVERT" WHICH PRICE SHALL INCLUDE ALL MATERIAL AND LABOR TO COMPLETE THE INSTALLATION AS SHOWN.

SHEET 1 OF 2

ILLINOIS DEPARTMENT OF TRANSPORTATION

FOR CONCRETE HEADWALL STATION 225+00

SCALE: NA

DRAWN BY: CADD
CHECKED BY

LOCATION #2 PESOTUM