

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	1041PP07	CHAMPAIGN	11	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

SHORT-TERM PAVEMENT MARKING

ROUTE	STATION	TO	STATION		SKIP DASH YELLOW (FOOT)	NO PASSING YELLOW (FOOT)	TURN LANE WHITE (FOOT)
US 136	1450+95.00		1457+85.24	BO	63	--	--
US 136	1458+28.24	BO	1519+46.30		557	--	--
US 136	1519+46.30		1524+74.30		48	48	--
US 136	1524+74.30		1530+02.30		48	--	--
US 136	1530+02.30		1535+83.10		53	53	--
US 136	1535+83.10		1587+04.70		465	--	--
US 136	1587+04.70		1592+32.70		48	48	--
US 136	1592+32.70		1597+60.70		48	--	--
US 136	1597+60.70		1602+88.70		48	48	--
US 136	1602+88.70		1648+00.00	BK	410	--	--
US 136	1647+98.80	AH	1648+60.00		6	--	--
US 136	1648+60.00		1654+26.16		52	52	--
US 136	1654+26.16		1659+20.00		--	90	--
US 136	1659+20.00		1661+00.00		--	33	17
US 136	1661+87.12		1664+40.00		--	46	23
US 136	1664+40.00		1673+02.16		--	157	--
US 136	1673+02.16		1676+02.16		28	28	--
US 136	1676+02.16		1741+58.00		596	--	--
SUB-TOTALS					2,470	603	40
X 2 APPLICATIONS					4,940	1,206	80
TOTAL SHORT-TERM PAVEMENT MARKING					6,226		

BO = BRIDGE OMISSION
AH = AHEAD
BK = BACK

MICRO-SURFACING, 2 PASSES, TYPE 2 *

LANE	STATION	WIDTH (FOOT)	TO	STATION	WIDTH (FOOT)	SO YDS
EB / WB	1450+95.00	26.00		1457+85.24	BO 26.00	1,994.03
EB / WB	1458+28.24	BO 26.00		1648+00.00	BK 26.00	54,807.31
EB / WB	1647+98.80	AH 26.00		1650+68.35		778.70
EB / WB	1650+68.35	26.00		1651+93.35		361.11
EB	1651+93.35	13.00		1653+54.78		233.18
WB	1651+93.35	13.00		1653+62.74		272.91
EB	1653+54.78	13.00		1654+76.16		195.56
WB	1653+62.74	16.00		1654+76.16		195.33
EB	1654+76.16	16.00		1657+11.02		430.58
WB	1654+76.16	15.00		1660+81.43		975.16
EB	1657+11.02	17.00		1658+10.00		170.47
EB	1658+10.00	14.00		1658+60.00		94.92
EB	1658+60.00	20.17		1659+00.00		102.60
EB	1659+00.00	26.00		1661+87.12		829.46
WB	1660+81.43	14.00		1660+97.00		29.41
WB	1660+97.00	20.00		1661+87.12		200.27
EB	1661+87.12	14.00		1672+02.16		1,578.95
WB	1661+87.12	26.00		1664+40.00		730.54
WB	1664+40.00	26.00		1666+90.00		555.56
WB	1666+90.00	14.00		1667+26.50		56.78
WB	1667+26.50	14.00		1669+67.30		414.71
WB	1669+67.30	15.00		1672+02.16		391.43
EB	1672+02.16	14.00		1676+09.79		611.45
WB	1672+02.16	15.00		1673+23.54		188.81
WB	1673+23.54	13.00		1676+09.79		413.47
EB / WB	1676+09.79	26.00		1741+58.00		18,917.05
TOTAL						85,529.75
USE						85,530.00

* APPLICATION RATES: FIRST PASS = 16 LBS/ SQ YD
SECOND PASS = 16 LBS/SQ YD

PAINT PAVEMENT MARKING - LINE 4"

ROUTE	STATION	TO	STATION	LENGTH	4" WHITE (FOOT)	4" SKIP DASH YELLOW (FOOT)	4" NO PASSING YELLOW (FOOT)
US 136	1450+95.00		1648+00.00	BK 19,705.00	39,410.00	4,927.00	2,164.80
US 136	1647+98.80	AH	1741+58.00	9,359.20	18,977.04	1,871.00	4,443.92
SUB-TOTALS					58,387.04	6,798.00	6,608.72
TOTAL WHITE					58,387.04		
TOTAL YELLOW					13,406.72		
TOTAL					71,793.76		
USE					71,795.00		

PAINT PAVEMENT MARKING - LINE 24"

STATION EQUATION
STA 1661+38.40 (US 136) =
STA 546+60.40 (IL 47 NORTH) DECREASE STA NORTH
STA 507+35.80 (IL 47 SOUTH) DECREASE STA SOUTH

ROUTE	STATION	OFFSET	FOOT
US 136	1160+96.00	RT	26
US 136	1661+06.00	RT	17
US 136	1661+70.00	LT	17
US 136	1661+88.00	LT	26
IL 47 N	546+10.00	RT	26
IL 47 N	546+25.00	RT	17
IL 47 S	506+80.00	RT	26
IL 47 S	507+00.00	RT	17
TOTAL			172

RAISED REFLECTIVE PAVEMENT MARKER

STATION	TO	STATION	EACH
1672+02.16		1741+58.0	90
TOTAL			90

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

STATION	TO	STATION	EACH
1672+02.16		1741+58.0	90
TOTAL			90

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.P. 709 (U.S. 136)
SECTION 104,1051PP07
CHAMPAIGN COUNTY

SCALE: NOT TO SCALE
DATE: 09/01/06
DRAWN BY: B.B.P.
CHECKED BY: R.M.N.