

CONTRACT: 60A44

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE Y222		
				LOCATION 1 RURAL	LOCATION 2 URBAN	
42001200	PAVEMENT FABRIC	SQ YD	90	90		
42001300	PROTECTIVE COAT	SQ YD	497.8	248.9	248.9	
44200929	CLASS B PATCHES, TYPE I, 8 INCH	SQ YD	37	37		
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	53	53		
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	41	41		
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	48	48		
44213200	SAW CUTS	FOOT	680	680		
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	168	168		
45200300	JOINT OR CRACK FILLING	POUND	392	392		
50102400	CONCRETE REMOVAL	CU YD	55.3	35.2	20.1	
50104800	REMOVAL OF EXISTING CONCRETE DECK	L SUM	1	0.5	0.5	
50300225	CONCRETE STRUCTURES	CU YD	55.3	35.2	20.1	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	83.0	41.5	41.5	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	20,240	10,120	10,120	
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1		
50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1		1	
50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO.1	L SUM	1	1		
50606402	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO.2	L SUM	1		1	
50800105	REINFORCEMENT BARS	POUND	5180	2640	2540	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	29920	14960	14960	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2	2	
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.5	
Z0017202	DOWEL BARS 1 1/2"	EACH	178	178		
X0324265	JACK REMOVE AND REPLACE LOAD CELLS	L SUM	1	0.5	0.5	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE															
CODE NO	ITEM	UNIT																	

12/19/2005 8:03:46 AM C:\05406\05406.dwg

Rev.

REVISIONS	
NAME	DATE