

THORNDALE AVE EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL)			EARTH EXCAVATION (CUT)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)			EMBANKMENT (FILL)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
STATION	TO	STATION	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD
10+00.00	TO	11+00.00	17.27	0.00	0.00	6.38	0.00	0.00	5.42	0.00	0.00	3.69	0.00	19.35	1.73	0.00	-19.35
11+00.00	TO	11+66.32	43.50	0.00	0.00	13.85	0.00	22.29	11.78	0.00	18.95	2.45	0.00	15.76	9.33	0.00	3.19
11+66.32	TO	12+00.00	22.23	0.00	0.00	6.23	0.00	26.25	5.30	0.00	22.31	2.29	0.00	3.56	3.01	0.00	18.75
12+00.00	TO	12+54.08	26.56	0.00	0.00	37.27	0.00	66.25	31.68	0.00	56.31	3.67	0.00	7.25	28.01	0.00	49.07
12+54.08	TO	13+00.00	31.54	0.00	0.00	74.35	0.00	75.18	63.20	0.00	63.90	0.00	0.00	21.27	63.20	0.00	42.64
13+00.00	TO	14+00.00	73.57	0.00	0.00	173.64	0.00	298.22	147.59	0.00	253.49	0.00	0.00	67.33	147.59	0.00	186.16
14+00.00	TO	16+00.00	199.46	0.00	0.00	285.70	733.02	425.35	242.85	623.07	361.55	0.00	0.20	56.52	242.85	622.86	305.03
16+00.00	TO	16+50.91	66.64	0.00	0.00	67.10	314.96	0.00	57.03	267.72	0.00	0.00	17.30	0.00	57.03	250.42	0.00
16+50.91	TO	17+00.00	55.39	0.00	0.00	67.80	224.82	0.00	57.63	191.10	0.00	0.00	35.12	0.00	57.63	155.98	0.00
17+00.00	TO	18+00.00	72.06	0.00	0.00	76.59	281.94	0.00	65.10	239.64	0.00	0.65	37.66	0.00	64.46	201.99	0.00
18+00.00	TO	19+00.00	46.68	0.00	0.00	4.06	125.15	0.00	3.45	106.38	0.00	0.65	1.87	0.00	2.80	104.51	0.00
19+00.00	TO	19+48.76	13.50	0.00	0.00	0.00	49.44	0.00	0.00	42.03	0.00	0.00	0.91	0.00	0.00	41.11	0.00
19+48.76	TO	20+00.00	10.95	0.00	0.00	0.00	41.03	0.00	0.00	34.88	0.00	0.00	0.00	0.00	0.00	34.88	0.00
20+00.00	TO	21+00.00	13.64	0.00	0.00	0.00	27.72	0.00	0.00	23.56	0.00	0.00	0.00	0.00	0.00	23.56	0.00
TOTALS =			692.98	0.00	0.00	812.98	1798.09	913.54	691.03	1528.37	776.51	13.40	93.06	191.03	677.64	1435.31	585.48

Q:\1001\9356_A02_01153\Drawings\CADD Sheets\019139797-sht-schedule_029-041.dgn