

NOTES:

- 1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
- 2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

- 1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
- 2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEQUENCE OF CONSTRUCTION (MILLING FIRST)

- 1. MILL HMA FIRST IF THERE IS AT LEAST 41/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
- 2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

	FILE NAME =	USER NAME = galbanjr	DESIGNED - R. SHAH	REVISED -	A. ABBAS 04-27-98		PAVEMENT PATCHING FOR	F.A.I.	SECTION	COUNTY TOTAL SHEET
	c:\pw_work\pwidot\galbanjr\d0212968\DistBtd.dgn		DRAWN -	REVISED -	R. BORO 01-01-07	STATE OF ILLINOIS	· ·		2010-079-RS	COOK/DUPAGE 96 91
- 1		PLOT SCALE = 50.7684 '/ IN.	CHECKED -	REVISED -	R. BORO 09-04-07		HMA SURFACED PAVEMENT		BD400-04 (BD-22)	CONTRACT NO. 60L67
		PLOT DATE = 1/3/2011	DATE - 10-25-94	REVISED -	K. ENG 10-27-08		SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. RC	DAD DIST. NO. 1 ILLINOIS FED. A	ID PROJECT