## **GENERAL NOTES**

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING THE INSTALLATION OF TIE ASSEMBLIES AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

## **SUMMARY OF QUANTITIES**

	100% STATE			
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	
67100100	MOBILIZATION	L SUM	1	
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3000	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1432	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	862	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	862	
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	1074	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	538	
<del>x0325363</del>	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE BOARD	CAL DA	30	
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	120	
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	1	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	80	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	
X0327128	HANGER TIE ASSEMBLY	EACH	32	

\* SPECIALTY ITEM

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

REVIEWED BY:

DISTRICT STUDIES & PLANS ENGINEER

DATE:

12-06-10

EXAMINED BY: Sobert fory (une)
DISTRICT CONSTRUCTION ENGINEER

las I milleri

DISTRICT MATERIALS ENGINEER

DISTRICT OPERATIONS ENGINEER

benesch engineers - scientists - planners

Alfred Benesch & Company 205 North Michigan Avenue, Suite 2400 Chicago, Illinois 60601 312-565-0450 Job No. 3938.05

ILE NAME =	USER NAME = carpenterdj	DESIGNED -	HMS/MC	REVISED -
FILEA*		DRAWN -	MC	REVISED -
	PLOT SCALE = '/ IN.	CHECKED -	KJN	REVISED -
	PLOT DATE = Dec 06 2010 - 02:07:52 PM	DATE -	11/10/2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

COMMITMENTS, GENERAL NOTES

& SUMMARY OF QUANTITIES

LE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA

pw\_work\pwidot\carpenterdj\d02l430l\D366A34-sht-gennoteS00

\* T11117

- 02:07:52 PM \$TIME\$