

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1566	1996-151RS	COOK	21	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

100% FED URBAN

100% FED URBAN ROADWAY

CONTRACT NO.: 60232

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY				
				1000-2A				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	212	212				
21400100	GRADING AND SHAPING DITCHES	FOOT	400	400				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	16				
40600300	AGGREGATE (PRIME COAT)	TON	76	76				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	504	504				
40600990	TEMPORARY RAMP	SQ YD	504	504				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3181	3181				
42001300	PROTECTIVE COAT	SQ YD	191	191				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	37867	37867				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	978	978				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	1243	1243				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	569	569				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	813	813				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	846	846				
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1079	1079				
<input type="checkbox"/> 55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1858	1858				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8				
63200310	GUARDRAIL REMOVAL	FOOT	1858	1858				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7110	7110				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46706	46706				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	110	110				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16579	16579				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46706	46706				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	110	110				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	586	586				
* 78200405	GUARDRAIL MARKERS	EACH	25	25				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	528	528				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	77.1	77.1				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1491	1491				
<input type="checkbox"/> Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	3	3				
<input checked="" type="checkbox"/> Z0076600	TRAINEES	HOUR	500	500				

\* SPECIALTY ITEMS  
 NON-PARTICIPATING ITEMS 100% STATE  
 © 1080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 F.A.U. 1566 (95TH ST.)  
 IL 171 (ARCHER AVE.) TO US 45 (LA GRANGE RD.)

Rev.