F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2021.1B-R	COOK	101	007
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62532

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% FED. URBAN X771-2A	ROADWAY	BRIDGE (1)	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS					
				CONSTRUCTION TYPE CODE										
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1										
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	224	224										
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	61	61										
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	502	502										
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1879	1879										
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1240	1240										
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1600	1600										
* 72000100	SIGN PANEL - TYPE 1	SQ FT	24	24										
* 72000200	SIGN PANEL - TYPE 2	SQ FT	11	11										
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	11	11										
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	43	43										
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	2	2										
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	71	71										
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1856	1856										
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	621	621										
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	402	402										
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	130	130										
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	205	205										
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	836	836										
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	341	341										
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	100	100										
* 78003180	PREFORMED PLASTIC PAVEMENT MARKINC TYPE B - LINE 24"	FOOT	108	108										
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	128	128										
78300100	PAVEMENT MARKING REMOVAL	SQ FT	963	963										
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	820				820							
* 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6 " X 4"	EACH	12				12							
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10 " X 6"	EACH	6				6							
* 81700110	ELECTRIC CABLE IN CONDUIT, 600V, (EPR-TYPE RHW) 1/C NO. 10	FOOT	2860				2860							
* 88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4						4					
* 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	12						12					
* 88040110	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2						2					

* DENOTES SPECIALTY ITEMS
☐ NON-PARTICIPATING

BRIDGE INFORMATION

(1) 111TH ST. OVER NB & SB I-57 S.N. 016-0989

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
111TH STREET OVER
F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
DATE: 01/16/09 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

...\TTBOUMRA.DGN ...\SU000UME.DGN ...\SU000UP9.DGN
T:\DOCUMENT~1\BOB60K\LOCAL\TEMP\...\U000UC.DGN
HECHTBR
F-16-2009, 10:54:25