

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	•	IROQUOIS	14	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• (135)RS-3 & (136)RS-2

SUMMARY OF QUANTITIES

CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	TOTAL QUANT	100% FEDERAL	
				I000 RDWY QUANT	
20400800	FURNISHED EXCAVATION	CU YD	33	33	
• 25000200	SEEDING, CLASS 2	ACRE	0.24	0.24	
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	22	22	
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	22	22	
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	22	22	
• 25100630	EROSION CONTROL BLANKET	SQ YD	1144	1144	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	119	119	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	56	56	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	34939	34939	
40600300	AGGREGATE (PRIME COAT)	TON	665	665	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	49	49	
40600525	LEVELING BINDER (HAND METHOD), N50	TON	82	82	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	6854	6854	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1230	1230	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	8	8	
40600990	TEMPORARY RAMP	SQ YD	195	195	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	13747	13747	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	710	710	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	714	714	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4289	4289	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	701	701	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	5	5	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11331	11331	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	61.2	61.2	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	126156	126156	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	13317	13317	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	44	44	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1888	1888	
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	61	61	
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	44	44	
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	126156	126156	
• 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	13317	13317	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	713	713	
X0325866	CENTERLINE-RUMBLE STRIP	FOOT	4000	4000	
Z0021700	EXPANSION JOINT REHABILITATION	FOOT	104	104	

• SPECIALTY ITEMS

SUMMARY OF QUANTITIES