F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	*	CASS	33	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 114(RS-3); 115(RS-3)

72830

SUMMARY OF QUANTITIES				100% FED IOOO ESP
				ROADWAY
CODE NO	ITEM	UNIT	TOTAL	1000
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	3,580	3,580
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	12	12
63200310	GUARDRAIL REMOVAL	FOOT	4,360	4,360
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	15,678	15,678
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	138,803	138,803
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQFT	1,742	1,742
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	138,803	138,803
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	653	653
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	55	55
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	653	653

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP ROUTE 310 (US 67)
SECTION 114 (RS-3); 115 (RS-3)
CASS COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = Feb-05-2009 8:14:49PM
FILE NAME = c:\pw_work\IDOT\LAURA.LINE\dms28277\summary.dgn
PLOT SCALE = 185.8824 ft / IN.
USER NAME = laurallin+1