

ROUTE: Dixie Hwy (138th St to 168th St)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
150th	154th	SB	2	6	50	300	33					33		
150th	154th	SB	2	6	12	72	8			8				
150th	154th	SB	2	Joint	500	0	0							
150th	154th	SB	2	6	6	36	4		4					
150th	154th	SB	2	12	25	300	33					33		
150th	154th	SB	2	12	100	1200	133	133						
154th	159th	SB	2	12	12	144	16				16			
154th	159th	SB	2	Joint	200	0	0							
154th	159th	SB	2	8	12	96	11			11				
154th	159th	SB	2	Joint	700	0	0							
154th	159th	SB	2	4	12	48	5		5					
154th	159th	SB	2	6	6	36	4		4					
154th	159th	SB	2	6	20	120	13			13				
154th	159th	SB	2	6	12	72	8			8				
154th	159th	SB	2	6	6	36	4		4					
154th	159th	SB	2	6	6	36	4		4					
154th	159th	SB	2	4	30	120	13			13				
154th	159th	SB	2	4	20	80	9			9				
154th	159th	SB	2	6	20	120	13			13				
154th	159th	SB	2	6	30	180	20				20			
159th	167th	SB	2	6	30	180	20				20			
159th	167th	SB	2	6	12	72	8			8				
159th	167th	SB	2	6	50	300	33					33		
159th	167th	SB	2	6	6	36	4		4					
159th	167th	SB	2	4	40	160	18			18				
159th	167th	SB	2	4	12	48	5		5					
159th	167th	SB	2	6	12	72	8			8				
159th	167th	SB	2	6	6	36	4		4					
I-80/94	170th	NB	1	6	12	72	8			8				
170th	167th	NB	1	6	6	36	4		4					
167th	159th	NB	1	6	12	72	8			8				
159th	154th	NB	1	6	12	72	8			8				
I-57	138th	NB	1	6	6	36	4		4					
I-57	138th	NB	1	6	6	36	4		4					
I-57	138th	NB	1	4	20	80	9			9				
I-57	138th	NB	1	6	12	72	8			8				
I-57	138th	NB	1	6	12	72	8			8				
I-57	138th	NB	1	6	6	36	4		4					
I-57	138th	NB	1	6	6	36	4		4					
I-57	138th	NB	1	6	6	36	4		4					
I-57	138th	NB	1	6	12	72	8			8				
138th	139th	SB	1	Joint	200	0	0							
138th	139th	SB	1	6	20	120	13			13				
138th	139th	SB	1	6	12	72	8			8				
139th	I-57	SB	1	6	12	72	8			8				
139th	I-57	SB	1	6	12	72	8			8				
139th	I-57	SB	1	6	6	36	4		4					
139th	I-57	SB	1	6	20	120	13			13				
139th	I-57	SB	1	6	6	36	4		4					
I-57	Sibley	SB	1	6	12	72	8			8				
Sibley	150th	SB	1	6	20	120	13			13				
150th	154th	SB	1	6	12	72	8			8				
154th	159th	SB	1	6	12	72	8			8				
159th	167th	SB	1	6	6	36	4		4					
159th	167th	SB	1	6	12	72	8			8				
159th	167th	SB	1	6	6	36	4		4					
159th	167th	SB	1	6	12	72	8			8				
159th	167th	SB	1	6	12	72	8			8				
167th	168th	SB	1	12	12	144	16				16			

Total
 1,624 SY 520 SY 130 SY 607 SY 202 SY 159 SY 1600 FT 40 EACH

FILE NAME = c:\projects\dl36708\design_ee.dgn	USER NAME = wlgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE DIXIE HIGHWAY	F.A.P. RTE. VAR.	SECTION 2008-016 PP	COUNTY COOK	TOTAL SHEETS 131	SHEET NO. 44
PLOT SCALE = 103.7051' / IN.		CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
PLOT DATE = 3/15/2008		DATE -	REVISED -	CONTRACT NO. 60E42						