

SUMMARY OF QUANTITIES

CONSTR. CODE
100% STATE
ROADWAY
1000
RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
20200100	EARTH EXCAVATION	CU YD	155	155
20400800	FURNISHED EXCAVATION	CU YD	66	66
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	324	324
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	920	920
28000400	PERIMETER EROSION BARRIER	FOOT	374	374
28000500	INLET AND PIPE PROTECTION	EACH	2	2
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	324	324
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	223	223
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	23	23
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	102	102
40600300	AGGREGATE (PRIME COAT)	TON	559	559
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5397	5397
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	5897	5897
40600990	TEMPORARY RAMP	SQ YD	613	613
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	10770	10770
40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	6325	6325
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	817	817
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	551	551
42400800	DETECTABLE WARNINGS	SQ FT	10	10
44000100	PAVEMENT REMOVAL	SQ YD	266	266
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	117770	117770

* SPECIALTY ITEM

SUMMARY OF QUANTITIES

CONSTR. CODE
100% STATE
ROADWAY
1000
RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	86470	86470
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1826	1826
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	359	359
44000600	SIDEWALK REMOVAL	SQ FT	548	548
44002805	ISLAND REMOVAL	SQ FT	733	733
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	179	179
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	35	35
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	1628	1628
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	340	340
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	117	117
44213100	PAVEMENT FABRIC	SQ YD	35	35
44213200	SAW CUTS	FOOT	1313	1313
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4400	4400
48203100	HOT-MIX ASPHALT SHOULDERS	TON	269	269
60237480	INLETS, TYPE A, TYPE 37 GRATE	EACH	1	1
60241900	INLETS, TYPE G-1, SPECIAL	EACH	1	1
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1
60260100	INLETS TO BE ADJUSTED	EACH	1	1
60500060	REMOVING INLETS	EACH	1	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	374	374
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1

* SPECIALTY ITEM