

ROUTE		SECTION	COUNTY	SHEET	
F.A.P.	669	15RS-6;(14,13,11R) RS-4;(10R)RS-7	PEORIA	TOTAL	NO.
MKD.	IL 116			65	34

TEMPORARY & EPOXY PAVEMENT MARKING								
STATION TO STATION	LENGTH	WHITE					YELLOW	
		6"	8"	24"	LETTERS & SYMBOLS	12"	12"	
		FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	
FARMINGTON ROAD		65				85		
WB RIGHT TURN			210		31.2		103	
EB LEFT TURN			290		62.4		150	
TAYLOR ROAD								
WB LEFT TURN			170		31.2		135	
EB LEFT TURN			130		31.2		150	
STA. 648+97 to STA. 651+47	250		628			111	98	
STA. 651+47 to STA. 682+36	3089	110			436.8			
STATION EQUATION								
STA. 682+56 to STA. 688+48	592				93.6			
PEKIN LANE								
EB LEFT TURN			120		31.2			
STA. 691+23 to STA. 694+98	375				78.0			
McALLISTER ROAD								
EB LEFT TURN			120		31.2			
TANGER ROAD								
WB RIGHT TURN			120		31.2			
CUL-D-SAC								
WB RIGHT TURN			120		31.2			
	0							
STA. 123+47 to STA. 125+82	235						60	
I.U.O.E.								
WB LEFT TURN			120		31.2		30	
MAXWELL RD			1021	96		587		
WB LEFT TURN			160		46.80		60	
EB LEFT TURN			275		31.20		30	
NB LEFT TURN			120		31.20			
SB LEFT TURN			65		15.60			
STA. 136+02 to STA. 166+68	3066				468.00		36	
SUB-TOTAL		110	3,734	96	1,513	783	852	

TEMPORARY & EPOXY PAVEMENT MARKING							
STATION TO STATION	LENGTH	WHITE				YELLOW	
		6"	8"	24"	LETTERS & SYMBOLS	12"	12"
		FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT
STARR LANE							
EB RIGHT TURN			100		31.2		
MAIL TECH DR							
EB RIGHT TURN			100		31.2		
MAIN STREET							
WB LEFT TURN			100		31.2		
STA. 169+39 to STA. 173+81	442						
STA. 228+58 to STA. 230+01	143						15
STA. 230+01 to STA. 231+69	168	100					
STA. 248+98 to STA. 252+64	366						220
STA. 248+98 to STA. 271+20	2222	1120					
STATION EQUATION							
STA. 271+12 to STA. 281+91	1079	540					
STA. 282+81 to STA. 289+47	666	340					
HILLSDALE AVE							
EB LEFT TURN			85		31.2		
STA. 254+29 to STA. 271+20	1691				280.8		
STATION EQUATION							
STA. 271+12 to STA. 280+16	904				156		
LARAMIE ST		168		96			
WB LEFT TURN			160		46.8		
WB RIGHT TURN			100		31.2		
EB LEFT TURN			100		31.2		
NB		100					
SB			15		41.6		
STA. 285+31 to STA. 289+47	416				140.2		
DR MARTIN LUTHER KING DR			305			36	200
EB LEFT TURN / THROUGH LANE			220		54.2	80	
SUB-TOTAL		2,368	1,285	96	907	116	435
SUB-TOTAL (PG 1)		110	3,734	96	1,513	783	852
TOTAL		2,478	5,019	192	2,420	899	1,287
						2,186	

SCHEDULE OF QUANTITIES
IL 116