

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODES 80% FEDERAL / 20% STATE	
PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	CULVERT X028-2A
51500100	NAME PLATES	EACH	1		1
54001000	BOX CULVERT END SECTIONS	EACH	2		2
54011108	PRECAST CONCRETE BOX CULVERT 11'X8"	FOOT	105		105
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	4	
54213705	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"	EACH	1	1	
NP 55030200	STORM SEWERS TO BE CLEANED 24"	FOOT	169.6	169.6	
55100900	STORM SEWER REMOVAL 18"	FOOT	101.8	101.8	
NP 55039000	STORM SEWERS TO BE CLEANED 60"	FOOT	410.6	410.6	
55102100	STORM SEWER REMOVAL 60"	FOOT	58	58	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2	2	
60107600	PIPE UNDERDRAINS 4"	FOOT	200	200	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	50	50	
60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	250	250	
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2	
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	6	6	
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60224445	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2	
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60228400	MANHOLES, SPECIAL	EACH	2	2	
60500040	REMOVING MANHOLES	EACH	3	3	
60603300	GUTTER OUTLET	EACH	1	1	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	467.1	467.1	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1362.6	1362.6	

NP = NON-PARTICIPATING
* - Specialty Items

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODES 80% FEDERAL / 20% STATE	
PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	CULVERT X028-2A
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	275	275	
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	87.5	87.5	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4	
* 63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	4	4	
* 63200310	GUARDRAIL REMOVAL	FOOT	391.5	391.5	
* 63300725	STEEL PLATE BEAM GUARD RAIL (SHORT RADIUS)	FOOT	73.1	73.1	
63500105	DELINEATORS	EACH	4	4	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	120	120	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1200	1200	
70300200	TEMPORARY PAVEMENT MARKING	FOOT	1200	1200	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	2000	2000	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1070	1070	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	218.4	218.4	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4557.9	4557.9	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	682.8	682.8	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	214	214	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	71	71	

SUMMARY OF QUANTITIES

Rev. 4-13-09

COLLINS ENGINEERS	QUANTITIES SHEET NO. 2 OF 3 SHEETS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		2774	0306T	COOK	55	4
DESIGNED: LDB	CHECKED: JMH	SN: 016-2848		CONTRACT NO. 60C07		
DATE: 01/29/09	DRAWN: DR	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				