

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	IL 72 BRIDGE SFTY-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	27	27
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	32	32
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	381	381
50102400	CONCRETE REMOVAL	CU YD	65.0	65.0
50157300	PROTECTIVE SHIELD	SQ YD	700	700
50300255	CONCRETE SUPERSTRUCTURE	CU YD	65.0	65.0
50300260	BRIDGE DECK GROOVING	SQ YD	832	832
50300300	PROTECTIVE COAT	SQ YD	961	961
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	15,190	15,190
50800515	BAR SPLICERS	EACH	122	122
52000110	PREFORMED JOINT STRIP SEAL	FOOT	225	225
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,179	1,179
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6	6
78300100	PAVEMENT MARKING REMOVAL	SQ FT	393	393
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10

* SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	IL 72 BRIDGE SFTY-2A
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	1,608	1,608
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	8	8
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	8	8
* 83057435	LIGHT POLE, WOOD, 80 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	2	2
* 83057430	LIGHT POLE, WOOD, 80 FOOT, CLASS 3	EACH	1	1
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	8	8
* X0322141	REMOVE TEMPORARY WOOD POLE	EACH	1	1
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	6
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	1,481	1,481
* X0325867	COMBINATION POLE MOUNTED ELECTRIC SERVICE BOX	EACH	1	1
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1
* X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1
* XX006937	GROUND ROD, 5/8" DIA. x 10 FT.	EACH	2	2
Z0006229	BRIDGE DECK HYDRO-SCARIFICATION 3"	SQ YD	901	901
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	44	44
X0326346	BRIDGE DECK LATEX CONCRETE OVERLAY, 3 INCHES	SQ YD	901	901
* X0326135	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	1	1

* SPECIALTY ITEM