SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
09-00090-01-BT	DUPAGE	117	5
STA.	TO STA.		
IDOT PROJECT NO. M-9003(227)			
SALT CREEK GREENWAY TRAIL			

CONTRACT NO. 63154

	CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY	DUPAGE FOREST PRESERVE		VILLAGE OF ADDISON		ADDISON PARK DISTRICT	
					BIKEWAY	STRUCTURES	BIKEWAY	STRUCTURES	BIKEWAY	STRUCTURES
					Y047	Y047	Y047	Y047	Y047	Y047
*										
	A2000116	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE	EACH	10	6		4			
*		FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED								
	A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER,	EACH	6	3		3			
*		BALLED AND BURLAPPED								
	B2000962	TREE, AMELANCHIER LAEVIS (ALLEGHENY SERVICEBERRY)	EACH	3			3			
*		4' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED								
	B2001616	TREE, CRATAEGUS CRUSGALLI INERMIS (THORNLESS COCKSPUR	EACH	8			8			
*		HAWTHORN), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED								
	C2C02124	SHRUB, COTONEASTER APICULATUS (CRANBERRY	EACH	34			34			
*		COTONEASTER), 2' WIDTH, CONTAINER								
	D2C02224	EVERGREEN, PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE),	EACH	18			18			
*		2' HEIGHT, CONTAINER								
*	D2C02724	EVERGREEN, PINUS NIGRA (AUSTRIAN PINE), 2' HEIGHT, CONTAINER	EACH	22			22			
*	K0039110	CALAMAGROSTIS ACUTIFOLIA 'STRICTA' CONTAINER GROWN (1 GALLON)	UNIT	100			100			
*	K1004595	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	L SUM	1	0.75				0.25	
	MZ022800	FENCE REMOVAL	METER	3					3	
	MX030564	PAVER BRICKS	SQ M	92			92			
	MX030565	ALUMINUM SIGN POST, SPECIAL	METER	169.9	141.9		17.5		10.5	
*	MX030566	UNIT DUCT, WITH 4 - 1/C NO. 2 AND 1 1/C NO. 2 GROUND,	METER	121			121			
		600V (XLP), 50 MM POLYETHYLENE								
	MX030567	RUSTIC RAIL FENCE	METER	547	528.6				18.4	
*	MX030568	MODIFIED TIMBER RAIL	METER	37		37				
	MX030569	LIMESTONE TRAIL SCREENINGS, 50 MM	SQ M	3,208	3208					
*	MX030570	PEDESTRIAN BRIDGE SUPERSTRUCTURE	SQ M	341		297				44
	MX032529	SEGMENTAL CONCRETE BLOCK WALL	SQ M	125		110		15		
*	MX032950	PERMANENT STEEL SHEET PILING	SQ M	2,217		1933		284		
	X0444100	BENCHES	EACH	6	4				2	
	XX001683	INFORMATION KIOSK	EACH	3	2				1	
*	XX001882	HEMEROCALLIS 'STELLA D' ORO' (PERENNIAL DAYLILY)	UNIT	90			90			
*	XX001884	RUDBECKIA FULGIDA 'GOLDSTRUM' (PERENNIAL BLACK EYED SUSAN)	UNIT	70			70			
	XX002906	TIP DOWN GATE	EACH	1					1	
*	XX003240	MISCANTHUS SINENSIS 'GRACILLIMUS' (2 GAL)	EACH	75			75			
	XX006082	INFORMATION KIOSK GRAPHIC PANEL	EACH	9	6				3	
	XX006083	RELOCATE SIGN, SPECIAL	EACH	2	1		1			
	XX006084	REMOVE EXISTING MONUMENT	EACH	1			1			
	XX006085	ENTRANCE MONUMENT	EACH	1			1			

* SPECIALTY ITEMS

URS
100 S. WACKER DR., SUITE 500 TEL (312) 939-1000
CHICAGO, IL 60606 FAX (312) 939-4198

REVISIONS		
NO.	NAME	DATE

VILLAGE OF ADDISON

SALT CREEK GREENWAY TRAIL

SUMMARY OF QUANTITIES

DATE: 02/13/2009 DRAWN BY: MIA&VP

DESIGNED BY: MIA CHECKED BY: DDL