

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
09-00090-01-BT	DUPAGE	117	10
STA.	TO STA.		
IDOT PROJECT NO. M-9003(227)			
SALT CREEK GREENWAY TRAIL			
CONTRACT NO. 63154			

DUPAGE FOREST PRESERVE

TREE REMOVAL SCHEDULE

LOCATION			6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
STATION	OFFSET			
	LT	RT		
9+442.0	2.9			47
9+485.6	3.5			30
9+486.1		4.1		49
9+502.2		5.6	6	
9+540.9	4.1		6	
9+543.3	3.3		8	
9+571.0		0.3		17
10+126.2	0.5		14	
10+128.0	2.5		15	
10+137.8	1.8		7	
10+137.9		1.0		17
10+143.3		1.3	9	
10+145.7		0.6	10	
10+148.6	0.1		6	
10+149.8	2.0			22
10+186.6	0.2			16
10+197.1	0.2		8	
10+204.5	1.6			24
10+207.9	1.5		7	
10+213.9	1.5		14	
10+214.9	2.1		8	
10+217.4	1.9			24
10+251.1		2.5	12	
10+266.7		2.5	8	
10+267.3		1.0	9	
10+270.6	1.6		7	
10+275.2	0.3		9	
10+279.3	2.0			28
10+321.7		4.1	7	
10+337.2	1.7			26
10+347.0		2.3	10	
10+350.9	2.9		11	
10+352.1	4.1		11	
10+352.4		0.5	13	
10+358.6		0.8	8	
10+358.7	0.1		11	
10+360.2	2.5		8	

LOCATION			6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
STATION	OFFSET			
	LT	RT		
10+367.8	0.5		7	
10+370.4	0.5		11	
10+372.6		0.1	6	
10+373.3		0.1	7	
10+378.2	0.8		8	
10+379.8	0.1		8	
10+388.7		0.6		33
10+395.7		1.1	13	
10+395.7		1.4	14	
10+395.8	0.1		8	
10+395.9	0.2		7	
10+396.5	2.2			24
10+396.6	2.2			30
10+397.8	0.1		7	
10+400.9		1.5	11	
10+401.1	2.5			20
10+404.8		2.3	7	
10+407.0	2.2		6	
10+407.7	0.8		14	
10+409.8	0.8		8	
10+414.9	0.2		7	
10+416.1	1.2		14	
10+417.7		0.4	7	
10+422.3	0.2		7	
10+425.9		0.3	7	
10+426.7		1.2	8	
10+427.0	0.2		8	
10+432.1	1.9			19
10+433.6	2.4		7	
10+434.7	1.5		7	
10+442.4	1.6		7	
10+444.0	0.7		8	
10+448.5	2.4		9	
10+457.3	0.2		12	
10+464.1	2.2		10	
10+539.9		2.7		31
10+551.5	2.8		12	

LOCATION			6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
STATION	OFFSET			
	LT	RT		
10+555.7		2.1	10	
10+556.1	0.5		11	
10+559.6	1.0		8	
10+562.3		1.3	8	
10+573.4	0.6		8	
10+575.5		0.6	6	
10+580.2		2.5	6	
10+580.8	1.9			30
10+584.8		1.9	10	
10+589.1	0.5		10	
10+590.3	1.6		7	
10+590.8		0.5	7	
10+591.1		1.2	9	
10+593.6	0.9		9	
10+607.3		0.7	8	
10+611.5	2.8		6	
10+614.9	2.8		9	
10+617.8		1.7		16
10+618.4	1.0			17
10+620.4		0.3	7	
10+621.3		2.4	7	
10+623.2	2.3		8	
10+624.2	1.3		6	
10+627.3	1.8		12	
10+627.5	1.1			16
10+631.1	0.2		7	
10+631.3	1.9			22
10+633.5		1.5	6	
10+635.0	1.4		9	
10+635.1		3.0	6	
10+636.5		1.9	12	
10+638.0	1.8		10	
10+639.4		1.8	13	
10+640.2		1.6	6	
10+642.7		2.1	7	
10+644.4		1.6	8	

LOCATION			6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
STATION	OFFSET			
	LT	RT		
10+647.4		2.3	7	
10+648.3		3.1	15	
10+649.5		3.2	7	
10+654.6		2.1	7	
10+656.1	3.0		7	
10+662.1	2.8		6	
10+666.9		2.9	9	
10+672.1	0.4		11	
10+681.6	1.2		7	
10+689.3	1.4			30
10+699.9	0.5		13	
10+702.2	0.0		6	
10+706.7		1.0	6	
10+706.7	0.5		7	
10+706.7	1.5			37
10+711.0		1.0	7	
10+725.4	2.7			22
10+734.9	2.8			28
10+749.5	4.1			31
10+762.4	1.6			33
10+777.9	0.8		7	
10+784.2	0.4		10	
10+785.8	1.8		13	
10+789.8				26
10+790.0	1.4		9	
10+791.1	0.7		7	
10+792.9		2.0	14	
10+793.0	0.6		10	
10+798.8		1.7	22	
10+805.8	2.2		10	
10+808.6		2.4		35
10+808.9	2.1		11	
10+814.3	0.3		7	
SUBTOTAL			996	794

LOCATION			6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
STATION	OFFSET			
	LT	RT		
VILLAGE OF ADDISON				
10+854.5	3.2		12	
10+881.1	0.9		6	
11+131.4	3.0		10	
11+133.3	2.6			18
11+336.0	1.7		6	
11+337.7	0.4		7	
11+338.9	2.9		6	
11+341.4		0.2	6	
SUBTOTAL			52	18

EARTHWORK SCHEDULE

LOCATION	SUITABLE EXCAVATION (EARTH EXCAVATION)	EARTH EX. ADJUSTED FOR SHRINKAGE (15%)	SUITABLE EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (FURNISHED EXCAVATION)	UNSUITABLE EXCAVATION (REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL)	UNSUITABLE EMBANKMENT	TOPSOIL FURNISH & PLACE 150MM	UNSUITABLE BALANCE WASTE (+) OR SHORTAGE (-)
	CU M	CU M	CU M	CU M	CU M	CU M	CU M	CU M
SIA. 9+278 TO 10+850	124	105	1909	-1804	2289	0	204	+1085
STA. 10+850 TO 11+523	89	76	1061	-985	1043	0	252	+791
STA. 11+523 TO 12+523	559	475	2495	-2020	2806	0	333	+1873
STA. 12+548 TO 14+447	1186	1008	2396	-1388	4434	0	321	+3113
STA. 15+800 TO 17+066	1969	1674	1692	-18	2647	0	683	+1964
TOTAL	3927	3338	9553	-6215	13219	0	4393	+8826

NOTE:

TREES WERE SURVEYED AND MEASURED IN 2004 AND THE INFO COLLECTED IS REFLECTED IN THE TREE REMOVAL SCHEDULE. HOWEVER, ADDITIONAL UNITS HAVE BEEN ALLOTTED TO COMPENSATE FOR TREE GROWTH BETWEEN 2004 AND 2009. THE ADDITIONAL QUANTITIES FOR TREE REMOVAL ARE REFLECTED IN THE SUMMARY OF QUANTITIES.

REVISIONS		
NO.	NAME	DATE

URS
100 S. WACKER DR., SUITE 500 TEL (312) 939-1000
CHICAGO, IL 60606 FAX (312) 939-4198

VILLAGE OF ADDISON
SALT CREEK GREENWAY TRAIL
TREE REMOVAL AND
EARTHWORK
SCHEDULE OF QUANTITIES

DATE: 02/13/2009
DESIGNED BY: MIA
DRAWN BY: MIA&VP
CHECKED BY: JDL